

4.0

**Public
Involvement
and Agency
Coordination**

4.0 PUBLIC INVOLVEMENT AND AGENCY COORDINATION

Throughout the development of this feasibility study, the District Division of Transportation (DDOT) has actively sought the input and contribution of citizens, community groups, and city agencies for the Klinge Road study. This community involvement has included public meetings, presentations to Advisory Neighborhood Commissions (ANC) and other groups, analyses of community input and agency coordination, and participation within the D.C. government.

In December 1999, the DDOT presented information at the Cleveland Park Public Library to members of the Cleveland Park Citizens Association and all other interested parties. On March 15, 2000, the DDOT hosted a public informational open house to provide information concerning the Klinge Road project to the public at-large. Letters were sent from the DDOT to community groups, ANCs, advocacy groups, and other individuals who had expressed interest in the project. Notice was provided in both citywide and local community newspapers. Over 200 people attended this event. All attendees were given the opportunity to complete a comment card and add their names to the project mailing list. More than 180 comment forms were returned over the following three months, including email comments from citizens sent to the DDOT. Comments and addresses were geocoded to illustrate the location of citizen responses with respect to the project area. Geocoding the mailing list clearly demonstrated the project effectively reached out to communities on both the east and west sides of Klinge Valley (Appendix B).

In September 2000, the DDOT presented information relating to the Klinge Road study to residents in the Mount Pleasant ANC and all other interested residents at the Mount Pleasant Public Library.

On November 30, 2000, the DDOT hosted a public meeting at its office. This meeting was intended to provide citizens with updated information concerning the study process. Citizens were invited to speak on the record

about the Klinge Road study. Similar to the March Public Meeting, attendees were given the opportunity to complete a comment card and add their name to the mailing list. Again, the comment letters as well as the names and addresses from the meeting sign-in sheet were geocoded to determine the effectiveness of the community outreach efforts. Petition signatures were not geocoded as many of them had incomplete addresses or no addresses at all. Approximately 200 names and addresses from the November Public Meeting were geocoded which resulted in a fairly even geographic distribution both east and west of the project study area (Appendix B).

Overall, based on comments received throughout the duration of this feasibility study, the results are almost split evenly. Approximately, half of the respondents, who completed comment cards or signed petitions, are in favor of closing Klinge Road permanently to traffic while the other half favor re-opening Klinge Road to vehicular traffic. Exact numbers are impossible to extract, given the multiple comments received from single individuals and organizations as well as citizens who signed more than one petition in favor of a particular option (Table 4-1).

The DDOT and its consultants have maintained a database and mailing list of over 500 names and addresses. All comments, responses, and emails from concerned individuals and community groups have been incorporated into the public involvement aspect of this feasibility study.

The DDOT also received several petitions from community groups, which were factored into community input. Careful consideration of the written comments and response of citizens helped define the scope of the project. Citizens who attended either the March 15 meeting or the November 30 meeting or sent comments, all received acknowledgement of their comments and were placed on the mailing list to receive notification of all future events concerning this project. DDOT has also received comments

and information from local ANC's, neighborhood citizen associations and several environmental organizations including the Earth Justice Legal Defense Fund, Sierra Club and the Audubon Naturalist Society.

Given the scope of the study, the DDOT has sought to coordinate with many local and federal agencies to facilitate the feasibility study process. Beginning in 1999, the DDOT and its consultants began coordination with the Federal Highway Administration and the National Park Service. The DDOT followed up with coordination letters to the D.C. Department of Health (including the Environmental Health Administration's Water Quality Division, Air Quality Division, Watershed Protection Division and the Fisheries and Wildlife Division), D.C. Department of Consumer and Regulatory Affairs, State Historic Preservation Office, Fish and Wildlife Service (U.S. Department of the Interior), and the National Capital Planning Commission. Also, representatives from utility companies and community services in the study area were consulted regarding how the proposed feasibility study might affect services to residents and businesses in the area.

The DDOT has made every effort to keep the community as a whole informed and involved during the process of this feasibility study.

Table 4-1: Summary of Citizen Input

	Open Klinge Road to Vehicular Traffic	Close Klinge Road to Vehicular Traffic
Individual Comments	178	242
Petition Signatures	---	---
Harvard Street, N.W. Association	20	---
Students/Faculty of Washington International School	---	**25
Woodley Park Towers	---	62
"Save Klinge Valley"-email response form	---	19
"Klinge Valley-Save it Don't Pave It" form letter	---	26
Citizens Petition for the Reopening of Klinge Road	*1,500	---
Klinge Valley Park Association-1994	---	1,176

* 1,500 is an estimate.

** This petition had signatures of both adults and young children, approximately 50 children signed. Signatures of children are, in general, difficult to include in petitions, given the difficulty in verification and children's understanding of the project and the petition concept.

5.0

List of Agencies and Persons Consulted

5.0 LIST OF AGENCIES AND PERSONS CONSULTED

Sgt. Yolander Alexander
D.C. Police Department
4th District Headquarters
6001 Georgia Avenue, NW
Washington, D.C. 20011

Jerusalem Bekele
D.C. Department of Health
Water Quality Division
51 N Street, NE
Washington, D.C. 20001

Herb Bixhorn
Chief, State Data Center
District of Columbia
801 North Capitol Street, NE
Washington, D.C. 20002

Bernie Bloom
D.C. Department of Health
Air Quality Division
51 N Street, NE
Washington, D.C. 20001

Lt. John Briscoe
D.C. Fire and Emergency Medical Service
5th Battalion
1763 Lanier Place, NW
Washington, D.C. 20010

Adrienne Coleman
National Park Service
Rock Creek Park
3545 Williamsburg Lane, NW
Washington, D.C. 20008

R.R. Dash
Counsellor & Head of Chancery
Embassy of India
2107 Massachusetts Avenue, NW
Washington, D.C. 20008

Ray Dodd
Verizon
Relocations Office
3901 Calverton Boulevard
Beltsville, MD 20705

Mike Dorsey
D.C. Bureau of Traffic
65 K Street, NE
Washington, D.C. 20002

Roberto Duke
D.C. Office of Planning
801 North Capitol Street, NE
4th Floor
Washington, D.C. 20002

Paulette Grady
D.C. Office of Planning
801 North Capitol Street, NE
Washington, D.C. 20002

Michael Harrison
WMATA
Office of Renovations
600 5th Street, NW
Washington, D.C. 20001

Purnell Jackson
District Cable Vision
900 Michigan Avenue, NE
Washington, D.C. 20002

Charles Johnson
Water and Sewer Authority
Maps and Records
5000 Overlook Drive
Washington, D.C. 20032

Lt. Christopher Jordan
D.C. Fire and Emergency Medical Service
4th Battalion
3420 14th Street, NW
Washington, D.C. 20010

Lloyd J. Jordan
D.C. Department of Consumer and Regulatory
Affairs
941 North Capitol Street, NE, Suite 9500
Washington, D.C. 20002

Hamid Karimi
D.C. Department of Health
Erosion Control
51 N Street, NE
Washington, D.C. 20001

Don Kooney
D.C. Department of Public Works
2000 14th Street, NW
Washington, D.C. 20009

Peter May
D.C. Department of Health
Watershed Protection Division
51 N Street, NE
Washington, D.C. 20001

Frank Mirak
Federal Highway Administration
820 1st Street, NE
Washington, D.C. 20002

Ira Palmer
D.C. Department of Health
Fisheries and Wildlife Division
51 N Street, NE
Washington, D.C. 20001

George Papadopolous
Water and Sewer Authority
5000 Overlook Drive
Washington, D.C. 20032

Robert J. Pennington
U.S. Fish and Wildlife Service
Chesapeake Bay Field Office
177 Admiral Cochrane Drive
Annapolis, MD 21401

Lt. Roger Roch
D.C. Police Department
2nd District Headquarters
3320 Idaho Avenue, NW
Washington, D.C. 20016

Douglas Ryan
Washington Gas
Workload Distribution
6801 Industrial Road
Springfield, VA 22151

Jim Shebelski
Water and Sewer Authority
Design Branch Manager
5000 Overlook Drive
Washington, D.C. 20032

Bill Sigafoose
PEPCO
1900 Pennsylvania Avenue, NW
Washington, D.C. 20006

Jim Slaten
PEPCO
Supervisor of Engineering Liaison
3400 Benning Road, NE
Building 59, Room 200B
Washington, D.C. 20019

Lt. Herby Sprow
D.C. Fire and Emergency Medical Service
5th Battalion
3522 Connecticut Avenue, NW
Washington, D.C. 20008

6.0

References

6.0 REFERENCES

- Banta, W.C. 1993. *Biological Water Quality of the Surface Tributary Streams of the District of Columbia*. The American University, Washington, D.C.
- Boschke, A. 1861. *Topographic Map of the District of Columbia, Surveyed in the Years 1856-59*. Copy on file at Rock Creek Park, National Park Service, Washington, D.C.
- Bushong, William. 1990a. *Rock Creek Park Historic District*. National Register of Historic Places Nomination Form. On file at Rock Creek Park, National Park Service, Washington, D.C.
- Bushong, William. 1990b. *Historic Resource Study: Rock Creek Park, District of Columbia*. On file at Rock Creek Park, National Park Service, Washington, D.C.
- Center of Watershed Protection (CWP). 1997. *The District of Columbia Wetland Conservation Plan*. Prepared for the District of Columbia Department of Consumer and Regulatory Affairs. Silver Spring, MD. August, 1997.
- Coast and Geodetic Survey, 1892; District of Columbia, Sheet #33. Engraved by Evans and Bartle, Washington D.C., 1893.
- Columbia Heights Neighborhood Groups. 2000. Information pertaining to activities, events, and businesses in the Columbia Heights Neighborhood. Available: <http://innercity.org/columbiaheights/>.
- Comprehensive Plan Publications. 1995. *District of Columbia Generalized Land Use Map*, District of Columbia.
- District of Columbia Public Library. 2000. D.C. Office of Planning/State Data Center, website visited on June 27, 2000, <http://www.dclibrary.org/sdc.html>
- Environmental Data Resources, Inc. *EDR Radius Map (1.5 Miles) with GeoCheck*, 2000.
- Federal Emergency Management Agency (FEMA). 1998. National Flood Insurance Program: Q3 Flood Data, Washington, D.C.
- Federal Highway Administration, Office of Environmental Policy, Noise and Air Division. 1986. *Appropriate Levels of Highway Air Quality Analysis for a CE, EA/FONSI, and EIS*. March 1986.
- Historic Preservation Division. 1995. *District of Columbia Inventory of Historic Sites: 1995 Edition*. Historic Preservation Division, D.C. Department of Consumer and Regulatory Affairs.
- Holmes, William H. 1897. *Stone Implements of the Potomac-Chesapeake Tidewater Province*. Annual Report 15. Bureau of American Ethnology, Washington, D.C.
- Inashima, Paul. 1985. *Archeological Survey Report: An Archeological Investigation of Thirty-One Erosion Control and Bank Stabilization Sites Along Rock Creek and Its Tributaries*. U.S. Department of the Interior, National Park Service, Denver Service Center, Seneca, Maryland.
- Johnson, B. 1988. *1988 Rapid Bioassessment of Streams in the District of Columbia*. District of Columbia Department of Consumer and Regulatory Affairs Housing and Regulatory Administration Environmental Control Division, Water Hygiene Branch, Washington, D.C.

Metropolitan Washington Council of Governments. 2000. Information pertaining to air quality trends in the Washington region. Available: www.mwcog.org.

Metropolitan Washington Air Quality Committee. 1999. *Air Quality Trends in the Washington Metropolitan Area: 1985-1999*.

Michler, N. 1867. *Topographic Sketch Map of the Environs of Washington, D.C.* Copy on file at Rock Creek Park, National Park Service, Washington, D.C.

Munford, Barbara. 1982. *The Piney Branch Quarry Site: An Analysis of a Lithic Workshop in Washington, D.C.* M.A. thesis, Department of Anthropology, The George Washington University.

National Capital Planning Commission (NCPC). 1995. *District of Columbia Aerial Images*, Tiled 0.2 Meter Resolution. Washington, D.C.

Potter, Stephen. n.d. *Piney Branch Quarry Site*. National Register of Historic Places Nomination Form. On file at the Historic Preservation Division, District of Columbia Department of Consumer and Regulatory Affairs.

R.S. Means. 2001. *Building Construction Cost Data, 59th Annual Edition, 2001*. Kingston, MA.

Ryan, D. 2000. *Fisheries Assessment of Klinge Branch in Rock Creek*. District of Columbia, Department of Health, Environmental Health Administration, Washington, D.C.

United States Coast and Geodetic Survey. 1892. *Topographic Map of the District of Columbia*. Copy on file at Rock Creek Park, National Park Service, Washington, D.C.

United States Department of Agriculture. 1976. *Soil Survey of the District of Columbia*. United States Department of Agriculture, Soil Conservation Service (Natural Resources Conservation Service). Washington, D.C.

United States Fish and Wildlife Service. 1998. *National Wetland Inventory Map*, Washington West, District of Columbia, Maryland and Virginia.

United States Geological Survey. 1994. *Geological Map of the Washington West Quadrangle*, District of Columbia, Montgomery and Prince Georges Counties, Maryland, and Arlington and Fairfax Counties Virginia. U.S. Department of the Interior, U.S. Geological Survey.

United States Geological Survey (photorevised 1983). *7.5 Minute Series Topographic Quadrangle for Washington West, District of Columbia, Maryland and Virginia*.

United States Census Bureau. 1990. *U.S. Demographic Information*. Available: <http://www.census.gov>

United States Department of the Interior, National Park Service. *Rock Creek Watershed Conservation Study*, 1979.

Washington, D.C. Government. 2000. *Advisory Neighborhood Commission Information*. Available: <http://anc.dcgov.org>.

Wheelock, Perry. 1993. *Cultural Landscape Report: Pierce-Klinge Mansion, Rock Creek Park*. On file at Rock Creek Park, National Park Service, Washington, D.C.

Zoning Commission for the District of Columbia. 1996. *Zoning Map of the District of Columbia*, Washington, D.C.

7.0

**List of
Preparers**

7.0 LIST OF PREPARERS

Government of the District of Columbia
District Division of Transportation
Transportation Policy and Planning Administration
2000 14th Street, NW
Washington, DC 20009

Ken Laden
Associate Director for Transportation Planning
Transportation Policy and Planning Administration
District Division of Transportation

Maurice Keys
Environmental Program Coordinator
Transportation Policy and Planning Administration
District Division of Transportation

The Louis Berger Group, Inc.
1819 H Street, NW
Suite 900
Washington, DC 20006

Jess Commerford, AICP - Project Manager
B.G.S., University of Kansas, 1987
M.U.R.P., University of Kansas, 1990

Dana Otto, AICP- Environmental Scientist
B.S., Florida State University, 1993
M.U.R.P., Florida State University, 1997

Dan Tangherlini
Acting Director
District Division of Transportation

Shannon Cauley, USACECWD, CPSS - Senior Ecologist
B.S., Ricker College, 1976
Graduate Studies, University of Maryland, 1986

Andy Paluri, P.E. -Transportation Engineer
B.E., Andhra University, 1984
M.S., Clarkson University, 1987

Charlie Leedecker- Archeologist, Historic Preservation Specialist
B.A., Cornell University, 1970
M.A., The George Washington University, 1978

Raed El-Farhan – Water Resources Engineer
B.S., University of Missouri-Rolla, 1986
M.S., Clemson University, 1990
Ph.D., Clemson University, 1997

Todd Taylor- Environmental Analyst
B.S., Frostburg State University, 2000

Michael J. Schuster, AICP - Planner
B.A., University of Maryland, 1997
M.C.P., University of Maryland, 1999

Melissa Bird, AICP - Planner
B.A., University of North Carolina-Charlotte, 1995
M.C.P., University of Maryland, 1998

Ariel A. Cuschnir – Senior Environmental Scientist
B.S., Tel Aviv University, 1979
M.S., Tel Aviv University, 1982
Ph.D., Tel Aviv University, 1991

8.0

Acronyms

8.0 ACRONYMS

ANC	Advisory Neighborhood Commission	ESRI	Environmental Research System Institute, Inc.
APE	Area of Potential Effect	EO	Executive Order
ASTM	American Society for Testing and Materials	ERNS	Emergency Response Notification System
ATSDR	Agency for Toxic Substances and Disease Registry	FHWA	Federal Highway Administration
BMP	Best Management Practice	HRS	Hazard Routing System
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act	LUST	Leaking Underground Storage Tank
CERCLIS	Comprehensive Environmental Response, Compensation, and Liability Information System	msl	mean sea level
CFR	Code of Federal Regulations	NCPC	National Capital Planning Commission
cfs	cubic feet per second	NO _x	Nitrogen Oxides
CO	Carbon Monoxide	NPS	National Park Service
COD	Carbon Oxygen Demand	NRHP	National Register of Historic Places
DCMR	District of Columbia Municipal Regulations	NWI	National Wetland Inventory
dbh	diameter breast height	PEPCO	Potomac Electric Power Company
DPW	D.C. Department of Public Works	PM ₁₀	Particulate Matter
DCRA	Department of Consumer and Regulatory Affairs	PSA	Patrol Service Area
DCWCP	D.C. Wetland Conservation Plan	RCRA	Resource Conservation and Recovery Act
DDOT	District Division of Transportation	RCRIS	Resource Conservation and Recovery Information System
EDR	Environmental Data Resources, Inc.	ROW	Right of Way
ESA	Endangered Species Act	SHPO	State Historic Preservation Office
EPA	Environmental Protection Agency	USGS	United States Geological Survey
		USDA	United States Department of Agriculture
		USFWS	United States Fish and Wildlife Service

USTs	Underground Storage Tanks
WMATA	Washington Metropolitan Transit Authority
WASA	Water and Sewer Authority

Appendix A: Agency Coordination



801 Pennsylvania Avenue, NW
Suite 301
Washington, DC 20576
tel 202 482-7200
fax 202 482-7272
www.ncpc.gov

Mr. Maurice Keys
Page 2

Your project information indicates that preliminary discussions with the National Park Service have taken place in the context of non-vehicular use of the right-of-way. The Commission staff reaffirms that position relative to the federal interest in Rock Creek Park, and the project's potential effects on this important resource.

Rock Creek Park is a 1,754-acre urban forest in the District of Columbia. It is the oldest, largest natural urban park in the National Park System and is significant for its exceptional scenic beauty. Its natural forested landscapes stands in contrast to the surrounding cityscape of the District of Columbia. The park mission to preserve and perpetuate the ecological resources of Rock Creek valley in as natural a condition as possible, and to preserve its scenic value for the enjoyment of the public, is grounded in the park's 1890 enabling legislation which established Rock Creek Park for the purpose of providing a "...public park or pleasure ground for the benefit and enjoyment of the people of the United States."

The Commission staff wishes to support the concerns of the National Park Service relative to potential impacts to the park. Rock Creek Park is made up of steep side slopes that bisect several significant east-west trending ridgelines. The park descends along the piedmont fall-line through numerous small rapids and drainage ways along the creek and its sideslope watershed. Floodplain development in the park is fairly restrictive, limited primarily to Rock Creek itself. Most sections of the park are accessible either by automobile or by hiking. Many portions of the park are accessible by walking, usually under one mile. Gradients above the floodplain are surprisingly steep, and provide moderate hiking opportunities.

We want to emphasize that the lands currently being considered in the transportation corridor alternatives will potentially affect Rock Creek Park. Rock Creek Park environs should be considered a unique and significant environmental resource. While the park is the largest existing area of natural terrestrial vegetation in the District, this federal and community resource is being increasingly stressed and degraded. All eastern tributaries of Rock Creek have been paved over in past years. Rock Creek has water quality problems relating to over 200 outfalls into the stream. Uncontrolled runoff and larger volumes of flow, due to reduced infiltration and increased piping of runoff, have scoured Rock Creek instream habitat. The stream also has been evaluated as having poor benthic macroinvertebrate communities indicative of habitat degradation due to urban pollution.

IN REPLY REFER TO:
NCPC File No. 5822

APR - 3 2000

Mr. Maurice Keys
Office of Intermodal Planning
District of Columbia Department of Public Works
Attention: Klinge Road Environmental Assessment
2000 14th Street, NW
Washington, DC 20009

Dear Mr. Keys:

Thank you for the opportunity to comment on the scoping for the proposed Environmental Assessment (EA) for the Klinge Road project, located adjacent to Rock Creek Park in northwest Washington, DC. The EA is being prepared on the currently closed portion of Klinge Road to evaluate alternatives for future use of the right-of-way. These scoping comments are limited to the Commission's role as the central planning agency for the federal government in the National Capital Region and express our general views on planning and environmental issues.

As noted in the provided project materials, preliminary project alternatives include:

- A no action alternative.
- Rebuilding Klinge Road to its original alignment and dimensions.
- Reconfiguring Klinge Road within the existing right-of way.
- No development of a roadway, but addressing drainage issues only.
- Converting the roadway to a bike/recreation corridor.

Commission Members

Appointed by the

President of the United States
Harvey S. Gold, Chairman
Robert A. Galois
Margaret C. Vanderby

Appointed by the Mayor of the
District of Columbia
Arlington Diaz
John E. Howard

Appointed by the Secretary of the Interior
Honorable Bruce Babbitt

Appointed by the Secretary of Defense
Honorable David J. Barnard

Appointed by the Secretary of the Interior
Honorable Bruce Babbitt

Chairman, Committee on
Governmental Affairs
United States Senate
Honorable Fred Thompson

Chairman, Committee on
Government Reform
U.S. House of Representatives
The Honorable Dan Burton

Mayor, District of Columbia
Honorable Anthony A. Williams

Chairman, Council of the
District of Columbia
Honorable Linda W. Cropp

Executive Director
W. Griffith

Mr. Maurice Keys


Page 3

The Commission staff believes the Klinge Road alignment area presents a unique opportunity to offset urbanization impacts that are increasingly affecting the basic ecosystem of the park. Rock Creek Park holds the promise of important restoration of anadromous fish, if aquatic habitat and improved water quality are achieved. Moreover, improved water quality and streamside environment at this point in the drainage system translates to enhanced conditions for all downstream environments including the Potomac River. A chance to upgrade the biodiversity and ecological functions of this drainage reach is available with your planned activity.

We strongly request that assessment of land area be directed toward limited impervious pavement areas within the alignment and that the most compatible form of access, if necessary, be determined in association with the National Park Service.

We appreciate your consideration of our comments at this stage of the project planning. The Commission anticipates your successful completion of the EA and looks forward to the review of the EA information, when available. Please place the Commission on the distribution list pertaining to all project planning. If you have technical questions concerning the information related in this letter, you may contact Mr. Eugene Keller, in the Office of Plans Review, at (202) 482-7251.

Sincerely,


William R. Lawson, FAIA
Acting Executive Director



THE LOUIS BERGER GROUP, INC.

1819 H Street, NW, Suite 800, Washington, DC 20006

Phone: 202.331.7775 Fax 202.293.8224

FAXTRANSMIT

To: Naresh Sood, Embassy of India	From: Kammy Horne
Project Number/Description: Kling Road	RE: Kling Road/Property
Date: April 21, 2000	
Facsimile Number: <u>202-319-2840</u>	
Pages (Including Cover): 2	

Mr. Sood,


We spoke on Wednesday concerning the property that is owned by the Embassy of India (2700 Macomb NW) that borders Kling Road. The Louis Berger Group is contracted by the DC Department of Public Works to do an environmental study on the closed portion of this road. It appears that your property access is from Macomb Street, NW, however I want to be sure that you do not require access from Kling Road.

I have attached a map that shows the property bounded by Macomb, Porter, and Kling Road. Please let me know if the Embassy has an access point from Kling Road.

I hope that you can read the attached map—I will try to phone you on Monday (4/24) to discuss this (or you can phone me at your convenience).

Thank you for your assistance. We will continue to keep the Embassy of India informed of meetings regarding this study.

Kammy Horne
(202) 331-7775 ext. 476



R. R. DASH
Counsellor &
Head of Chancery



EMBASSY OF INDIA
2107 Massachusetts
Avenue, NW
Washington, DC 20008
Tel: (202) 939-7020
Fax: (202) 265-4351

WAS/PROP/MISC/4/00

April 26, 2000

Dear Ms. Horne

Please refer to you fax message dated April 21, 2000 addressed to Mr. Sood regarding the Embassy-owned property at 2700 Macomb Street. While, our access to our property presently is from Macomb Street, we would very much like to keep our options open for access from Klinge Road.

2. We would appreciate it if you could keep us informed of any developments in this regard.

Yours sincerely

A handwritten signature in black ink, appearing to be 'R. R. Dash', written over the typed name.

(R. R. DASH)

Ms. Kammy Horne
Environmental Planner
The Louis Berger Group, Inc.
1819 H Street, NW
Suite 900
Washington, DC 20006

rec'd OIP76-00

GOVERNMENT OF THE DISTRICT OF COLUMBIA
Department of Consumer and Regulatory Affairs

Office of the Director



June 28, 2000

Mr. Kenneth G. Laden
Administrator for Office of Intermodal Planning
Department of Public Works
2000 14th Street, N.W. 7th Floor
Washington, DC 20009


Dear Mr. Laden:

This letter is to acknowledge your letter dated June 19, 2000, regarding the reopening of Kingle Rd. Please be advised that the matter has been referred to Armando Lourenco, Administrator for Building Land Regulation Administration.

you should receive a response from Mr. Lourenco within five (5) business days from the date of this letter. If you have not received a response from Mr. Lourenco by July 6, 2000, please feel free to contact Ms. Regina Dobbins at (202) 442-8941 for further assistance.

Thank you for bringing this matter to my attention. It is my hope that through cooperative efforts between citizens and the Department, to address issues such as yours, we can help transform the District of Columbia into the model-city of excellence it was designed to be.

Sincerely,



Lloyd J. Jordan
Director

Correspondence Ticket No. 3309



United States Department of the Interior

FISH AND WILDLIFE SERVICE
Chesapeake Bay Field Office
177 Admiral Cochrane Drive
Annapolis, MD 21401



July 19, 2000

Mr. Ken Laden
Administrator
Office of Intermodel Planning
Department of Public Works, D.C.
2000 14th Street, N.W., Seventh Floor
Washington, D.C. 20009

RE: Proposed Reopening of Klinge Road
Environmental Assessment
Rock Creek Park, District of Columbia

Dear Mr. Laden:

This responds to your June 19, 2000, request for information on the presence of species which are federally listed or proposed for listing as endangered or threatened in the above referenced project area. We have reviewed the information you enclosed and are providing comments in accordance with Section 7 of the Endangered Species Act (87 Stat. 884, as amended; 16 U.S.C. 1531 *et seq.*).

Except for occasional transient individuals, no proposed or federally listed endangered or threatened species are known to exist within the project impact area. Therefore, no Biological Assessment or further Section 7 consultation with the U.S. Fish and Wildlife Service is required. Should project plans change, or should additional information on the distribution of listed or proposed species become available, this determination may be reconsidered.

This response relates only to federally protected threatened or endangered species under our jurisdiction. Limited information is currently available regarding the distribution of other rare species in the District of Columbia. However, the Nature Conservancy and National Park Service (NPS) have initiated an inventory of rare species within the District. For further information on such rare species, you should contact Ellen Gray of the DC Natural Heritage Program at (202) 342-1443 ext. 223.

An additional concern of the Service is wetlands protection. Federal and state partners of the Chesapeake Bay Program have adopted an interim goal of no overall net loss of the Basin's remaining wetlands, and the long term goal of increasing the quality and quantity of the Basin's wetlands resource base. Because of this policy and the functions and values wetlands perform, the Service recommends avoiding wetland impacts. All wetlands within the project area should be

identified, and if alterations of wetlands proposed, the U.S. Army Corps of Engineers, Baltimore District, should be contacted for permit requirements. They can be reached at (410) 962-3670.

We appreciate the opportunity to provide information relative to fish and wildlife issues, and thank you for your interests in these resources. If you have any questions or need further assistance, please contact Andy Moser at (410) 573-4537.

Sincerely,

Robert J. Pennington
Assistant Field Supervisor
Chesapeake Bay Field Office

GOVERNMENT OF THE DISTRICT OF COLUMBIA
DEPARTMENT OF CONSUMER AND REGULATORY AFFAIRS
BUILDING AND LAND REGULATION ADMINISTRATION



July 31, 2000

Mr. Ken Laden
Administrator
Office of Intermodal Planning
Department of Public Works, D.C.
2000 14th St., N.W., Seventh Floor
Washington, D. C. 20009

Dear Mr. Laden:

We have received your letter addressed to Mr. Gregory McCarthy, SHPO regarding the Klinge Road project. Our primary concerns are: the impact that this project will have on landmark or National Register properties within the "area of potential effect"; and on archaeological resources that would be disturbed or destroyed by construction, installation of storm drainage systems, removal and replacement of asphalt, and those places to be used as staging areas for the project.

If you would like to discuss any of these issues please feel free to contact Nancy Kassner of my staff at (202) 442 - 4663.

Sincerely,

A handwritten signature in black ink, appearing to read "Stephen Raiche".

Stephen Raiche
Chief, Historic Preservation Division

GOVERNMENT OF THE DISTRICT OF COLUMBIA
Department of Health

Office of the Senior Deputy Director
for Public Health Assurance



MEMORANDUM

TO: Ken Laden, Administrator
Office of Intermodal Planning
Department of Public Works

FROM: Theodore J. Gordon
Senior Deputy Director for Public Health Assurance

DATE: August 7, 2000

SUBJECT: Klingle Road

The program managers of the Bureau of Environmental Quality have been meeting with your staff and contractor since May 31, 2000. We initiated the series of meetings, because of our concern that we had not been contacted and we possess a significant amount of data and environmental information on Klingle Road.

We appreciate the time and attention your staff and consultants have spent with our staff and believe that there is a need to maintain closer communications in order to have an accurate assessment of the environment. There are a few concerns that bear to be restated, even though I am sure your staff has kept you informed.

Water Quality Division - Jerusalem Bekele

The Water Quality Standards, 21 DCMR, Section 1102.5 designate "Rock Creek and its tributaries" as "Special Waters of the District of Columbia." The requirements of Section 1102.4 are for the application of BMPs, maintenance of water quality at or above existing conditions and no long term adverse water quality effects. There are wetlands involved and DPW has not complied with previous agreements on wetland mitigation.

Air Quality Division - Donald Wambsgans

The impact of increased traffic resulting from the reopening of Klingle Road should be evaluated using the Air Quality Division's protocol for air quality analysis. The initial meeting with Mr. Keyes and the DPW contractor, Mr. Berger, was inconclusive and subsequent efforts to meet again have not been successful.

Klingle Road
August 7, 2000
Page 2

Watershed Protection Division - Hamid Karimi

There is severe bank erosion. Storm water BMPs will need to be specially designed in accordance with the requirements of 21 DCMR Section 1104.

Due to difficulties in scheduling a meeting, information was transmitted by letter to the consultant.

Fisheries and Wildlife Division - Ira Palmer

Any transportation related impediments to fish movement, need to be avoided.

Your principal point of contact is James R. Collier, Chief of the Bureau of Environmental Quality.

C: Norman S. Dong, Deputy Mayor for Operations
Jim Wareck, Deputy Director, Federal & Congressional Affairs
Leslie Hotelling, Acting Interim Director

GOVERNMENT OF THE DISTRICT OF COLUMBIA
DEPARTMENT OF PUBLIC WORKS



OFFICE OF INTERMODAL PLANNING

AUG 11 2000

Ms. Adrienne A. Coleman
Superintendent
Nation Park Service
National Capital Region
Rock Creek Park
3545 Williamsburg Lane, N.W.
Washington, D.C. 20008-1207

Dear Ms. Coleman:

As you know the Department of Public Works, District Division of Transportation is conducting an environmental assessment of Klinge Road between Woodley Road and Porter Street, N.W. We request your assistance in locating any traffic data or studies that have been collected or performed by the National Park Service in this general area. In addition, please inform us of the status of the Draft General Management Plan and Environmental Impact Statement and whether the draft is available for review.

Should you have any questions, please contact me or Maurice Keys at (202) 671-2740.

Sincerely,

A handwritten signature in dark ink, appearing to read "KG Laden".

Kenneth G. Laden
Administrator



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

October 11, 2000

Dr. Ellen Gray
National Park Service
4598 McArthur Boulevard, NW
Washington, DC 20007

Re: Proposed Reopening of Kingle Road Environmental Assessment
Rock Creek Park, District of Columbia

Dear Dr. Gray:

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of Kingle Road, located in Northwest Washington, DC. As shown on the attached copy of the USGS topographic map for the Washington West, DC-MD-VA Quadrangle, the EA is being prepared for the portion of Kingle Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ◆ The No Action Alternative
- ◆ Rebuild Kingle Road to its original alignment and dimensions and repair/replace storm drainage
- ◆ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ◆ Bike recreation/facility management (conversion of the closed portion of Kingle Road to a bike path with appropriate resurfacing)
- ◆ Green Space Alternative (removal of asphalt on Kingle Road to allow the area to return to natural condition)



THE Louis Berger Group, INC.


1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

With the exception of the No Action Alternative that must be considered under NEPA, all of the alternatives will correct existing drainage related damage and deficiencies in the Kingle Valley watershed.

The purpose of this correspondence is to formally request the current list of special status species that are known to occur, or that could potentially occur on, or in the vicinity of the Kingle Valley site. We would also like to know if there are any other sensitive natural resources or ecosystems that should be considered in the environmental analysis.

If you have any questions or need additional information, please contact Shannon Cauley at 202-331-7775, ext. 474, or by e-mail at scauley@louisberger.com. Thank you in advance for your assistance.

Sincerely,
The Louis Berger Group, Inc.


Shannon R. Cauley
Senior Ecologist

cc: Mr. Maurice Keys, DCDPW
Mr. Jess Commerford, Director, The Louis Berger Group, Inc.



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

October 12, 2000

Sergeant Yolander Alexander
Fourth District Headquarters
6001 Georgia Avenue, NW
Washington, D.C. 20011

Dear Sergeant Alexander:

The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of the Fourth District's needs and concerns as they relate to this project and project alternatives.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ◆ The No Action Alternative
- ◆ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ◆ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ◆ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ◆ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



Information Request

We are aware that these alternatives may potentially impact the Fourth District's ability to provide service in the area. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- Fourth District's review of this project information.
- The effect of the road closure on providing service in the area.
- Concerns, if any, about crime in the closed portion of the road.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Sergeant Alexander, thank you for your attention to this matter, we look forward to receiving your information on behalf of the Fourth District.

Sincerely,
The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com



Information Request

We are aware that these alternatives may potentially impact the Second District's ability to provide service in the area. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- Second District's review of this project information.
- The effect of the road closure on providing service in the area.
- Concerns, if any, about crime in the closed portion of the road.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Lt. Roch, thank you for your attention to this matter, we look forward to receiving your information on behalf of the Second District.

Sincerely,
The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group

October 12, 2000

Lt. Roger Roch
Second District Headquarters
3320 Idaho Avenue, NW
Washington, D.C. 20016

Dear Lt. Roch:

The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of the Second District's needs and concerns as they relate to this project and project alternatives.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com



Information Request

We are aware that these alternatives may potentially impact the 5th Battalions ability to provide service in the area. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- 5th Battalion's review of this project information.
- The effect of the road closure on providing service in the area.
- Concerns, if any, about fire or safety hazards in the closed portion of the road.
- Needs, if any for an access road to areas in the closed portion of the roadway.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Lt. Briscoe, thank you for your attention to this matter, we look forward to receiving your information on behalf of the 5th Battalion.

Sincerely,

The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group

October 12, 2000

Lt. John Briscoe
5th Battalion
1763 Lanier Place
Washington, D.C. 20010

Dear Lt. Briscoe:

The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Kingle Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of the 5th Battalion's needs and concerns as they relate to this project and project alternatives.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Kingle Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Kingle Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Kingle Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Kingle Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Kingle Road to its original alignment and dimensions and repair/replace storm drainage



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com



Information Request

We are aware that these alternatives may potentially impact the 4th Battalions ability to provide service in the area. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- 4th Battalion's review of this project information.
- The effect of the road closure on providing service in the area.
- Concerns, if any, about fire or safety hazards in the closed portion of the roadway.
- Need, if any, for an access road to areas in the closed portion of the roadway.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Lt. Jordan, thank you for your attention to this matter, we look forward to receiving your information on behalf of the 4th Battalion.

Sincerely,
The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group

October 12, 2000

Lt. Christopher Jordan
4th Battalion
3420 14th Street, NW
Washington, D.C. 20010

Dear Lt. Jordan:

The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of the 4th Battalion's needs and concerns as they relate to this project and project alternatives.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

October 17, 2000

Jim Shebelski
Water and Sewer Authority
Design Branch Manager
5000 Overlook Drive
Washington D.C. 20032

Dear Mr. Shebelski:

This is a follow-up to the letter sent to you on October 12th. The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of Water and Sewer Authority's needs and concerns as they relate to this project and project alternatives. Attached to this letter is a detailed topography map with the project area identified.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- The No Action Alternative
- No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



Information Request

We are aware that these alternatives may potentially impact relating to WASA's ability to provide service in the area. On behalf of DCDPW, Louis Berger is requesting written verification of the following information from your office:

- WASA's review of this project information.
- The presence of active water and sewer lines along the closed portion of the road.
- WASA's need for access to the closed portion of Klinge Road for service and maintenance purposes.
- WASA's needs, if any, for an access road to the closed portion of the existing road, if necessary, the width and surface type.
- The types of vehicles/equipment needed, if any.
- The amount of ground coverage required for lines.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by October 27, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Mr. Shebelski, thank you for your attention to this matter, we look forward to receiving your information on behalf of WASA.

Sincerely,

The Louis Berger Group, Inc.

Jess Commerford

Jess Commerford, AICP
Director, Planning and Environmental Services

Enclosure as cited

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com
October 17, 2000

Douglas Ryan
Washington Gas
Workload Distribution
6801 Industrial Road
Springfield, VA 22151

Dear Mr. Ryan:

This is a follow-up to the letter sent to you on October 12th. The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of Washington Gas's needs and concerns as they relate to this project and project alternatives. Attached to this letter is a detailed topography map with the project area identified.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



Information Request

We are aware that these alternatives may potentially impact Washington Gas's ability to provide gas service in the area or maintain infrastructure. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- Washington Gas's review of this project information.
- The presence of active and inactive gas lines in the Connecticut Avenue Bridge.
- The presence of active and inactive gas lines along or underneath the closed portion of Klinge Road.
- The effect road bed removal would have on gas lines.
- Washington Gas's need, if any, for an access road to the closed portion of the existing road, if necessary, the width and surface type.
- The types of vehicles/equipment needed, if any.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Mr. Ryan, thank you for your attention to this matter, we look forward to receiving your information on behalf of Washington Gas.

Sincerely,

The Louis Berger Group, Inc.

Jess Commerford

Jess Commerford, AICP
Director, Planning and Environmental Services

Enclosure as cited

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group



THE Louis Berger Group, INC.

1819 H Street, NW, Suite 900, Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

October 17, 2000

Jim Slayton
Potomac Electric Power Company
Engineering Liaison
3400 Benning Road, NE
Bldg. 59, Room 200-B
Washington, D.C. 20019

Dear Mr. Slayton:

This is a follow-up to the letter sent to you on October 12th. The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of Potomac Electric Power Company's needs and concerns as they relate to this project and project alternatives. Attached to this letter is a detailed topography map with the project area identified.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



Information Request

We are aware that these alternatives may potentially impact PEPCO'S ability to provide service in the area or maintain infrastructure in the area. On behalf of DCDPW, Berger is requesting written verification of the following information from your office:

- PEPCO's review of this project information.
- The presence of existing (active) power lines on the closed portion of Klinge Road.
- The presence of existing (active) power lines in the Connecticut Avenue Bridge.
- The presence of conduits/power stations on the closed portion of Klinge Road.
- PEPCO's need for access, if any, to the closed portion of Klinge Road for service purposes.
- Number of times PEPCO needs to access this area for scheduled maintenance, if any.
- The types of vehicles/equipment needed, if any.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by November 3, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Mr. Slayton, thank you for your attention to this matter, we look forward to receiving your information on behalf of PEPCO.

Sincerely,

The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

Enclosure as cited

CC: Maurice Keys, DCDPW
Larry D. Walker, The Louis Berger Group



THE Louis Berger Group, INC.

1819 H Street, N.W. Suite 900 Washington, DC 20006 USA
Tel 202 331 7775 Fax 202 293 0787 Email answers@louisberger.com www.louisberger.com

October 17, 2000

Michael Harrison
Washington Metropolitan Transit Authority
Office of Renovations
600 5th Street, N.W.
Washington D.C. 20001

Dear Mr. Harrison:

This is a follow-up to the letter sent to you on October 12th. The Louis Berger Group, Inc. (Berger) is a consultant to the District of Columbia Department of Public Works (DCDPW) conducting the Klinge Road Environmental Assessment (EA). Per your conversation with Melissa Bird (of Berger) in April 2000, we are now requesting your written confirmation of Washington Metropolitan Transit Authority's needs and concerns as they relate to this project and project alternatives. Attached to this letter is a detailed topography map with the project area identified.

Project Description

The District of Columbia Department of Public Works (DPW) is preparing an Environmental Assessment (EA) to assess the potential impacts associated with the alternative potential uses of the Klinge Road right of way, located in Northwest Washington, DC. As shown on the attached map, the EA is being prepared for the portion of Klinge Road that is currently closed to vehicular traffic between Porter Street, N.W. and Woodley Road, N.W. Although previous correspondence and discussions between the DPW, the National Park Service, and the public have primarily considered a non-vehicular use of the roadway, it is necessary to prepare an EA which examines various options if federal funds are to be used for any project alternative, including any recreational use. The EA is being prepared under requirements of the National Environmental Policy Act (NEPA) and the implementing regulations of the Council on Environmental Quality and the Federal Highway Administration.

The preliminary project alternatives include:

- ♦ The No Action Alternative
- ♦ No Build Alternative (differs from the No Action Alternative in that drainage problems will be addressed)
- ♦ Green Space Alternative (removal of asphalt on Klinge Road to allow the area to return to natural condition)
- ♦ Bike recreation/facility management (conversion of the closed portion of Klinge Road to a bike path with appropriate resurfacing)
- ♦ Rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage



Information Request

We are aware that these alternatives may potentially impact relating to WMATA'S ability to provide METRO service in the area. On behalf of DCDPW, Louis Berger is requesting written verification of the following information from your office:

- WMATA's review of this project information.
- The presence of conduits/power stations in the Connecticut Avenue Bridge.
- WMATA's need for access to the closed portion of Klinge Road for service and maintenance purposes.
- Number of times WMATA/METRO needs to access the grounding station in the Connecticut Avenue Bridge abutment for scheduled maintenance.
- WMATA's needs, if any, for an access road to the closed portion of the existing road, if necessary, the width and surface type.
- The types of vehicles/equipment needed, if any.

The information provided by your office will become part of the final Environmental Assessment. Also, all written information from your office may be incorporated into the appendix of the EA. If possible, we would like to receive this information in our office by October 27, 2000 in order to prepare for a public hearing on November 29, 2000 at DPW. If you have any questions or need more information please contact either Jess Commerford at 202 331-7775 ext. 459 or Melissa Bird at 202 331-7775 ext. 496. Mr. Harrison, thank you for your attention to this matter, we look forward to receiving your information on behalf of WMATA.

Sincerely,

The Louis Berger Group, Inc.

Jess Commerford, AICP
Director, Planning and Environmental Services

Enclosure as cited

cc: Maurice Keys, DCDPW

Larry D. Walker, The Louis Berger Group, Inc.

Received via email Nov. 3, 2000

Mr. Jess Commerford, AICP
Director of Planning and Environmental Services
The Louis Berger Group, Inc.
Suite 900
1819 H Street, NW
Washington, DC 20006

Dear Mr. Commerford:

This is in response to your attached October 17, 2000, letter requesting information for the environmental assessment (EA) of the closed portion of Klinge Road in northwest Washington, DC. You plan to include the District of Columbia Water and Sewer Authority's (DC WASA) needs and concerns as they relate to this project and the five project alternatives in the environmental assessment. You also requested the presence of active water mains and sewers along the closed portion of Klinge Road.

WATER AND SEWER SYSTEMS

DC WASA does not have any active water mains in the study area. The enclosed maps illustrate the sanitary and storm sewers along the closed portion of Klinge Road. The enclosed disks contain the entire sewer maps for the area.

Regarding the storm sewer system, the unimproved stream to the south and east of Klinge Road carries all of the storm water runoff from Klinge and Woodley Roads and the surrounding drainage area. This stream appears to be in National Park Service property and hence may be NPS responsibility for maintenance. There is a 4' 3" round storm drain in Klinge Road, which starts about 300 feet west of Connecticut Avenue and travels east to Porter Street. This storm drain does not carry any storm water from Klinge Road but carries drainage from Macomb Street and the surrounding area. This drain is the responsibility of DC WASA to maintain. At the east end of Klinge Road, east of Connecticut Avenue, one drainpipe that transverses under the road is undermined and collapsed in the stream. It will have to be repaired to prevent future erosion. It should be noted that several existing catch basins are not shown on these maps.

There is a sanitary sewer, which comes from Woodley Road and follows Klinge Road to Porter Street. DC WASA recently sliplined 1670 feet of this sanitary sewer because of maintenance problems. The sliplined sewer starts at Woodley Road and runs to the first manhole east of Connecticut Avenue, which is illustrated on the enclosed maps. The remaining sewer from this manhole to Porter Street will be evaluated for possible lining in the future.

Before summarizing DC WASA's needs and concerns, the following background information describes our involvement in the closing of Klinge Road.

BACKGROUND

In the 1980's, the District of Columbia initiated a federally funded project to reconstruct Klinge Road. DC WASA was not yet created as the responsible agency so that the DC Department of Public Works (DC DPW) developed storm drain and channel improvement plans to correct the drainage problems associated with the deteriorated road and stream. The City planned to construct the new storm drains and channel improvements under the road reconstruction contract. During the review process of the plans for the storm drain and channel improvements, the National Park Service expressed an interest to return the channel along Klinge Road to its natural state. Because of this requirement, DC DPW initiated survey work to design a new storm drain system that would convey all of the storm water from Woodley and Klinge Roads in a large storm drain within the road right-of-way. DC DPW did not complete the survey and the subsequent design when the city officially closed the road. Since then the erosion along the road has continued. Since DC WASA has subsequently been created, any storm drainpipe within the road right of way would have to be designed, constructed and maintained by DC WASA.

PROJECT ALTERNATIVES

- 1) Under the no action alternative, and the other four alternatives, DC WASA will need access to the sanitary and storm sewers for emergency and routine maintenance work. This alternative would not allow DC WASA to construct a storm drainpipe to address the issue of storm drain system deterioration.
- 2) The "No Build Alternative", will only address the drainage problems. Based on prior studies by DC DPW it would appear that a full storm drain system within the paved road is the best overall solution for this alternative. However, additional engineering and cost studies would be required to verify prior engineering before proceeding with design and construction of this pipe system. Some restoration work will also be required along the road and channel to correct erosion; however, coordination with DPW would be needed to establish responsibilities.
- 3) The Green Space Alternative includes the removal of asphalt to allow the area to return to natural conditions. If this alternative also includes the removal of the concrete base under the asphalt, then additional fill may be necessary to provide sufficient cover over the existing storm drains, sanitary sewer and other utilities (gas main). This additional fill will also provide adequate surface drainage in low areas. DC WASA requires a minimum of 4 ½ feet of cover over the sanitary and storm sewers. Some stretches of Klinge Road are very steep. Once the

asphalt is removed, these steep slopes will have to be protected to prevent excessive erosion, which could expose and possibly damage the existing utilities and limit future access of vehicles for maintenance of the utilities. The type of surface within the road easement should be strong and durable enough to support the utility maintenance trucks and heavy equipment without causing ruts during wet weather. No trees should be planted in the road right-of-way. Shrubs should not be planted any closer than 5 feet from the centerline of the sewers and structures.

- 4) Traditional Bike recreation trails generally do not provide adequate access for sewer maintenance vehicles and heavy equipment. The bike trail should be engineered such that there is sufficient width and strength for use by mid-size dump trucks pulling trailers with backhoes. The area should also be graded so that no surface structures like manhole covers are above grade, which could be hazardous for cyclists. Some storm drains will be required at low areas along the trail.
- 5) Under this alternative to rebuild Klinge Road to its original alignment and dimensions and repair/replace storm drainage, all infrastructure should be built to current standards and codes. Based on prior DC DPW studies, it would appear that the construction of a new storm drain in the paved road from Woodley Road to Porter Street is the optimum solution. The channel along Klinge Road should be restored to natural conditions as required by the National Park Service.

GENERAL REQUIREMENTS FOR ALL ALTERNATIVES

The full width of the road easement will be needed to provide adequate service to existing and possibly future pipelines. If excavation work were required for maintenance purposes, DCWASA would transport backhoes, 5-yard dump trucks, possibly flat bed trucks and backhoe trailers along the right-of-way to work sites. If excavation work is required on the 4' 3" storm sewer, a large tracked backhoe may be necessary. This machine and a regular backhoe will require a wide space for pivoting between the excavation and trucks hauling spoils and backfill material. DC WASA maintenance staff will also drive sewer cleaning vehicles to work sites for emergencies and routine cleaning work. This equipment consists of jet/vacuum trucks, high-pressure water jet trucks, dump trucks pulling sewer cable cleaning machines, the catch basin cleaning dump truck and the sewer televising van.

DC WASA would like to be involved in the review and approval process for all design and construction plans that may affect our sanitary and storm sewers. If you need our staff to discuss our facilities and maintenance procedures, please contact Mr. Cuthbert Braveboy at (202) 264-3828. For any other information please call my office at (202) 787-2379 or send e-mail to jshabels@dcwasa.com.

Sincerely;

James J. Shabelski, PE
Water and Sewer Design Branch

Washington Gas
6801 Industrial Rd
Springfield, VA 22151
November 6, 2000

The Louis Berger Group, Inc.
1819 H St., NW
Suite 900
Washington, DC 20006

FAX Copy
No Attachment B.

Attn: Jess Commerford, AICP
Director, Planning and Environmental Services

Dear Mr. Jess Commerford,

Washington Gas (WG) would prefer any of the alternatives that would produce the least disturbance to our piping that runs along this abandoned portion of Klinge Rd. This pipeline is an integral portion of our distribution piping network which supplies natural gas to our customers in Washington DC. If construction is planned that would take place near or across our pipeline then we would require that the provisions of Attachment A, enclosed with this letter, be met. WG

ll also need to review all construction prints for this area that show plans for any changes in grade or in the location and depth of any proposed utilities that will cross or run parallel to WG pipelines at a distance of less than 5 ft. These drawings should be sent to the Attention of Mr. Allan Melliza, DC Section Leader for Replacement Design at the above address. These proposed construction drawings should be sent at least four months prior to the proposed start of any construction

WG does not have any active natural gas pipelines suspended from the Connecticut Ave bridge that passes over Klinge Rd. Our records indicate that we do have an abandoned 12" steel pipeline hangs from the bottom of the bridge and is located between two of the bridges longitudinal girders.

WG does have a 12" wrapped steel pipeline that operates at 20 psig that passes below the bridge. This 12" pipeline runs from the intersection of Klinge Rd and Cortland Pl NW, alongside and beneath Klinge Rd as shown on the enclosed drawing plot, Attachment B. Just east of the Connecticut Ave. bridge there is a piping tee. From this tee one of our gas pipes, an 8" wrapped steel pipe, continues to run east beneath and alongside Klinge Rd to the intersection with Porter

NW. The other connection of this tee travels northwest up the side the ravine in a parallel direction with Connecticut Ave, NW. Refer to the enclosed drawing plot, Attachment B of this area. This drawing plot shows the approximate location of our natural gas pipeline; however, Washington Gas makes no warranty as to the accuracy of this

Response to Louis Berger Group

11/6/2000

drawing plot. In accordance with Attachment A, "Miss Utility" must be called to obtain the location of these gas pipelines and spot holes must be dug to determine their exact location and their actual depth below ground.

WG has plans to perform two construction projects that are planned to take place near or along Klinge Rd during either the year 2001 or 2002. The first involves replacement of the 8" cast iron pipeline that runs northwest up the side of the ravine from Klinge Rd to where the north side of the Connecticut Ave bridge is located. This cast iron piping replacement along with piping to be replaced alongside Connecticut Ave is highlighted in orange on the enclosed drawing plot labeled Washington Gas, Attachment B. The second construction project involves the replacement of approximately 400 ft of 8" steel piping that runs alongside Klinge Rd just west of the intersection with Porter St. NW. This steel piping replacement is highlighted in blue on the attached drawing plot.

WG performs leak surveys every 3 years on our Distribution mains, such as this pipeline along Klinge Rd. This inspection could be accomplished by walking along the route of the pipeline. If leak repairs are needed, then WG will need a 12 ft wide surface over which we could get a backhoe tractor to travel to reach any portion of our pipeline.

If you have plans to make a field inspection of Klinge Rd along this abandoned section, I would be interested in joining you.

Sincerely,

Douglas W. Ryan

Douglas W. Ryan,
Spec., Construction Design & Planning

Xc: A Melliza
C:\replacement\WashDC\Klinge rd 11-2000

ATTACHMENT A

11/6/2000

Response to Louis Berger Group regarding proposed Klingle Rd
Construction near Washington Gas Distribution Pipeline

1. Notify "Miss Utility" 48 hours prior to construction for gas facility location. Call 1-800-257-7777 for location scheduling.
2. Notify Damage Protection of Washington Gas on (703)750-4205, at least five (5) working days prior to any construction, subsequent maintenance, or repair.
3. Blasting within 100' of Washington Gas facilities shall be conditionally allowed pending approval of a Blasting Plan. Blasting on a Washington Gas right of way shall not be permitted without the prior written approval of the Washington Gas Damage Protection Office. Approval request should be forwarded by mail or fax 30 days in advance of blasting to:

Washington Gas
Damage Protection - Room 169B
6801 Industrial Road
Springfield, Virginia 22151
(703) 750-5125 or by fax (703) 750-7584

4. Prior to physically locating the gas pipeline by digging spot holes, no mechanized ditching or excavation shall be allowed within ten (10) feet of the extremities of the pipeline(s), as were marked by Miss Utility. These spot holes must be dug at each bend of the natural gas pipeline and at 75 ft intervals for straight sections of piping. Once spot holes have been dug and the WG pipeline has been located, machine tools may be used as close as 18 inches from the WG pipeline. No excavation is permitted over any Washington Gas pipeline or within its easement without a Company representative being present. Subgrading, grading, and the placement of fill over Washington Gas pipeline(s) will require the written approval of Washington Gas as to method and extent.
5. Full access must be maintained to, from and along the pipeline(s) at all times. Stockpiling of fill, including spoil, or topsoil over the pipeline(s) is not permitted, unless approved by Washington Gas in writing.
6. Any erosion control measures required for your development including temporary diversion dikes, sediment traps, silt fences, gravel outlets, and emergency spillways that may

ATTACHMENT A

11/6/2000

Response to Louis Berger Group regarding proposed Klingle Rd
Construction near Washington Gas Distribution Pipeline

- influence or contribute to the degradation of Washington Gas right of way will require the approval of Washington Gas' field representative as to equipment and method. Under no circumstances shall water be impounded on the pipeline(s) right of way.
7. Temporary equipment crossings over the pipeline(s) are permitted with four (4) vertical feet of cover over the pipeline(s) or Washington Gas approved plating material of sufficient size at selected locations as approved by Washington Gas' field representative. Depth of pipe as determined by test holes will determine amount of temporary fill required. No equipment or vehicles may be parked over the pipeline(s).
8. Washington Gas steel pipelines such as the pipeline along Klingle Rd have cathodic protections system which protect steel pipelines from corrosion. Washington Gas must be contacted prior to actual construction so that these cathodic facilities can be identified and efforts taken to prevent damage to them.
9. Relocation or removal of Washington Gas pipeline markers shall not be permitted without the approval of a Washington Gas representative. In addition no pipeline marker shall be obscured from public view.
10. Test spot holes must be dug at all crossings of gas facilities and must include a Washington Gas visual inspection of facilities involved.
11. A minimum of one foot (1) vertical clearance and five (5) feet horizontal clearance must be maintained between other buried utilities that cross or run parallel to WG gas pipelines of twelve inch (12") or less diameter.
12. All proposed roadways and parking areas shall maintain a minimum of four (4) feet from top of pipe to top of finished road surface and three (3) feet minimum vertical cover in open drainage or road ditches. Washington Gas' Corporate Engineering Department may increase these minimum requirements as determined by analysis of the pipe, and other variable conditions and factors. If these determined clearances cannot be maintained, then Washington Gas must be notified so that an alternative means can be taken to properly protect our gas pipeline, such as protective slabs.

ATTACHMENT A

11/6/2000

Response to Louis Berger Group regarding proposed Klinge Rd
Construction near Washington Gas Distribution Pipeline

13. Cover above the WG pipeline(s) that are NOT located below roads or other paved areas shall be a minimum of three (3) feet and shall be a maximum of six (6) feet, unless approved by WG.
14. Washington Gas reserves the right to excavate and perform maintenance as needed for our pipeline.



IN REPLY REFER TO

United States Department of the Interior

NATIONAL PARK SERVICE
National Capital Region
Rock Creek Park
3545 Williamsburg Lane, N.W.
Washington, D.C. 20008-1207



D30(NCR-ROCR)

AUG 13 2001

Mr. Kenneth G. Laden, Administrator
D.C. Department of Public Works
2000 14th Street, NW.
Washington, D.C. 20009

Dear Mr. Laden:

We are writing to reaffirm our 1996 position on the Klingle Road project.

We believe that the environment, and thus, the public, would be best served by the permanent closure and removal of the asphalt road, repair or replacement of the inadequate drainage systems, restoration of the natural valley, and construction of a pedestrian, permeable surface trail on the alignment of the old road. With the road removed and all of the improvements described above completed, we would be willing to accept transfer of the right-of-way now under the jurisdiction of the District of Columbia, providing that the appropriate agencies maintain the storm water, sanitary sewer and other utilities in the valley.

We are aware that the public debate over the Klingle Road project has largely centered on transportation and traffic issues. However, the traffic study conducted by the Berger Group concluded that "the opening of Klingle Road under any of the build scenarios would result in only minor improvements to traffic operations due to the fact that the road size [a minor arterial roadway for vehicular traffic on the District of Columbia's Functional Classification Map] is incapable of relieving traffic or the current Level of Service (LOS) at surrounding intersections."

The failure of the Klingle Valley drainage system has resulted in severe deterioration of the roadway and its underlying storm water system and has caused a chronic degradation of the soils and vegetation along the stream. The interim report on the progress of the Klingle Road Environmental Study, prepared by the Berger Group and issued in November 2000 by your office, confirmed that existing conditions in Klingle Creek, a tributary of Rock Creek, are not representative of a healthy urban stream.

The suggestion that Klingle Road could be built with adequate storm water management facilities to protect the valley is not supported by any studies to date. We do not believe that studies could be developed to support that conclusion.

8-20-01; 4:09PM;

12026710617

3 3

We firmly believe that the construction of the necessary storm water management and sewage systems which would be required by the reconstruction of Klingle Road will exceed the land within the road right-of-way. Use of park land for road or storm water purposes, either in the form of direct or indirect use would be environmentally destructive, and therefore, cannot be permitted by the National Park Service.

We look forward to continuing to work with your office on this important issue.

Sincerely,

Adrienne A. Coleman
Superintendent, Rock Creek Park

Appendix B: Methodology

GOVERNMENT OF THE DISTRICT OF COLUMBIA
DEPARTMENT OF HEALTH
ENVIRONMENTAL HEALTH ADMINISTRATION
WATERSHED PROTECTION DIVISION

FAX COVER SHEET

DATE: 10/8/00 11/8/00

TIME SENT: 1:30

NUMBER OF PAGES: 3 (INCLUDING COVER PAGE)

TO: RAED EL-FARHAN

OFFICE: LOUIS BERGER

ADDRESS:

FAX #: 202, 293 0187

OFFICE #: 1 331 7775

FROM: SUZY WARD

OFFICE ADDRESS: 51 N STREET, N.E., 5TH FLOOR
WASHINGTON, D.C. 20002

FAX #: (202) 535 - 1364

OFFICE #: (202) 535 - 2240

COMMENTS: EXCEPT FROM OCT 2000

305 (b) - Klingle Valley
W.Q.

Overall Use Support Status Report

Waterbody ID : DCTKV01R
Waterbody Name: KLINGLE VALLEY
Waterbody Type: River
Basin: POTOMAC

Segment Number: 00

Size: 0.80 Miles

Description of the Waterbody

KLINGLE VALLEY TRIBUTARY FLOWS THROUGH A RESIDENTIAL AREA AND DISCHARGES INTO ROCK CREEK FROM THE WEST NEAR THE PORTER STREET BRIDGE. THE STREAM'S REACH PARALLELS THE SOUTH SIDE OF KLINGLE ROAD. A WOODED BUFFER OF A FEW HUNDRED FEET COVERS ONE SIDE OF THE STREAM WITH THE REST OF THE 120 ACRE WATERSHED RESIDENTIAL URBAN AREA. NINE (9) OUTFALLS INCLUDING ONE CSO LINE THE STREAM.

THE ABOVE DESCRIPTION WAS TAKEN FROM 'BIOLOGICAL WATER QUALITY OF THE SURFACE STREAMS OF THE DISTRICT OF COLUMBIA,' W.C. SANTA, THE AMERICAN UNIVERSITY, 1993.

Assessment Date: 0004

Use Support

Designated Use	Fully Supp	Threat	Partial Supp	Not Supported	Not Attained	Not Assessed
OVERALL USE SUPPORT	0.00	0.00	0.00	0.00	0.00	0.00
AQUATIC LIFE SUPPORT	0.00	0.00	0.00	0.00	0.00	0.00
SWIMMABLE	0.00	0.00	0.00	0.00	0.00	0.00
SECONDARY CONTACT REC	0.00	0.00	0.00	0.00	0.00	0.00
FISH CONSUMPTION	0.00	0.00	0.00	0.00	0.00	0.00
NAVIGATION	0.00	0.00	0.00	0.00	0.00	0.00

Nonattainment Causes

Cause	Size Mag
0100-UNKNOWN TOXICITY	0.00 S
1200-ORGANIC ENRICHMENT/LOW DO	0.00 H
2400-TOTAL TOXICS	0.00 M

Nonattainment Sources

Source	Size Mag
0400-COMBINED SEWER OVERFLOW	
4000-URBAN RUNOFF/STORM SEWERS	0.00 H
	0.00 H

Comments on the Assessment

THE EVALUATION OF KLINGLE CREEK'S AQUATIC LIFE SUPPORT USE IS BASED ON LEVEL II RAPID BIOASSESSMENT PROTOCOLS PERFORMED BY WQMB IN 1998. KLINGLE CREEK WAS FOUND TO BE 'PARTIALLY SUPPORTING' OF THIS DESIGNATED USE. IT RECEIVED A 24% OF REFERENCE ON ITS BIOASSESSMENT SCORE AND 66% OF REFERENCE

ON ITS HABITAT ASSESSMENT SCORE. PH, D.O. AND TEMPERATURE WERE IN FULL COMPLIANCE.

THE SWIMMABLE USE STANDARD OF 200 MPN/100ML WAS VIOLATED 66.7% OF THE TIME. THE SWIMMABLE USE WAS NOT SUPPORTED. THE SECONDARY CONTACT RECREATION USE STANDARD OF 1000 MPN/100ML WAS VIOLATED 33.3% OF THE TIME. THE USE WAS NOT SUPPORTED.

DETERMINATION OF THE FISH CONSUMPTION USE WAS BASED ON A PUBLIC HEALTH ADVISORY ISSUED ON NOVEMBER 15, 1994 BY THE D.C. COMMISSIONER OF PUBLIC HEALTH. THE ADVISORY URGES NON-CONSUMPTION OF CATFISH, CARP OR EEL AND LIMITED CONSUMPTION OF OTHER FISH CAUGHT IN ALL DISTRICT OF COLUMBIA WATERS. THIS WATERBODY DID NOT SUPPORT FISH CONSUMPTION CRITERIA.

Vegetation Survey Methodology

Characterization of vegetation was conducted as part of the Environmental Assessment (EA) to determine the potential affects associated with the implementation of alternatives being considered for use of the Klinge Road right-of-way. The survey provides the baseline data necessary to assess potential impacts to vegetation and vegetative communities associated with implementation of each of the alternatives. The characterization and inventory of vegetative resources includes a comprehensive survey of understory vegetation based on random sampling throughout the maximum potential extent of the project area, a general characterization of dominant tree species occurring within the project area, and the identification and location of all trees with diameters at breast height (dbh) of greater than 24 inches. The following describes the methodology used to characterize vegetation in the project area for use in assessing the effects of implementing each of five alternative uses considered in the EA.

Study Area Determination

The assessment area was determined by evaluating the construction and land use requirements for each of the five alternatives consider in the EA. Three of the alternatives considered could potentially directly effect existing vegetation on the site resulting from widening or modifying the existing roads footprint. The maximum potential construction widths, or areas of impact, associated with implementation of these alternatives are identified as follows:

- **28 feet**—Rebuild the road for vehicular use only ((2 x 12 ft. lanes) + (2 x 2 ft. shoulder))
- **40 feet**—Rebuild road for vehicular use plus Pedestrian/Bikeway use assuming a bike/pedestrian path on each side of the road ((2 x 12 ft. lanes) + (2 x 2 ft shoulder) + (2 x 6 ft. path)) (This alternative was considered, but not carried forward in the Environmental Assessment.)
- **6 feet** – Build a bike path, no vehicular use

Using the above projections, the greatest potential area of impact was determined to equal 44 feet (width) by 2,588 feet (length). The area of study was extended to 50 feet, or 25 feet to either side of the centerline of the existing road. The study area was divided into quadrants that

were identified by dividing the road into four equal sections of 647 feet by 50 feet, for comparison and data management purposes. Each quadrant was subdivided by the centerline of the road to create 8 total quadrants equaling 647 feet in length and 25 feet in width. Quadrants to the north of the centerline were labeled A, and to the south B.

Understory Vegetative Survey

Characterization of understory vegetation was based on random sampling using meter-square plots located in each of the established quadrants (discussed above). Twenty sampling locations were randomly located in each of the 647 foot by 25 foot quadrants. Plot locations were randomly generated using the Excel Sampling tool to create a sample from a population by treating the input range as a population. Distance down the centerline of the road from the beginning of the quadrant and the distance north or south of the centerline made up the two input ranges. From each of these ranges, Excel selected a random number that combined to determine sampling points. Overall, 160 sampling points were located over the study area. The sampling points were located on the project site. Each sampling point located the center of a meter square plot. Sampling points located in the existing road, in areas where no vegetation occurred, were moved to the edge of the road and the adjustment was recorded. Sampling points located within fenced in private property were also adjusted so that the point would fall outside the private property line.

Sampling plot characterization included the identification and percent coverage of all herbaceous and woody vegetation occurring within the meter square. The strata of the vegetation, whether the species was invasive or indigenous, and the dbh of any trees occurring partially or completely in the plot were also recorded. The presence or absence of exotic invasive plant species in the plots was used as an indicator of the overall quality of habitat.

Plant species diversity, the presence of sensitive or rare plants and the occurrence and potential impacts of exotic invasive plant species in the plots were noted to determine overall community health and to determine potential affects of proposed alternatives.

Tree Survey

Quadrants established for the understory characterization were also used in the tree survey.

Dominant tree species located within the potential areas of impact were identified and recorded. All trees with a dbh of 24 inches or greater occurring within the potential areas of impact were identified, measured, and mapped. Each tree was given an identification number associated with its location. Large diameter trees occurring adjacent to the area of potential disturbance and having the potential to be affected by the alternative uses were also recorded. In addition, trees with a dbh of slightly less than 24 inches were noted to better exemplify forest characteristics within the survey area.

Assessment of Data Collected in the Understory Vegetation and the Tree Surveys

Plant species diversity, the presence of sensitive or rare plants and the occurrence and potential impacts of exotic invasive plant species and their effect on native plant species diversity and overall habitat quality will be used to assess the potential adverse effects of implementing the proposed alternatives. Tree species diversity and the presence of large diameter trees, along with the potential for adverse impacts associated with the proposed alternatives will be used to further characterize impacts and mitigation requirements.

METHODOLOGY FOR GEOCODING AND DELINEATION OF STUDY BOUNDARY FOR SOCIAL AND ECONOMIC ISSUES

A. METHODOLOGY

According to the Federal Highway Administration, Office of Environment and Planning, a community impact analysis should identify a geographic region that incorporates the communities expected to be affected by the project based on scoping, public involvement and interagency coordination. In an effort to identify affected communities, a study boundary was identified by geocoding addresses from the original Klingle Road Community Mailing List and then performing a visual analysis of the mapped addresses. The original Klingle Road Community Mailing List consisted of community groups, ANCs, advocacy groups, and other individuals that showed interest in the project from the March 15, 2000 public informational open house. The following five steps were performed to complete the geocoding process and the determination of the study boundary for addressing social and economic issues.

Step One: Clean and Update Klingle Road Mailing List

The Klingle Road Community Mailing List consists of 399 addresses obtained in preparation of the public meeting held on March 15, 2000, as well as, addresses obtained during the meeting and by letters or comment cards that were received by concerned citizens during and after the meeting. The first phase of cleaning the mailing list was to save the Microsoft Access file as a new regular database file. Once this was completed all unnecessary addresses with respect to the social and economic study were deleted. The majority of addresses deleted were for local and federal agency coordination. For instance, Andrew Altman from the District's Office of Planning and U.S. Fish and Wildlife addresses were deleted. After the completion of the above task the Klingle Road Community Mailing had a total of 344 addresses. These addresses included District citizens, heads of Area Neighborhood Commissions and so forth. The last phase of this stage was to correct spelling mistakes in road names and to verify correct abbreviation for street types.

Step Two: Geocoding Klingle Road Mailing Addresses

The process of geocoding is an application of Geographical Information Systems (GIS) that identifies the coordinates of a location using an address table and a reference theme. The address table utilized was the cleaned and updated Klingle Road Mailing List (344 addresses). The reference theme utilized was a street theme with attributes that specify street names, street types, range of addresses that occur along each street, and city quadrants for the District of Columbia. The District of Columbia street theme was a TIGER line file that was downloaded from the U.S. Census web page. The geocoding process was completed using the GIS software package ArcView 3.2 developed by the Environmental Systems Research Institute, Inc. (ESRI).

Step Three: Review Geocoding Results

Of the 344 mailing list addresses, 343 addresses were geocoded (99.7 %) in the initial geocoding batch match. The remaining address could not be geocoded because the address was a P.O. Box and not a mailing address. Due to the success of the initial geocoding, no re-batch matching was necessary. In all, 343 addresses were geocoded and will be used to assist in defining the socioeconomic study boundary (Refer to Figure 1-2).

Step Four: Determine What Geographic Entity to Use for Data Collection

Before performing any visual analysis of the geocoded addresses it was necessary to choose a type of geographical (statistical) boundary system that will direct data collection and help distinguish the study boundary. To determine an appropriate boundary system for data collection, two characteristics were investigated, boundary size and quantity of data. For the District of Columbia there are four types of statistical boundaries (from largest to smallest); Wards, Advisory Neighborhood Commissions (ANCs), U.S. Census tracts, and U.S. Census block groups. There are 37 ANCs in the District of Columbia's 8 Wards. An ANC consists of elected representatives from neighborhood communities and advises the City government on issues relating to zoning, social service programs, health, police protection, sanitation, and recreation. Neither ANCs nor Wards were chosen due to lack of data for ANCs and the large boundary sizes of Wards.

After investigating and searching for both U.S. Census tract and block group data it was determined that demographic and economic data is more readily available in the tract format. With this conclusion, it was determined that data collection for the study area would be based on the U.S. Census tract geographical (statistical) boundary system. In general, tracts are small statistical subdivisions of a county or city. Tracts normally have 2,500 to 8,000 persons and are designed to be homogeneous with respect to population characteristics, economic status, and living conditions. The spatial size of tracts varies widely depending on the density of settlement. All tract statistical data was collected from the U.S. Census Bureau and the District of Columbia's State Data Center. All tract data is based on the 1990 U.S. Census, however Claritas performed projection analysis for years 1997 and 1998.

Step Five: Visual Analysis and Boundary Determination

After geocoding mailing addresses and obtaining a geographic boundary system, the next step was to overlay the tract boundaries with the geocoded address points. The purpose of this exercise was to locate address point clusters that could be used to help define the socioeconomic study boundary. The results of this exercise displayed a cluster of addresses (236, 68.6% of the geocoded addresses) that were identified in Cleveland Park, Woodley Park, and Mount Pleasant communities. The remaining addresses (108, 31.4% of the geocoded addresses) were scattered throughout the District of Columbia, however the majority are located in the designated northwest section of the city. In order to limit the socioeconomic study area, tracts that were associated with the location of the 236 clustered addresses were selected and utilized to define the study boundary for social and economic issues (Figure 1-1). Therefore, 8 tracts were selected for the extent of the study area. This included tract numbers 0004.00, 0006.00, 0005.01, 0005.02, 0013.02, 0027.01, 0027.02, and 0039.00 (Figure 1-4).

Upon the completion of determining the extent of the study boundary data was collected for the tracts located in the study boundary and for the District of Columbia as a whole. The data collected will be used to examine the socioeconomic impacts related to the proposed project options. Demographic and Economic data was obtained from the U.S. Census, the District of Columbia State Data Center, the District of Columbia, and the Washington Metropolitan Council of Governments. Data has been collected for the following attributes:

1. Population for 1990, 1997, and 1998.
2. Ethnicity and Race 1998
3. Age 1998
4. Percent of Population Below Poverty 1990
5. Median House Value 1990
6. Median Household Income 1998
7. Education Attainment for Persons Over 25 Years of Age


In an effort to verify the study boundary, the above geocoding steps were performed again upon completion of the second public meeting held on November 30, 2000. Of the 209 names and addresses that were collected at the November meeting, 191 (91.4 percent) were geocoded (*mapped*) (Figure 3). Addresses that were not geocoded included: 11 addresses outside the District of Columbia, 3 addresses that could not be found, and 2 addresses with P.O. Box addresses. This geocoding did not take into consideration petition signatures, because many had incomplete addresses or no addresses at all. The results of the geocoding verified the placement of the established study boundary for evaluating the socio-economic impacts.

Methodology for Geocoding and Determination of Study Boundary for Social and Economic Issues.

Geocoding from the March 15, 2000 Open House

Figure 1

Of the 344 mailing list addresses, 343 addresses were geocoded (99.7 %) in the initial geocoding batch match. The remaining address could not be geocoded because the address was a P.O. Box and not a mailing address. Due to the success of the initial geocoding, no re-batch matching was necessary. In all, 343 addresses were geocoded and will be used to assist in defining the socioeconomic study boundary.



LEGEND

- Mailing List Addresses
- Roads

City Quadrants




- Northeast
- Northwest
- Southeast
- Southwest

2 0 2 4 6 Miles



Methodology for Geocoding and Determination of Study Boundary for Social and Economic Issues.

Figure 2




Methodology for Geocoding and Determination of Study Boundary for Social and Economic Issues.

Geocoding from the November 30, 2000
Public Hearing

Figure 3

Of the 209 names and addresses that were collected at the November 30, 2000 meeting, 191 (91.4 percent) were geocoded (mapped). Addresses that were not geocoded included: 11 addresses outside the District of Columbia, 3 addresses that could not be found, and 2 addresses with P.O. Box addresses. This geocoding did not take into consideration petition signatures, because many had incomplete addresses or no addresses at all. The results of the second geocoding verified the placement of the established study boundary for evaluating the socio-economic impacts.



Appendix C: Technical Information

MEMORANDUM

APR 2 1986

Design Standards for Highways
in National Flood Insurance
Program Mapped Floodplains

Associate Administrator for Engineering
and Program Development

HNG-31

Regional Federal Highway Administrators Regions 1-10

The FHWA recognizes the National Flood Insurance Program (NFIP) standard that provides for up to a 1-foot increase in flood stages when (1) designating a floodway or (2) evaluating an encroachment where no floodway is designated. This standard is established as the Federal standard under Executive Order 11988, Floodplain Management, and is to be used in designing highways in NFIP mapped floodplains.

The FHWA floodplain regulations were issued in November 1979 (23 CFR 650, subpart A). These regulations established standards for the cost-effective design of highways in floodplains and for consistency with the NFIP. Guidance for complying with the NFIP part of the regulations was provided to the field by Mr. R. D. Morgan's memorandum of June 25, 1982, and was titled "Procedures for Coordinating Highway Encroachments on Floodplains with the Federal Emergency Management Agency (FEMA)".

The coordination procedures established that NFIP standards are to be used in designing a highway in a NFIP mapped floodplain. Highways can normally be designed to be consistent with the NFIP standards because the standards provide for a 1-foot rise in the water surface elevation of the 100-year flood. This increase is included in most State and local floodplain regulations. Development, including highways, is permitted that does not cause backwater in excess of this increase.

The courts have generally ruled that the 1-foot rise of water onto affected property is not a taking and therefore does not require compensation. In addition, the property owner is eligible for damage protection under the NFIP. The property owner is further protected from loss in that the flood insurance rates will not be increased for a rise of 1-foot or less.

Some States have elected to adopt more restrictive standards than the NFIP standards. By more restrictive, it is meant that less than 1-foot of increase is permitted. In a few States, no increase is permitted at all. Permitting little or no increase has the effect of limiting floodplain development. Limiting development in this way is a State/local option under the FEMA regulations. The FEMA encourages restrictive standards because the liability of the NFIP is reduced.

2

However, there may be a cost to others. Application of these more restrictive standards can also result in larger, more costly highway structures and/or right-of-way costs than would have been required under the NFIP standards. These increased costs to meet standards more restrictive than NFIP standards are the responsibility of the State.

Therefore, Federal-aid highway funds should not be used either (1) for payments to property owners or (2) for more costly highway facilities if, in either case, the costs are incurred to meet State standards that require less than a 1-foot rise in water surface elevation for the 100-year flood. Exceptions for designs that limit the water surface to less than a foot may be granted on a case by case basis where the cost effectiveness of such designs can be demonstrated by an economic analysis.

If it is cost effective to exceed the 1-foot increase, FHWA will participate in right-of-way costs for insurable buildings in order to limit flood damage increased for which the State or NFIP might be responsible. Attached are options which should be considered if the 1-foot increase is to be exceeded.

/s/

Rex C. Leathers

Attachment

Procedures for Coordinating Highway Encroachments on
Floodplains with Federal Emergency Management Agency (FEMA)

Local community with land use jurisdiction, whether it is a city, county, or State, has the responsibility for enforcing National Flood Insurance program (NFIP) regulations in that community if the community is participating in the NFIP. Most NFIP communities have established a permit requirement for all development within the base (100 year) floodplain. Consistency with NFIP standards is a requirement for Federal-aid highway actions involving regulatory floodways. The community, by necessity, is the one who must submit proposals to FEMA for amendments to NFIP ordinances and maps in that community should it be necessary. Determination of the status of a community's participation in the NFIP and review of applicable NFIP maps and ordinances are, therefore, essential first steps in conducting location hydraulic studies and preparing environmental documents.

Where NFIP maps are available, their use is mandatory in determining whether a highway location alternative will include an encroachment on the base floodplain. Three types of NFIP maps are published: (1) a Flood Hazard Boundary Map (FHBM), (2) a Flood Boundary and Floodway Map (FBFM), and a Flood Insurance Rate Map (FIRM). A FHBM is generally not based on a detailed hydraulic study and, therefore, the floodplain boundaries shown are approximate. A FBFM, on the other hand, is generally derived from a detailed hydraulic study and should provide reasonably accurate information. The hydraulic data from which the FBFM was derived is available through the regional office.

FEMA. This is normally in the form of computer input data cards for calculating water surface profiles. The FIRM is generally produced at the same time using the same hydraulic model and has appropriate rate zones and flood elevations added.

Communities in the regular program of the NFIP have detailed flood insurance studies performed. In these communities the NFIP map will be a FIRM and in the majority of cases, a regulatory floodway is in effect.

Communities in the emergency program of the NFIP usually have not had a detailed flood insurance study completed and, usually, only limited floodplain data is available. In this case the community NFIP map will be a FHBM and there will not be a regulatory floodway.

Other possibilities are: (1) the community is not in a FEMA identified flood hazard area and thus there is no NFIP map, (2) a FHBM, FIRM, or FBFM is available but the community is not participating in the NFIP, (3) a community is in the process of converting from the emergency program to the regular program and a detailed flood insurance study is underway, or (4) a community is participating in the regular program, the NFIP map is a FIRM, but no regulatory floodway has been established. Information on community participation in the NFIP is provided in the "National Flood Insurance Program Community Status Book" which is published bimonthly for each State and is available through the Headquarters of FEMA.

Coordination With FEMA

It is intended that there should be highway agency coordination with FEMA in situations where administrative determinations are needed involving a regulatory floodway or where flood risks in NFIP communities are significantly impacted. The circumstances which would ordinarily require coordination with FEMA are:

1. a proposed crossing encroaches on a regulatory floodway and, as such, would require an amendment to the floodway map,
2. a proposed crossing encroaches on a floodplain where a detailed study has been performed but no floodway designated and the maximum 1 foot increase in the base flood elevation would be exceeded,
3. a local community is expected to enter into the regular program within a reasonable period and detailed floodplain studies are underway,
4. a local community is participating in the emergency program and base flood elevation in the vicinity of insurable buildings is increased by more than 1 foot. (Where insurable buildings are not affected, it is sufficient to notify FEMA of changes to base flood elevations as a result of highway construction.)

The draft EIS/EA should indicate the NFIP status of affected communities, the encroachments anticipated and the need for floodway or floodplain ordinance amendments. Coordination means furnishing to FEMA the draft EIS/EA and, upon selection of an alternative, furnishing to FEMA through the community a preliminary site plan and water surface elevation information and technical data in support of a floodway revision request as required. If a determination by FEMA would influence the selection of an alternative, a commitment from FEMA should be obtained prior to the FEIS or FONSI. Otherwise this later coordination may be postponed until the design phase.

For projects that will be processed with a categorical exclusion, coordination may be carried out during design. However, the outcome of the coordination at this time could change the class of environmental processing.

Highway Encroachments Which Are Consistent With Regulatory Floodways In Effect

In many situations it is possible to design and construct highways in a cost-effective manner such that their components are excluded from the floodway. This is the simplest way to be consistent with the standards and should be the initial alternative evaluated. If a project element encroaches on the floodway but has a very minor effect on the floodway water surface elevation (such as piers in the floodway), the project may normally be considered as being consistent with the standards if hydraulic conditions can be improved so that no water surface elevation increase is reflected in the computer printout for the new conditions.

PARTICIPATION OPTIONS
FOR
LIMITING FLOOD DAMAGE

If a Federal-aid highway project will cause a 100-year flood elevation which is more than 1-foot higher than the base flood elevation shown on a NFIP map at either (1) a National Flood Insurance Program (NFIP) insurable building or (2) an unimproved property with a substantially changed highest or best use, participation may be provided with Federal-aid highway funds by the following option which best fits the State's property management plan:

1. Purchase property
 - a. Relocate owners/tenants
 - b. Buildings should be:
 - (1) Destroyed,
 - (2) Relocated out of the floodplain
 - (3) Resold with commitment of buyer to:
 - (a) Relocate out of the floodplain, or
 - (b) Elevate the building above the new 100-year flood level or accomplish other acceptable floodproofing techniques
2. Reimburse Owner for Floodproofing Buildings
 - a. Buildings should be elevated to or above the new 100-year flood level or other acceptable floodproofing techniques applied
 - b. Owner retains title
 - c. Owner arranges for floodproofing
 - d. Owner to sign instrument to hold State harmless from future flood damage
 - e. Reimbursement for floodproofing is limited to the cost to Purchase property and relocate residents.
3. Purchase Permanent Easement
 - a. For unimproved property
 - b. Reimbursement is based on before and after appraisal

Revision of Regulatory Floodway So That Highway Encroachment Would Be Consistent

Where it is not cost-effective to design a highway crossing to avoid encroachment on an established floodway, a second alternative would be a modification of the floodway itself. Often, the community will be willing to accept an alternative floodway configuration to accommodate a proposed crossing provided NFIP limitations on increases in the base flood elevation are not exceeded. This approach is useful where the highway crossing does not cause more than a 1 foot rise in the base flood elevation. In some cases, it may be possible to enlarge the floodway or otherwise increase conveyance in the floodway above and below the crossing in order to allow greater encroachment. Such planning is best accomplished when the floodway is first established. However, where the community is willing to amend an established floodway to support this option, the floodway may be revised.

The responsibility for demonstrating that an alternative floodway configuration meets NFIP requirements rests with the community. However, this responsibility may be borne by the agency proposing to construct the highway crossing. Floodway revisions must be based on the hydraulic model which was used to develop the currently effective floodway but updated to reflect existing encroachment conditions. This will allow determination of the increase in the base flood elevation that has been caused by encroachments since the original floodway was established. Alternate floodway configurations may then be analyzed.

Base flood elevation increases are referenced to the profile obtained for existing conditions when the floodway was first established.

Data submitted to FEMA in support of a floodway revision request should include:

Copy of current regulatory Flood Boundary Floodway Map, showing existing conditions, proposed highway crossing and revised floodway limits.

1. Copy of computer printouts (input, computation, and output) for the current 100-year model and current 100-year floodway model.
2. Copy of computer printouts (input, computation, and output) for the revised 100-year floodway model. Any fill or development that has occurred in the existing flood fringe area must be incorporated into the revised 100-year floodway model.
3. Copy of engineering certification is required for work performed by private subcontractors.

The revised and current computer data required above should extend far enough upstream and downstream of the floodway revision area in order to tie back into the original floodway and profiles using sound hydraulic engineering practices. This distance will vary depending on the magnitude of the requested floodway revision and the hydraulic characteristics of the stream.

A floodway revision will not be acceptable if development that has occurred in the existing flood fringe area since the adoption of the community's floodway ordinance will now be located within the revised floodway area unless adversely affected adjacent property owners are compensated for the loss.

If the input data representing the original hydraulic model is unavailable, an approximation should be developed. A new model should be established using the original cross-section topographic information, where possible, and the discharges contained in the Flood Insurance Study which establish the original floodway. The model should then be run confining the effective flow area to the currently established floodway and calibrate to reproduce within 0.10 foot, the "With Floodway" elevations provided in the Floodway Data Table for the current floodway. Floodway revisions may then be evaluated using the procedures outlined above.

Floodway Encroachment Where Demonstrably Appropriate

When it would be demonstrably inappropriate to design a highway crossing to avoid encroachment on the floodway and where the floodway cannot be modified such that the structure could be excluded, FEMA will approve an alternate floodway with backwater in excess of the 1 foot maximum only when the following conditions have been met:

1. A location hydraulic study has been performed in accordance with Federal-Aid Highway Program Manual (FHPM) 6-7-3-2 "Location and Hydraulic Design of Encroachments on Floodplains" (23 CFR 650, Subpart A) and FHWA finds the encroachment is the only practicable alternative.
2. The constructing agency has made appropriate arrangements with affected property owners and the community to obtain flooding easements or otherwise compensate them for future flood losses due to the effects of the structure.
3. The constructing agency has made appropriate arrangements to assure that the National Flood Insurance Program and Flood Insurance Fund do not incur any liability for additional future flood losses to existing structures which are insured under the Program and grandfathered in under the risk status existing prior to the construction of the structure.
4. Prior to initiating construction, the constructing agency provides FEMA with revised flood profiles, floodway and floodplain mapping, and background technical data necessary for FEMA to issue revised Flood Insurance Rate Maps and Flood Boundary and Floodway Maps for the affected area upon completion of the structure.

Highway Encroachment On A Floodplain With A Detailed Study (FIRM)

In communities where a detailed flood insurance study has been performed but no regulatory floodway designated, the highway crossing should be designed to allow no more than a 1 foot increase in the base flood elevation based on technical data from the flood insurance study. Technical data supporting the increased flood elevation should be submitted to the local community and FEMA for their files. Where it is demonstrably inappropriate to design the highway crossing and meet backwater limitations the procedures outlined under

Floodway Encroachment Where Demonstrably Appropriate should be followed in requesting a revision of base floodplain reference elevations.

Highway Encroachment On A Floodplain Indicated On An FIRM

communities where detailed flood insurance studies have not been performed, the highway agency must generate its own technical data to determine the base floodplain elevation and design encroachments in accordance with FHPM 6-7-3-2. Base floodplain elevations should be furnished to the community, and coordination carried out with FEMA as outlined previously where the increase in base flood elevations in the vicinity of insurable buildings exceeds 1 foot.

Highway Encroachment On Unidentified Floodplains

Encroachments which are outside of NFIP communities or NFIP identified flood hazard areas should be designed in accordance with FHPM 6-7-3-2 of the Federal Highway Administration. The NFIP identified flood hazard areas are those delineated on an FIRM, FBPM or FIRM.

To Obtain FEMA Publications

1. National Flood Insurance Program Community Status Book

Write to FEMA, 500 "C" Street, SW., Room 431, Insurance Operations, Washington, D.C. 20472 and request to be placed on the appropriate State mailing list.

2. Flood Insurance Study Report and/or FBPM

Write to FEMA, 500 "C" Street, SW., State and Local Programs Room 418, Washington, D.C. 20472 request:

(a) For future studies,

To be placed on mailing list to receive all studies and maps as they are completed for a State.

(b) For completed studies,

(1) The study for a particular community (provide number).

(2) All the studies for a particular State. You will receive about 50 percent of the completed studies to date.

1. FIRM or FIRM for a particular community with ID number,

(a) call NFIP contractor (800)638-6620, (800)492-6605(MD), 897-5900 in D.C., or

(b) write NFIP, P.O. Box 34604, Bethesda, Maryland 20034

MEMORANDUM

Procedures for Coordinating Highway
Encroachments on Floodplains with the
Federal Emergency Management Agency
(FEMA)

JUN 25 1982

HNG-31

Associate Administrator for
Engineering and Operations
Washington, D.C. 20590

Regional Federal Highway
Administrators
Regions 1-10
Direct Federal Division Engineers

Attached are copies of the subject procedures and a letter from Mr. Richard W. Krimm of FEMA dated June 7, 1982. Mr. Krimm has endorsed the procedures and has distributed them to the field offices of FEMA. Please send copies of these procedures to the FHWA Divisions Offices and the States in your Region.

We believe these procedures provide excellent guidance in regard to meeting our responsibility to be consistent with the standards of the National Flood Insurance Program (NFIP) as set forth in the Federal-Aid Highway Program Manual (FHPM) 6-7-3-2, Location and Hydraulic Design of Encroachments on Flood Plains. The procedures establish some flexibility for achieving cost-effective encroachments on floodplains within communities that are in the NFIP. If an encroachment is proposed within an NFIP community, the economic consequences of alternatives can be assessed using the analysis procedures in Hydraulic Engineering Circular No. 17 (HEC 17), the Design of Encroachments on Floodplains Using Risk Analysis. This assessment/analysis can then be used, if needed, to support the community's application to FEMA for approval of an alternate floodway or a floodway revision. For all locations outside of NFIP communities or NFIP identified flood hazard areas, FHPM 6-7-3-2 shall be followed for encroachment design. This policy requires that encroachment designs be supported, as appropriate, by a risk assessment or risk analysis. Economic (risk) analysis, if appropriate, can be accomplished using the guidelines in HEC 17.

We encourage you to work with the States to implement these procedures as a part of Program Emphasis Area Number 2, Cost Effective Design and Construction. We are aware that some State environmental agencies have adopted strict requirements for encroachments on all floodplains, whether rural or urban in nature. These requirements allow the highway designer little discretion to achieve cost-effective designs. In such cases, this subject should be discussed with appropriate State personnel so that practicable State floodplain encroachment requirements can be developed. Implementation of these procedures, along with the economic (risk) assessment/analysis design process required by FHPM 6-7-3-2, has a high potential for achieving significant cost savings in the Federal-aid Highway Program.

/s/
R. D. Morgan

Attachments

Federal Emergency Management Agency

Washington, D.C. 20472

7 JUN 1982

Mr. R. D. Morgan
Associate Administrator for Engineering
And Traffic Operations
Federal Highway Administration
Department of Transportation
Washington, D.C. 20590

Dear Mr. Morgan:

This is in response to your letter of May 3 1982, seeking our endorsement of the procedure paper entitled "procedures for Coordinating Highway Encroachments on Floodplains with FEMA." This paper expands upon my internal policy memorandum of December 29, 1981, concerning the Federal Emergency Management Agency's (FEMA's) handling of highway encroachments within regulatory floodways. Your expansion addresses highway agency responsibilities for coordination with FEMA under various situations in which FEMA has identified flood plains, floodways and base flood elevations.

I have reviewed your procedure paper and believe that it provides an excellent guideline for coordination between highway agencies, communities participating in the National Flood Insurance Program (NFIP) and FEMA, when flood plain encroachments involving highway construction are proposed. In accordance with Executive Order 11988, the procedures require compliance with NFIP standards and regulations, where practicable, but also provide for responsible actions where no practicable alternative can be identified. These actions include appropriate compensation to affected property owners, assurance that the NFIP will not incur additional liability due to increased flood hazards, and the provision of appropriate technical data to FEMA so that flood insurance maps and studies can be revised as necessary.

We compliment you on your efforts to establish workable operating procedures which incorporate coordination with FEMA on site specific projects. We believe that this procedure paper will facilitate the attainment of our mutual objective of future flood loss reduction. We will provide copies of the paper, with our endorsement to our Regional Offices.

Sincerely,

/S/

Richard W. Krimm
Assistant Associate Director
Office of Natural and Technological
Hazards Programs

Executive Order 11988

May 24, 1977

FLOODPLAIN MANAGEMENT

By virtue of the authority vested in me by the Constitution and statutes of the United States of America, and as President of the United States of America, in furtherance of the National Environmental Policy Act of 1969, as amended (42 U.S.C. 4321 et seq.), the National Flood Insurance Act of 1968, as amended (42 U.S.C. 4001 et seq.), and the Flood Disaster Protection Act of 1973 (Public Law 93-234, 87 Stat. 975), in order to avoid to the extent possible the long and short term adverse impacts associated with the occupancy and modification of floodplains and to avoid direct or indirect support of floodplain development wherever there is a practicable alternative, it is hereby ordered as follows:

Section 1. Each agency shall provide leadership and shall take action to reduce the risk of flood loss, to minimize the impact of floods on human safety, health and welfare, and to restore and preserve the natural and beneficial values served by floodplains in carrying out its responsibilities for (1) acquiring, managing, and disposing of Federal lands and facilities; (2) providing Federally undertaken, financed, or assisted construction and improvements; and (3) conducting Federal activities and programs affecting land use, including but not limited to water and related land resources planning, regulating, and licensing activities.

Sec. 2. In carrying out the activities described in Section 1 of this Order, each agency has a responsibility to evaluate the potential effects of any actions it may take in a floodplain; to ensure that its planning programs and budget requests reflect consideration of flood hazards and

floodplain management; and to prescribe procedures to implement the policies and requirements of this Order, as follows:

(a)(1) Before taking an action, each agency shall determine whether the proposed action will occur in a floodplain -- for major Federal actions significantly affecting the quality of the human environment, the evaluation required below will be included in any statement prepared under Section 102(2)(C) of the National Environmental Policy Act. This determination shall be made according to a Department of Housing and Urban Development (HUD) floodplain map or a more detailed map of an area, if available. If such maps are not available, the agency shall make a determination of the location of the floodplain based on the best available information. The Water Resources Council shall issue guidance on this information not later than October 1, 1977.

(2) If an agency has determined to, or proposes to, conduct, support, or allow an action to be located in a floodplain, the agency shall consider alternatives to avoid adverse effects and incompatible development in the floodplains. If the head of the agency finds that the only practicable alternative consistent with the law and with the policy set forth in this Order requires siting in a floodplain, the agency shall, prior to taking action, (i) design or modify its action in order to minimize potential harm to or within the floodplain, consistent with regulations issued in accord with Section 2(d) of this Order, and (ii) prepare and circulate a notice containing an explanation of why the action is proposed to be located in the floodplain.

16000

(3) For programs subject to the Office of Management and Budget Circular A-95, the agency shall send the notice, not to exceed three pages in length including a location map, to the state and areawide A-95 clearinghouses for the geographic areas affected. The notice shall include:

(i) the reasons why the action is proposed to be located in a floodplain; (ii) a statement indicating whether the action conforms to applicable state or local floodplain protection standards and (iii) a list of the alternatives considered. Agencies shall endeavor to allow a brief comment period prior to taking any action.

(4) Each agency shall also provide opportunity for early public review of any plans or proposals for actions in floodplains, in accordance with Section 2(b) of Executive Order No. 11514, as amended, including the development of procedures to accomplish this objective for Federal actions whose impact is not significant enough to require the preparation of an environmental impact statement under Section 102(2)(C) of the National Environmental Policy Act of 1969, as amended.

(b) Any requests for new authorizations or appropriations transmitted to the Office of Management and Budget shall indicate, if an action to be proposed will be located in a floodplain, whether the proposed action is in accord with this Order.

(c) Each agency shall take floodplain management into account when formulating or evaluating any water and land use plans and shall require land and water resources use appropriate to the degree of hazard involved. Agencies shall include adequate provision for the evaluation and consideration of flood hazards in the regulations and operating procedures for the licenses, permits, loan or grants-in-aid programs that they administer. Agencies

THE PRESIDENT

shall also encourage and provide appropriate guidance to applicants to evaluate the effects of their proposals in floodplains prior to submitting applications for Federal licenses, permits, loans or grants.

(d) As allowed by law, each agency shall issue or amend existing regulations and procedures within one year to comply with this Order. These procedures shall incorporate the Unified National Program for Floodplain Management of the Water Resources Council, and shall explain the means that the agency will employ to pursue the nonhazardous use of riverine, coastal and other floodplains in connection with the activities under its authority. To the extent possible, existing processes, such as those of the Council on Environmental Quality and the Water Resources Council, shall be utilized to fulfill the requirements of this Order. Agencies shall prepare their procedures in consultation with the Water Resources Council, the Federal Insurance Administration, and the Council on Environmental Quality, and shall update such procedures as necessary.

Sec. 3. In addition to the requirements of Section 2, agencies with responsibilities for Federal real property and facilities shall take the following measures:

(a) The regulations and procedures established under Section 2(d) of this Order shall, at a minimum, require the construction of Federal structures and facilities to be in accordance with the standards and criteria and to be consistent with the intent of those promulgated under the National Flood Insurance Program. They shall deviate only to the extent that the standards of the Flood Insurance Program are demonstrably inappropriate for a given type of structure or facility.

(b) If, after compliance with the requirements of this Order, new construction of structures or

facilities are to be located in a floodplain, accepted floodproofing and other flood protection measures shall be applied to new construction or rehabilitation. To achieve flood protection, agencies shall, wherever practicable, elevate structures above the base flood level rather than filling in land.

(c) If property used by the general public has suffered flood damage or is located in an identified flood hazard area, the responsible agency shall provide on structures, and other places where appropriate, conspicuous delineation of past and probable flood height in order to enhance public awareness of and knowledge about flood hazards.

(d) When property in floodplains is proposed for lease, easement, right-of-way, or disposal to non-Federal public or private parties, the Federal agency shall (1) reference in the conveyance those uses that are restricted under identified Federal, State or local floodplain regulations; and (2) attach other appropriate restrictions to the uses of properties by the grantee or purchaser and any successors, except where prohibited by law; or (3) withhold such properties from conveyance.

Sec. 4. In addition to any responsibilities under this Order and Sections 202 and 205 of the Flood Disaster Protection Act of 1973, as amended (42 U.S.C. 4106 and 4128), agencies which guarantee, approve, regulate, or insure any financial transaction which is related to an area located in a floodplain shall, prior to completing action on such transaction, inform any private parties participating in the transaction of the hazards of locating structures in the floodplain.

Sec. 5. The head of each agency shall submit a report to the Council on Environmental Quality and to the Water Resources Council on June 30, 1978, regarding the status of their procedures and the impact of this Order on the agency's operations. Thereafter, the Water Resources Council shall periodically evaluate agency procedures and their effectiveness.

Sec. 6. As used in this Order:

(a) The term "agency" shall have the same meaning as the term "Executive agency" in Section 105 of Title 5 of the United States Code and shall include the military departments; the directives contained in this Order, however, are meant to apply only to those agencies which perform the activities described in Section 1 which are located in or affecting floodplains.

(b) The term "base flood" shall mean that flood which has a one percent or greater chance of occurrence in any given year.

(c) The term "floodplain" shall mean the lowland and relatively flat areas adjoining inland and coastal waters including floodprone areas of offshore islands, including at a minimum, that area subject to a one percent or greater chance of flooding in any given year.


Sec. 7. Executive Order No. 11296 of August 10, 1966, is hereby revoked. All actions, procedures, and issuances taken under that Order and still in effect shall remain in effect until modified by appropriate authority under the terms of this Order.

Sec. 8. Nothing in this Order shall apply to assistance provided for emergency work essential to save lives and protect property and public health and safety, performed pursuant to Sections 305 and 306 of the Disaster Relief Act of 1974 (88 Stat. 148, 42 U.S.C. 5145 and 5146).

THE PRESIDENT

26957

Sec. 9. To the extent the provisions of Section 2(a) of this Order are applicable to projects covered by Section 104(h) of the Housing and Community Development Act of 1974, as amended (88 Stat. 640, 42 U.S.C. 5304(h)), the responsibilities under those provisions may be assumed by the appropriate applicant, if the applicant has also assumed, with respect to such projects, all of the responsibilities for environmental review, decisionmaking, and action pursuant to the National Environmental Policy Act of 1969, as amended.



THE WHITE HOUSE,
May 24, 1977


Handwritten notes at the top left of the page, partially illegible.

Biological Water Quality of the Surface Tributary
Streams of the District of Columbia

William C. Banta
The American University
Washington DC 20016

June 4, 1993

Occasional Publications of the Department of Biology
American University Volume 2 Number 1



Klinglet Creek KGL03: 03/30/93
Summary of Metrics

Metric	Biological Condition Scoring Criteria and/or (Score) for:			
	Study Station KGL03		Ref. Station BVC05	
1. Taxa Richness	74%	(4)	100%	(6)
2. Modified Hilsenhoff Biotic Index	49%	(0)	100%	(6)
3. Ratio of Scrapers/ filterers	0%	(0)	100%	(6)
4. Ratio EPT/Chironomid abundances	0%	(0)	100%	(6)
5. % Contribution of Dominant Taxon	21%	(2)	32%	(2)
6. EPT Index	0%	(0)	100%	(6)
7. Community Loss Index	1.3	(2)	0	(6)
8. Ratio of Shredders/ Total	60%	(6)	100%	(6)
TOTAL SCORE	14		44	
BIOASSESSMENT	32% 'Moderately Impaired'			

Severely Impaired	Moderately Impaired	Slightly Impaired	Not Impaired
.....
* KGL03			

Klinglet Creek (38°55'59"N 73°3'4"W; ADC 9:G6) is our name for a small unnamed stream about 1/2 mile long which discharges into Rock Creek near the Porter Street Bridge over Rock Creek. It parallels the south side of Klinglet Road and branches just west of Connecticut Avenue into two branches, one following Klinglet Road, the other paralleling the south side of Macomb Street. The watershed is about 1/2 square mile (320 acres), but runoff from the most of its watershed is collected by a storm drain system. A 3'6" storm drain, which parallels Klinglet creek and Macomb Street, joins a 4'6" drain from Porter Street just before the combined system empties into Rock Creek through a covered orifice immediately north of the mouth of Klinglet Creek. Except for a wooded buffer amounting to a few hundreds of feet on one side, the creek drains mostly residential urban areas. We sampled about 50m above its mouth; this is our third sampling of this stream.

The surface portions of the stream are cut through the Lower paleozoic Oligoclase-mica Facies of the Wissahickon Formation. Upper reaches are in the Kensington Granite Gneiss, a Piedmont formation of unknown geological age. A small proportion of the uppermost portions of the watershed lie in the Patuxent Formation,

176

Klinglet Creek: KGL03

Upper Cretaceous sediments of the Coastal Plain. The slope of the stream is 5%, measured from the USGS quadrangle; we measured only 2% by clinometer at the sampling site. The channel is almost 30 feet wide, about 6 of which is occupied by water. The stream is averages about 3.5 inches deep, with pools up to two feet deep. The water flowed at about 0.18 m/sec, for an estimated flow volume of 0.83 cfs (6.2 gps, 0.03 m³/sec). The bottom was largely sand, gravel and cobble, with some boulders and bedrock where the stream was heavily scoured.

No odors or oils were noticed in the water or sediments; the pale yellow water was clear, with no measurable turbidity. The DO measured 10.8 ppt, 96% saturated at the sampling temperature of 11C. Conductivity was 460 micromho/cm, slightly elevated; the pH measured near 7.

Erosion around the stream testifies to the impact of watershed pavement on its flow during a significant rain. We estimated that during even modest storms the level rises a foot or more above normal levels. Exposed tree roots at higher elevations suggest that during severe storms water may rise to over twice that level, threatening the storm drain and road next to it. The transverse profile of the stream is fairly steep, with slopes above 60%; the north side is effectively canalized by the concrete emplacements of the storm drain. In some places the stream has eroded away a narrow vegetated buffer and it appears to be only a matter of time before the stream seriously threatens both the storm drain system and Klinglet road.

The stream scored mostly in the Suboptimal range, with evidence of loss of instream cover, increased imbeddedness, channel alteration, bottom scouring and other evidence of erosion. The score was 93, 70% that of the reference stream. Here is a summary of our measurements of these parameters at this site:

Station	Date	Score	Ref Score	Habitat Assessment
KGL01	01/15/1992	84	127	66
KGL02	01/24/1992	73	127	57
KGL03	03/30/1993	93	133	70

We collected 28 individuals from 14 taxa in a 0.25m² kick net sample, of which 6 were species of chironomid. Also present were a crayfish (*Cambarus robustus*), tipulids, oligochaets and some other invertebrates. The apparent increase in density of animals (individuals/m²) between January, 1992 and March, 1993 is actually a decrease in relative density because of the much higher seasonal density in the March reference station (BVC05) compared to CBR04:

Station	Date	Density	Relative Density	No. Taxa	Bioassessment
J1	01/15/1992	84.0	20%	8	45%
KGL02	01/24/1992	80.0	19%	6	10%
KGL03	03/30/1993	112.0	10%	14	31%

This table illustrates wide variability among estimates of bioassessment at different dates. However, the variations are only between 'Severely Impaired' and 'Moderately Impaired.'

Erosion, scouring, and deposition of sand and other sediment contribute to the small population size compared to the reference stream. The ratio of scrapers to filterer-collectors was low relative to that of the reference stream in the 1992 samplings, suggesting eutrophication and organic enrichment. The dominance of one taxon, a deposit-feeding oligochaete, indicated community stress; the fact that it was a deposit feeder indicated organic enrichment, also supported by the relatively low DO (71%). This condition seems to have improved during 1992-3; the dominant in KGL03 was a chironomid and the relative importance of deposit feeders has decreased. Impairment due to organic pollution seems to have decreased, but the number of EPT species is reduced, and there is a decrease in both density and diversity relative to the reference station, indicating toxic pollution.

ic pollution, organic pollution, eutrophication and environmental degradation all appear to be important in this stream. Organic pollution, possibly caused by episodic leaks in sewer lines, has decreased during 1992-3. We note no evidence of recent sewer leaks during our sampling visits, but on one preliminary visit to the site in January, 1991, sewage odors were evident in the area of the stream.

Klinglet Road is closed pending road work in the area. This may temporarily improved conditions in the stream by reducing traffic and other human activity in the area. Construction may severely impact this small stream; it is likely that even more deterioration may occur unless care is taken to minimize loss of sediment into the stream. Additional canalization would further degrade the stream.

STATION KGL03

1 ISOTOMIDAE	COLLEMBOLA	ISOTOMURUS SP.
1 CAMBARIDAE	DECAPODA	CAMBARUS ROBUSTUS
1 CHIRONOMIDAE	DIPTERA	ABLABESMYIA SP.
6 CHIRONOMIDAE	DIPTERA	CHIRONOMIDAE UNIDENTIFIED
4 CHIRONOMIDAE	DIPTERA	ORTHOCLODIUS? SP.
1 CHIRONOMIDAE	DIPTERA	PARATANYTARSUS SP.
2 CHIRONOMIDAE	DIPTERA	SYMPOTTHASTIA SP. 1
3 CHIRONOMIDAE	DIPTERA	THIENEMANNIMYIA SP. 01
1 TIPULIDAE	DIPTERA	LIMONIA SP. 1
3 TIPULIDAE	DIPTERA	TIPULA SP. 1
1 ENCHYTRAEIDAE	OLIGOCHAETA	ENCHYTRAEID SP. 04
2 ENCHYTRAEIDAE	OLIGOCHAETA	ENCHYTRAEID SP. 13
1 LUMBRICIDAE	OLIGOCHAETA	LUMBRICIDAE UNIDENTIFIED
1 PLANARIIDAE	TURBELLARIA	CURA FORMANII

14 TAXA, 28 INDIVIDUALS

Station: KGL03
 Stream Name: KLINGLET ROAD
 Collection Date: 03/30/1993
 Reference Stream: BVC05
 Reference stream collecting date: 03/20/1993
 Days between Reference and Station collection: 10
 Reference Page: 262
 Map coordinates: 9:G6
 County: NW DC
 Tributary of: ROCK CREEK
 Latitude: 38 55'59"
 Longitude: 77 03'04"
 Predominant land use: RESIDENTIAL
 Stream gradient at site measured by clinometer: 3%
 Erosion code (1 None, 2 Moderate, 3 Severe): 2
 NPS Pollution sources (1 None, 2 Some potential sources, 3 Obvious source): 2
 NPS source, if any: RESIDENTIAL
 Channel width: 4m
 Area collected for biological sampling (square meters): 0.25
 Depth of riffle (cm): 6
 Depth of run (cm): 9
 Depth of pools (cm): 63
 Dam present? .F.
 Canalized? .T.
 Canopy cover (1 - 4) (open - shaded) 3
 Sediment odors NONE
 Bottoms of stones not deeply imbedded blackened? .F.
 Animals: NONE

Clay: 0%
 : 0%
 : 35%
 L. el: 20%
 Cobble: 20%
 Boulders: 15%
 Bedrock: 10%
 SAV - Submerged aquatic vegetation: 0%
 Muck and mud: 0%
 Organic debris deposits: 10%
 Weather: CLOUDY
 Weather in the past 24 hr: RAIN
 Water temperature (C): 11C
 Air temperature (C): 16C
 Flood stage (1 Below normal, 2 Normal, 3 Above normal): 2
 Water odors: NONE
 Water oils (0 Absent, 1 Slight, 2 Moderate, 3 Profuse): 0
 Water velocity (cm/sec): 0.18
 Flow volume, calculated: 0.8
 Turbidity (JTU): 0
 Water clarity (0 Clear, 1 Discolored, 2 Murky, 3 Muddy, 4 Very Muddy): 0
 Water color: YELLOW
 Dissolved Oxygen Concentration (ppt): 10.8
 Percent saturation of oxygen: 95.6
 Conductivity (micromho/cm): 460
 6.5
 ent:
 =====
 1. Bottom Substrate (Hab. Eval. 0-20): 12
 2. Embeddedness (Hab. Eval. 0-20): 11
 3. Flow Volume Category (Hab. Eval. 0-20): 4
 4. Canopy Coverage Shading (Hab. Eval. 0-20): 11
 5. Channel Alteration (Hab. Eval. 0-15): 8
 6. Bottom Scouring (Hab. Eval. 0-15): 8
 7. Pool/Riffle Run/Bend Ratio (Hab. Eval. 0-15): 12
 8. Lower Bank Channel Capacity (Hab. Eval. 0-15): 7
 9. Upper Bank Stability (Hab. Eval. 0-10): 5
 10. Bank Vegetative Protection (Hab. Eval. 0-10): 6
 11. Streamside Cover (Hab. Eval. 0-10): 7
 12. Riparian Vegetative Zone (Hab. Eval. 0-10): 2
 =====
 Score OPTIMAL: 12
 Score Sub-Optimal: 12
 Score Marginal: 63
 Score Poor: 12
 Total Score (Hab. Eval.) = 93
 Habitat Assessment: 70
 No animals collected (N): 28
 Animal density (macroinvertebrates / m2) (DENSITY): 112.0
 Number of Taxa at Study Site (N_TAX): 14

Number of Taxa at Reference Site (NR_TAXA): 19
 Ratio of Number of Taxa Study Site/Ref Site (M1): 74.00
 Number of Families at the Study Site (N_FAMS): 7
 Number of Families at the Reference Site (NR_FAMS): 13
 Ratio of No Families Study Site / Ref Site (M9): 0.54
 Hilsenhoff Biotic Index (M2): 4.84
 No. of Taxa Omitted (NTX_EXCL): 3
 No. of Individuals excluded (N_EXCLU): 3
 % of Sample excluded ((N_EXCL/N)*100): 10.71%
 Number of Scraper taxa at the Study Site (NTX_SCR): 0
 Number of Filter-collector taxa at the study site (NTX_FLCL): 0
 Number of scraper individuals (N_SCR): 0
 Number of filter-collector taxa Individuals (N_FLCL): 0
 Ratio of scrapers / filterers for Sampling Site (PS_SCFL): 0.00
 Ratio of scrapers / filterers for Reference Site (PR_SCFL): 0.14
 Scraper/Filterer Ratio Study Site / Reference Site (M3): 0.00
 Number of EPT Taxa at the Study Site (NTX_EPT): 0
 Number of Chironomid Taxa at the Study Site (NTX_CHIRON): 6
 Number of EPT individuals at the Study Site (N_EPT): 0
 Number of Chironomid individuals at the Study Site (N_CHIRON): 17
 EPT/Chironomid Ratio for the Study Site (PS_EPTC): 0.00
 EPT/Chironomid Ratio for the Reference Site (PR_EPTC): 0.00
 EPT/Chironomid Ratio Study Site / Reference Site (M4): 0.00
 Dominant Taxon (DOM_TAXON): CHIRONOMIDAE UNIDENTIFIED
 Number of individuals in the Dominant Taxon (N_DOMTAX): 6
 Percentage of the sample comprised of the dominant taxon (M5): 21.43
 Number of EPT Taxa at the Study Site (NTX_EPT): 0
 Number of EPT Taxa at the Reference Site (NRTX_EPT): 9
 EPT Index (M6): 0.00
 Number of taxa common to both Study Site and Ref. Site (NTX_COM): 1
 Number of taxa at Study Site (N_TAXA): 14
 Number of taxa at Reference Site (NR_TAXA): 19
 Community Loss Index (M7): 1.29
 Number of taxa in Study Site not present in the Ref. Site (NTX_SNR): 1
 Number of taxa in Ref. Site not present in the Study Site (NTX_RNS): 18
 Jaccard Coefficient (M10): 0.03
 No. Taxa at Study Site in Shredder Feeding Group (NTX_SRD): 2
 Number Non-Shredder taxa (NTX_NSRD): 12
 Number of taxa at the Study Site (N_TAXA): 14
 Total number of individuals collected: 28
 Density - Individuals/m2 112.0
 Settled Volume of sample: 99.9
 Settled Volume per m2: 999.9
 Number of individuals at Study Site in the Shredder feeding group (N_SRD): 4
 Proportion of shredders at the Study Site (PS_CPOM): 0.14
 Proportion of shredders at the Reference Site (PR_CPOM): 0.24

Prop. shredders Study Site / Reference Site (M8): 60.10

E Taxa Richnes: 4

E HBI - Hilsenhoff Biotic Index: 0

E Filter-Collectors: 0

EPA4 Ratio of EPTs to Chironomids: 0

EPA5 Contribution of Dominant Taxon: 2

EPA6 EPT Ratio: 0

EPA7 Community Loss Index: 2

EPA8 Ratio of Shredders:Total 6

Sum of EPA1-EPA8: 14

Bioassessment: 31.8

Habitat Assessment: 70

HABITAT ASSESSMENT FIELD DATA SHEET—HIGH GRADIENT STREAMS (FRONT)

STREAM NAME <u>Little Valley</u>	LOCATION <u>100m above Con of Rock Creek</u>
STATION # <u>RIVERMILE</u>	STREAM CLASS
LAT <u>38°46'01" N</u> LONG <u>77°03'06" W</u>	RIVER BASIN <u>RC</u>
LET#	AGENCY
STIGATORS <u>Deke & Suzy</u>	
AM COMPLETED BY <u>Deke</u>	DATE <u>7-29-98</u>
	TIME <u>11:30 AM</u> @
	REASON FOR SURVEY

Habitat Parameter	Condition Category			
	Optimal	Suboptimal	Marginal	Poor
1. Riparian Substrate Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover, mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not invariant).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of new fall, but not yet prepared for colonization (may rot at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
Velocity/Depth regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Score is < 0.3 m/s, deep is > 0.5 m/s).	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, confluences, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
6. Channel Flow Status	Water reaches base of both lower banks and normal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrate is mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

HABITAT ASSESSMENT FIELD DATA SHEET—HIGH GRADIENT STREAMS (BACK)

Habitat Parameter	Condition Category			
	Optimal	Suboptimal	Marginal	Poor
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yrs) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffles or bends; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (Score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Modestly stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank is reaching areas of erosion.	Modestly unstable; 30-60% of bank in such areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "new" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
SCORE (LB)	Left Bank 10 9 8 7 6	5 4 3 2 1 0		
SCORE (RB)	Right Bank 10 9 8 7 6	5 4 3 2 1 0		
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or no-mowedy macrophytes; vegetation disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-regenerated; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stable in height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stable in height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stable in height.
SCORE (LB)	Left Bank 10 9 8 7 6	5 4 3 2 1 0		
SCORE (RB)	Right Bank 10 9 8 7 6	5 4 3 2 1 0		
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roads, etc., clearcuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9 8 7 6	5 4 3 2 1 0		
SCORE (RB)	Right Bank 10 9 8 7 6	5 4 3 2 1 0		

Total Score 114

page 1 of 1

Enter Family and/or Genus and Species name on blank line.

Taxonomic certainty rating (TCR) 1-5: 1=most certain, 5=least certain. If rating is 3-5, give reason (e.g., missing gills). LS= life stage:
 I= immature; P= pupa; A= adult TI= Taxonomist's initials

Total No. Taxa 5

GOVERNMENT OF THE DISTRICT OF COLUMBIA
Department of Health

Watershed Protection Division



July 15, 2000

Ms. Kammy Horne
Louis Berger Group
1819 H St. NW Suite 900
Washington, D.C. 20006

Dear Ms. Horne

We are pleased to have made contact with your group concerning Klinge Valley and are hopeful that the information which you requested from us will be useful. Enclosed you will find the most up to date biologic data that the Watershed Protection Division has on the Klinge Valley Branch. This data, collected in 1998, reveals a stream which is obviously impacted by water quality and habitat degradation issues, although not to the extent that many other streams in the district are suffering. Benthic macroinvertebrate and fish collections reveal a low diversity of species, mostly tolerant to adverse conditions. Also enclosed is the Overall Use Support Status Report, 1998 305b Water Quality Report to Congress and the EPA for Klinge Valley.

I hope that you will find these helpful in your work with the issues involved with Klinge Valley and would like to organize a meeting here with one of your staff to update our office on plans for the Valley. The Watershed Protection Division is involved in several stream restoration projects and finds it beneficial to be 'in the loop' concerning any project which has the potential to affect an aquatic resource in the District. If you have any questions concerning the data, please feel free to contact my biological monitoring coordinator, Peter May at 202-535-2251. Thank you.

Sincerely,

Hamid Karimi, Program Manager
Watershed Protection Division

cc: Ken Laden, Department of Public Works
Jim Collier, Bureau of Environmental Quality

BENTHIC MACROINVERTEBRATE LABORATORY BENCH SHEET (FRONT)

page 1 of 1

STREAM NAME <u>Klinge Valley</u>		LOCATION
STATION # <u>TKV01</u>	RIVERMILE	STREAM CLASS
LAT	LONG	RIVER BASIN
STORET #		AGENCY
COLLECTED BY <u>AM</u>	DATE <u>4-7-98</u>	LOT #
TAXONOMIST	DATE	SUBSAMPLE TARGET <input type="checkbox"/> 100 <input type="checkbox"/> 200 <input type="checkbox"/> 300 <input type="checkbox"/> Other

Enter Family and/or Genus and Species name on blank line.

Organisms	No.	LS	TI	TCR	Organisms	No.	LS	TI	TCR
Oligochaeta	<u>Oligo</u>	<u>21</u>			Megaloptera				
Hirudinea					Coeloptera				
Isopoda									
Amphipoda	<u>Said</u>	<u>1</u>			Diptera	<u>Chiron</u>	<u>160</u>		
Decapoda	<u>crayfish</u>	<u>3</u>				<u>heulidae</u>	<u>4</u>		
Ephemeroptera									
					Gastropoda				
Plecoptera	<u>plecoptera</u>	<u>1</u>							
					Pelecypoda				
Trichoptera	<u>trichoptera</u>	<u>17</u>			Other				
Hemiptera									

Taxonomic certainty rating (TCR) 1-5: 1=most certain, 5=least certain. If rating is 3-5, give reason (e.g., missing gills). LS=life stage: I=immature; P=pupa; A=adult TI=Taxonomist initials

Total No. Organisms 207

Total No. Taxa 7

TRIBUTARY BIOASSESSMENT BENTHIC INVERTEBRATE SCORING SHEET

Tributary Name: Klinge Valley

Ecoregion: PIEDMONT

Station Code: TKV01

Date Collected: 4.7.98

METRICS

SCORE

Taxa Richness

7

EPT Index

2

% Dominant Taxon

$$\frac{160}{207} \times 100 = 77.39\%$$

Biotic Index: HBI = Sum of $x_i t_i / n$ where

x_i = # individuals in a family
 t_i = tolerance value of family
 n = total # organisms in sample

$$\Sigma 3.85$$

$$\Sigma 7.86$$

Oligo $\frac{21(4)}{207} = 0.41$ 1.01

Gammaridae $\frac{1(3)}{207} = 0.01$ 0.03

Cambaridae $\frac{3(3)}{207} = 0.04$ 0.10

Abundance of Scrapers/
(Scrapers+Filterers)

$$\frac{1}{18} = 0.06$$

$$= 6\%$$

plecoptera $\frac{1(2)}{207} = 0.01$ 0.01

SH, S, CG $\frac{17(3)}{207} = 0.25$ 0.49

Abundance of Shredders/
Total

$$\frac{4}{207} = 0.02$$

$$= 2\%$$

chiron $\frac{100(4)}{207} = 3.09$ 6.18

Hydropsyche+
Chenmatopsyche/
Total EPT

$$\frac{17}{18} = 0.94$$

$$= 94\%$$

Tipulidae $\frac{4(2)}{207} = 0.04$ 0.04

Total EPT ind / Total # ind

$$\frac{18}{207} = 0.09 = 9\%$$

$$\Sigma 3.85$$

$$\Sigma 7.86$$

Crib Sheet for Non-gamefish Processing

Site Name/Code Klinge Valley Brook

Sample Segment 100m above Rock Creek

Date 7-29-98

Biome ss 210 85 50 Total Weight g

Shock Seconds 868 837 764

Species

Count

Anomaly

Canopy Density

1st pass

B.N. DACE

Northern Crt. Chub

Tot. wt. = 210g

2nd pass

B.N. DACE

Tot. wt. = 85g

3rd Pass

B.N. DACE

Tot. wt. = 50g

1st print

N 4.16

S 11.16

E 3.12

W 9.36

MEAN = 5.2

Flow

3 in 0.8

2 in 0.0

3 in 0.2

Notes

temp 21.0

pH 6.9

D.O. 3.8

Conductivity 55

- Almost no rain in past month

- some sewage odors on the

- not many crayfish

Overall Use Support Status Report

Waterbody ID : DCTKV01R
 Waterbody Name: KLINGLE VALLEY
 Waterbody Type: River
 Basin: POTOMAC

Segment Number: 00
 Size: 0.80 Miles

----- Description of the Waterbody -----

KLINGLE VALLEY TRIBUTARY FLOWS THROUGH A RESIDENTIAL AREA AND DISCHARGES INTO ROCK CREEK FROM THE WEST NEAR THE PORTER STREET BRIDGE. THE STREAM'S REACH PARALLELS THE SOUTH SIDE OF KLINGLE ROAD. A WOODED BUFFER OF A FEW HUNDRED FEET COVERS ONE SIDE OF THE STREAM WITH THE REST OF THE 320 ACRE WATERSHED RESIDENTIAL URBAN AREA. NINE (9) OUTFALLS INCLUDING ONE CSO LINE THE STREAM.

THE ABOVE DESCRIPTION WAS TAKEN FROM 'BIOLOGICAL WATER QUALITY OF THE SURFACE STREAMS OF THE DISTRICT OF COLUMBIA,' W.C. BANTA, THE AMERICAN UNIVERSITY, 1993.

Assessment Date: 9802

----- Use Support -----

Designated Use	Fully Supp	Threat	Partial Supp	Not Supported	Not Attained	Not Assessed
OVERALL USE SUPPORT	0.00	0.00	0.00	0.80	0.00	0.00
AQUATIC LIFE SUPPORT	0.00	0.00	0.00	0.00	0.00	0.00
SWIMMABLE	0.00	0.00	0.00	0.00	0.00	0.80
SECONDARY CONTACT REC	0.00	0.00	0.00	0.80	0.00	0.00
FISH CONSUMPTION	0.00	0.00	0.00	0.00	0.00	0.00
NAVIGATION	0.80	0.00	0.00	0.00	0.00	0.00

----- Nonattainment Causes -----

Cause	Size Mag
0100-UNKNOWN TOXICITY	0.80 S
1200-ORGANIC ENRICHMENT/LOW DO	0.80 H
2400-TOTAL TOXICS	0.80 M

----- Nonattainment Sources -----

Source	Size Mag
0400-COMBINED SEWER OVERFLOW	0.80 H
4000-URBAN RUNOFF/STORM SEWERS	0.80 H

----- Comments on the Assessment -----

THE EVALUATION OF KLINGLE CREEK'S AQUATIC LIFE SUPPORT USE IS BASED ON LEVEL III RAPID BIOASSESSMENT PROTOCOLS PERFORMED BY BANTA, 1993. KLINGLE CREEK WAS FOUND TO BE 'PARTIALLY SUPPORTING' OF THIS DESIGNATED USE.

AN AQUATIC LIFE USE DESIGNATION OF 'PARTIALLY SUPPORTING' WAS DETERMINED BY COMPARING THIS STREAMS BIOASSESSMENT OF 31% TO THE EPA SCALE OF BIOLOGICAL CONDITION (PLAFKIN, 1989, 8-19), GIVING A RATING OF 'MODERATELY IMPAIRED'. THIS SCALE RATES 'SEVERELY IMPAIRED' AT 0-19%, 'MODERATELY IMPAIRED' AT

20-50%, 'SLIGHTLY IMPAIRED' AT 51-79% AND 'NONIMPAIRED' AT 80-100%. EPA 305B GUIDELINE ON CRITERIA FOR AQUATIC LIFE USE SUPPORT CLASSIFICATION RECOMMENDS DESIGNATIONS OF 'NOT SUPPORTING' IF SEVERE IMPAIRMENT EXISTS, 'PARTIALLY SUPPORTING' IF SLIGHT TO MODERATE IMPAIRMENT EXISTS AND 'FULLY SUPPORTING' IF NO IMPAIRMENT EXISTS.

THE BIOASSESSMENT SCORED 31% OF THE REFERENCE STREAM AND THE HABITAT ASSESSMENT SCORED 70% WHICH IS IN THE 'MODERATELY IMPAIRED' RANGE. THE DOMINANCE OF ONE TAXON, A CHIRONOMIDS, AND A DECREASE IN BOTH DENSITY AND DIVERSITY RELATIVE TO THE REFERENCE STATION INDICATES TOXIC POLLUTION ALTHOUGH ORGANIC POLLUTION, EUTROPHICATION AND HABITAT DEGRADATION ALL APPEAR TO BE FACTORS IN IMPAIRMENT. THE DO MEASURED 10.8 PPT AT A TEMPERATURE OF 11 DEGREE CELSIUS AND THE CONDUCTIVITY MEASURED 460 MICROMHOS/CM WHILE THE PH MEASURED 6.5. A 1988 BIOASSESSMENT BY JOHNSON FOUND FISH, CRAYFISH, AND SALAMANDERS PRESENT.

DETERMINATION OF THE FISH CONSUMPTION USE WAS BASED ON A PUBLIC HEALTH ADVISORY ISSUED ON NOVEMBER 15, 1994 BY THE D.C. COMMISSIONER OF PUBLIC HEALTH. THE ADVISORY URGES NON-CONSUMPTION OF CATFISH, CARP OR EEL AND LIMITED CONSUMPTION OF OTHER FISH CAUGHT IN ALL DISTRICT OF COLUMBIA WATERS. THIS WATERBODY DID NOT SUPPORT FISH CONSUMPTION CRITERIA.



Government of the District of Columbia

Department of Health

Environmental Health Administration

51 N Street N.E., Room 6039

Washington, DC 20002

Fisheries & Wildlife Division

Phone: (202) 535-2280

Fax: (202) 535-1373

TO: James Collier, Chief
Bureau of Environmental Quality

FROM: M. Jon Siemien, Chief *MJS*
Fisheries Research Branch

DATE: September 25, 2000

SUBJECT: Fisheries Assessment of Klingle Branch

Attached please find an assessment of the Klingle Branch tributary of Rock Creek. As you know there are several problems related to the habitat quality of this stream, and a major factor is the present condition of Klingle road which runs parallel to the stream. This assessment addresses the interrelationship of the road and its affect on the fishery found in the stream.

If you have any questions concerning this assessment please contact me on 202-535-2273.

cc: Ira F. Palmer

FISHERIES ASSESSMENT OF KLINGLE BRANCH IN ROCK CREEK

Performed by: Daniel Ryan, Eric Thadey, Jeffery Zahn
Prepared by: Daniel Ryan
Approved by: M. Jon Siemien
Date submitted: September 18, 2000

OVERVIEW

On Tuesday August 29th, and Friday September 15th, members of the Fisheries and Wildlife Division, and a member of the Water Quality Division performed a fisheries assessment of Klingle Branch. The aim of the assessment was to determine species diversity and abundance in relation to the habitat quality and potential of the stream. Observations were made by walking the stream and sampling for fish species by means of electrofishing with a backpack unit. We started at the confluence of Klingle Branch and Rock Creek, and worked our way upstream until we reached the source where the well-defined stream turned into a wetland area of springs and drainage seeps. Efforts to assess the habitat of the stream demanded that we examine potential environmental impacts such as existing roads, storm drains, and nearby sewer lines.

FINDINGS (Fish Diversity)

Three fish species were captured and identified from our electrofishing efforts in Klingle Branch. Fish were discovered in nearly every substantial pool from the mouth of the creek, upstream for about 269 meters. Here there was a distinct fall line and the elevation of the streambed raised approximately six meters through a series of small falls. Pools for this stream are defined as any area that is at least 15 centimeters deep with a surface area of at least 1600 cm². (It should be noted that these parameters are dependant upon factors such as temperature, precipitation, and runoff.) All pools provide some relief from the direct current of the stream, and all have a sand rubble substrate with larger rocks that concealed many fish that were only discovered by use of the electrofishing equipment. Forty-six pools were identified in this stretch of the stream with all but three containing fish. Each pool that harbored fish contained Blacknose Dace (*Rhinichthys atratulus*) ranging in number from as few as one to as many as 21. In all 254 Blacknose Dace were observed. Five pools revealed six American Eels (*Anguilla rostrata*) in addition to the Dace, and a total of four Creek Chubs (*Semotilus atromaculatus*) were collected from two different pools. Only 1 pool contained all three fish species but a total of six pools had at least 2 species represented (Table 1). No fish species were found above the fall line even in the pools that seemed to mimic the suitable habitats downstream. Other areas that could be classified as riffles or runs did not appear to support any fish life. Further evidence to support the absence of fish in these areas was the number of aquatic insects that were here, coupled with the bottoms of the pools being littered with dead worms and snails; likely washed in from recent rains. These invertebrates were nowhere to be found in the pools that harbored fish, probably because the opportunistic residents had consumed them.

FISHERIES ASSESSMENT OF KLINGLE BRANCH IN ROCK CREEK**RECOMMENDATIONS**

In order to protect and enhance the existing fishery in the Klingle Branch tributary of Rock Creek, the Fisheries Research Branch proposes three alternatives for action. Each alternative involves improvements to the system so that the fishery that is present will not only remain but be enhanced.

1) Klingle road is removed. In this alternative the area surrounding Klingle Branch stream would be restored to as natural condition as possible. In conjunction with the road removal, storm water runoff currently entering directly into the stream from the surrounding roads should be dealt with using the current BMP available. Also, sanitary sewers which are leaking into the stream should be repaired to prevent further stream contamination.

2) Klingle road is left in its present condition. In this alternative the area surrounding Klingle Branch stream would also be restored to as natural condition as possible. Even if the road is left in its current condition, storm water runoff currently entering directly into the stream from the surrounding roads should be dealt with using the current BMP available. Currently, in several places water also runs off the existing road surface directly into the stream. These areas should be eliminated so that any runoff is subjected to BMP before entering the stream. Also, sanitary sewers which are leaking into the stream should be repaired to prevent further stream contamination.

3) Klingle road is totally rebuilt. In this alternative the roadway is totally rebuilt and the area surrounding Klingle Branch stream would be restored to as natural condition as possible. As in the other two alternative all areas of storm-water runoff and sanitary sewer leaks into the stream would be eliminated or repaired. Also, during construction, every precaution should be taken to eliminate the chance of new sediment entering the stream.

Each of the three alternatives proposed have one item in common. In each, the Klingle Branch tributary to Rock Creek would be improved by the elimination of direct storm-water runoff, and the elimination of sanitary sewer contamination of the stream. Klingle Branch, since it acts as a refugia for species found in the mainstem of Rock Creek, is an important system to the overall health of Rock Creek. Due to this every attempt should be made to improve its functioning. To this end the suggested improvements should be made to this stream.

Number of Pools (*)	Number of each species found in pools		
	<i>Rhinichthys atratulus</i>	<i>Anguilla rostrata</i>	<i>Semotilus atromaculatus</i>
28	2		
29	6		
30	19		
31	6		
32	8		
33	6		1
34	-		
35	4		
36	2		
37	15		
38	3		
39	3		
40	4		
41	3		
42	2		
43	3		
44	5		
45	7		
46	12		
Total	254	6	4

The EDR-Radius Map with GeoCheck[®]

Klinge Road
Int of Connecticut Ave
Washington, DC 20008

Inquiry Number: 554815.3s

October 20, 2000



The Source For Environmental Risk Management Data

3530 Post Road
Southport, Connecticut 06490

Nationwide Customer Service

Telephone: 1-800-352-0050
Fax: 1-800-231-6802
Internet: www.edrnet.com

TABLE OF CONTENTS

SECTION	PAGE
Executive Summary	ES-1
Overview Map	2
Detail Map	3
Map Findings Summary	4
Map Findings	5
Orphan Summary	32
Government Records Searched/Data Currency Tracking	GR-1
GEOCHECK ADDENDUM	
Physical Setting Source Addendum	A-1
Physical Setting Source Summary	A-2
Physical Setting Source Map	A-5
Physical Setting Source Map Findings	A-6
Physical Setting Source Records Searched	A-7

Thank you for your business.
Please contact EDR at 1-800-352-0050
with any questions or comments.

Disclaimer Copyright and Trademark Notice

This report contains information obtained from a variety of public and other sources. NO WARRANTY EXPRESSED OR IMPLIED, IS MADE WHATSOEVER IN CONNECTION WITH THIS REPORT. ENVIRONMENTAL DATA RESOURCES INC. SPECIFICALLY DISCLAIMS THE MAKING OF ANY SUCH WARRANTIES, INCLUDING WITHOUT LIMITATION, MERCHANTABILITY OR FITNESS FOR A PARTICULAR USE OR PURPOSE. ALL RISK IS ASSUMED BY THE USER. IN NO EVENT SHALL EDR BE LIABLE TO ANYONE, WHETHER ARISING OUT OF ERRORS OR OMISSIONS, NEGLIGENCE, ACCIDENT OR ANY OTHER CAUSE, FOR ANY LOSS OR DAMAGE, INCLUDING, WITHOUT LIMITATION, SPECIAL, INCIDENTAL, CONSEQUENTIAL, OR EXEMPLARY DAMAGES.

Entire contents copyright 2000 by Environmental Data Resources, Inc. All rights reserved. Reproduction in any media or format, in whole or in part, of any report or map of Environmental Data Resources, Inc., or its affiliates, is prohibited without prior written permission.

EDR and the edr logos are trademarks of Environmental Data Resources, Inc. or its affiliates. All other trademarks used herein are the property of their respective owners.

EXECUTIVE SUMMARY

A search of available environmental records was conducted by Environmental Data Resources, Inc. (EDR). The report meets the government records search requirements of ASTM Standard Practice for Environmental Site Assessments, E 1527-00. Search distances are per ASTM standard or custom distances requested by the user.

TARGET PROPERTY INFORMATION

ADDRESS

INT OF CONNECTICUT AVE
WASHINGTON, DC 20008

COORDINATES

Latitude (North): 38.932200 - 38° 55' 55.9"
Longitude (West): 77.057300 - 77° 3' 26.3"
Universal Transverse Mercator: Zone 18
UTM X (Meters): 321672.2
UTM Y (Meters): 4311057.5

USGS TOPOGRAPHIC MAP ASSOCIATED WITH TARGET PROPERTY

Target Property: 2438077-H1 WASHINGTON WEST, DC MD VA
Source: USGS 7.5 min quad index

TARGET PROPERTY SEARCH RESULTS

The target property was not listed in any of the databases searched by EDR.

DATABASES WITH NO MAPPED SITES

No mapped sites were found in EDR's search of available ("reasonably ascertainable ") government records either on the target property or within the ASTM E 1527-00 search radius around the target property for the following databases:

FEDERAL ASTM STANDARD

NPL..... National Priority List
Delisted NPL..... NPL Deletions /
CERC-NFRAP..... Comprehensive Environmental Response, Compensation, and Liability Information System
CORRACTS..... Corrective Action Report
RCRIS-TSD..... Resource Conservation and Recovery Information System
RCRIS-LOG..... Resource Conservation and Recovery Information System

STATE ASTM STANDARD

SHWS..... State Haz. Waste

FEDERAL ASTM SUPPLEMENTAL

CONSENT..... CONSENT
ROD..... ROD
MLTS..... Material Licensing Tracking System

EXECUTIVE SUMMARY

MINES..... Mines Master Index File
NPL Lien..... NPL Liens
PADS..... PCB Activity Database System
RAATS..... RCRA Administrative Action Tracking System
TRIS..... Toxic Chemical Release Inventory System
TSCA..... Toxic Substances Control Act

STATE OR LOCAL ASTM SUPPLEMENTAL

AST..... AST

SURROUNDING SITES: SEARCH RESULTS

Surrounding sites were identified.

Elevations have been determined from the USGS 1 degree Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified. EDR's definition of a site with an elevation equal to the target property includes a tolerance of +/- 10 feet. Sites with an elevation equal to or higher than the target property have been differentiated below from sites with an elevation lower than the target property (by more than 10 feet). Page numbers and map identification numbers refer to the EDR Radius Map report where detailed data on individual sites can be reviewed.

Sites listed in **bold italics** are in multiple databases.

Unmappable (orphan) sites are not considered in the foregoing analysis.

FEDERAL ASTM STANDARD

CERCLIS: The Comprehensive Environmental Response, Compensation and Liability Information System contains data on potentially hazardous waste sites that have been reported to the USEPA by states, municipalities, private companies and private persons, pursuant to Section 103 of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA). CERCLIS contains sites which are either proposed to or on the National Priorities List (NPL) and sites which are in the screening and assessment phase for possible inclusion on the NPL.

A review of the CERCLIS list, as provided by EDR, and dated 04/16/2000 has revealed that there are 3 CERCLIS sites within approximately 1.5 miles of the target property.

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
UDC OIL SPILL 1997 SITE	4200 CONNECTICUT AVE. N	1/2 - 1 NNW Y92		23
SOAPSTONE CREEK OIL SPILL RESP	4411 CONNECTICUT AVE.,	1 - 2 NNW W101		25
ARCHIBALD GLOVER PARK OUTFALL	42ND & EDMUND STREET, N	1 - 2 WSW 124		31

RCRIS: The Resource Conservation and Recovery Act database includes selected information on sites that generate, store, treat, or dispose of hazardous waste as defined by the Act. The source of this database is the U.S. EPA.

A review of the RCRIS-SQG list, as provided by EDR, and dated 06/21/2000 has revealed that there are 4 RCRIS-SQG sites within approximately 0.5 miles of the target property.

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
UPTOWN CLEANERS	3333 CONNECTICUT AVE NW	0 - 1/8 NNW 87		6

EXECUTIVE SUMMARY

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
INTERNATIONAL VALET	3420 CONNECTICUT AVE NW	1/8 - 1/4NNW B9	6	
CATHEDRAL CUSTOM CLEANERS	3000 CONNECTICUT AVE NW	1/8 - 1/4SSE 14	7	
KM INC EXXON SERVICE STATION	3535 CONNECTICUT AVE NW	1/8 - 1/4NNW G26	10	

ERNS: The Emergency Response Notification System records and stores information on reported releases of oil and hazardous substances. The source of this database is the U.S. EPA.

A review of the ERNS list, as provided by EDR, and dated 08/08/2000 has revealed that there are 2 ERNS sites within approximately 0.5 miles of the target property.

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
3701 CONNECTICUT AVE NW AT AN	3701 CONNECTICUT AVE NW	1/4 - 1/2NNW S70	19	
3701 CT AVE NW APARTMENT BUILD	3701 CT AVE NW APARTMEN	1/4 - 1/2NNW S73	19	

STATE ASTM STANDARD

LUST: The Leaking Underground Storage Tank Incident Reports contain an inventory of reported leaking underground storage tank incidents. The data come from the Department of Consumer and Regulatory Affairs' District of Columbia LUST Cases list.

A review of the LUST list, as provided by EDR, and dated 09/05/2000 has revealed that there are 40 LUST sites within approximately 1.5 miles of the target property.

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
CENTER CATHEDRAL MANSION	3000 CONNECTICUT AV NW	1/8 - 1/4SSE E19	9	
CIRCLE MANAGEMENT PROPERTY	3501 CONNECTICUT AV NW	1/8 - 1/4NNW F21	9	
MARET SCHOOL (PRIVATE)	3000 CATHEDRAL AVE., NW	1/4 - 1/2SSW H33	12	
TEXACO	4225 CONNECTICUT AV NW	1/2 - 1 NNW V93	23	
SAINT SOPHIA CHURCH	36TH / MASS. AVE. NW	1/2 - 1 WSW 96	24	
ALBAN TOWERS	3700 MASSACHUSETTS AV N	1/2 - 1 WSW 97	24	
GARFIELD HOUSE APARTME	2844 WISCONSIN AVE NW	1/2 - 1 WSW 98	24	
CHARLES E SMITH REALTY PROPRT	4411 CONNECTICUT AV NW	1 - 2 NNW W100	25	
CARILLON HOUSE	2500 WISCONSIN AVENUE,	1 - 2 SW 102	25	
ANNUNCIATION CATHOLIC CHURCH	3125 39TH ST NW	1 - 2 W 103	26	
AMOCO OIL CO S/S #3478	2450 WISCONSIN AV NW	1 - 2 SW 104	26	
CONNECTICUT HOUSE	4500 CONNECTICUT AV NW	1 - 2 NNW 105	26	
CATHEDRAL AVENUE COOP	4101 CATHEDRAL AVE., NW	1 - 2 W 109	27	
3900 TUNLAW COOPERATIVE	3900 TUNLAW COOPERATIVE	1 - 2 WSW 110	27	
3900 WATSON PLACE INC.	3900 WATSON PL NW	1 - 2 WSW X111	27	
WATSON PLACE CONDOMI	3900 WATSON PLACE, NW	1 - 2 WSW X112	28	
BERKSHIRE APARTMENTS	4201 MASSACHUSETTS AV N	1 - 2 W 116	29	
ESSEX CONDO	4740 CONNECTICUT AV NW	1 - 2 NNW 125	31	

Lower Elevation	Address	Dist / Dir	Map ID	Page
CONNECTICUT PLAZA APARTMENTS	2901 CONNECTICUT AV NW	1/4 - 1/2SSE M43	14	
CONNECTICUT PLAZA APARTMENTS	2331 CATHEDRAL AV NW	1/4 - 1/2SSE P60	17	
CALVERT WOODLEY APARTMENTS	2601 WOODLEY RD NW	1/2 - 1 SSE 89	22	
CLEVELAND HOUSE	2727 29TH ST NW	1/2 - 1 S 90	22	
CALVERT HOUSE APTS.	2401 CALVERT ST NW	1/2 - 1 SSE 91	23	
ROYAL NETHERLANDS EMBASSY	4200 LINNEAN AV NW	1/2 - 1 N 94	23	

EXECUTIVE SUMMARY

Lower Elevation	Address	Dist / Dir	Map ID	Page
BRITISH EMBASSY	3100 MASSACHUSETTS AV N	1/2 - 1 SSW 95	24	
1788 COLUMBIA ROAD ASSOC LLC	1788 COLUMBIA RD NW	1 - 2 SE 99	25	
CROMWELL APARTMENTS	1515 ODGEN ST NW	1 - 2 E 106	26	
2100 COOPERATIVE ASSOC	2100 19TH ST, NW	1 - 2 SE 107	27	
AMOCO OIL CO S/S #84665	2307 CHAMPLAIN ST NW	1 - 2 SE 108	27	
WASHINGTON HILTON HOTEL & TOWE	1919 CONNECTICUT AV NW	1 - 2 SSE 113	28	
DORCHESTER HOUSE APART	2480 16TH ST, NW	1 - 2 ESE 114	28	
UNIVERSAL NORTH BLDG	1875 CONNECTICUT AVE NW	1 - 2 SSE 115	28	
DIPLOMAT APARTMENTS	2420 16TH ST NW	1 - 2 SE 117	29	
TWIN OAKS APTS - 3800	3800 14TH STREET, NW	1 - 2 ENE 118	29	
AMOCO OIL CO (FORMER)	3037 14TH ST NW	1 - 2 ESE 119	30	
AMERICAN GEOPHYSICAL U	2000 FLORIDA AVE, NW	1 - 2 SSE Y120	30	
PRESIDENT MADISON APPA	1908 FLORIDA AVE., NW	1 - 2 SSE Y121	30	
ADAMS MORGAN FOREIGN CAR SERV	1781 FLORIDA AV NW	1 - 2 SE 122	30	
FAIRMONT LTD PARTNERS	1401 FAIRMONT ST., NW	1 - 2 ESE 123	30	
AMOCO	2600 14TH STREET, NW	1 - 2 ESE 126	31	

UST: The Underground Storage Tank database contains registered USTs. USTs are regulated under Subtitle I of the Resource Conservation and Recovery Act (RCRA). The data come from the Department of Consumer & Regulatory Affairs' D.C. UST Database List.

A review of the UST list, as provided by EDR, and dated 07/19/1999 has revealed that there are 78 UST sites within approximately 0.5 miles of the target property.

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
PARKWAY APARTMENTS	3220 CONNECTICUT AV NW	0 - 1/8 NNW 1	5	
CLEVELAND PARK BRANCH LIBRARY	3300 CONNECTICUT AV NW	0 - 1/8 NNW 2	5	
UNKNOWN	2715 CORTLAND PL NW	0 - 1/8 S 4	5	
UNKNOWN	3400 CONNECTICUT AV NW	0 - 1/8 NNW B6	5	
UNKNOWN	2911 NEWARK ST NW	0 - 1/8 NNW B8	6	
UPTOWN THEATER	3426 CONNECTICUT AV NW	1/8 - 1/4NNW C10	7	
UNKNOWN	3100 CONNECTICUT AV NW	1/8 - 1/4SSE 11	7	
UNKNOWN	3432 CONNECTICUT AV NW	1/8 - 1/4NNW C12	7	
UNKNOWN	3417 CONNECTICUT AV NW	1/8 - 1/4NNW D13	7	
CLEVELAND TERRACE CONDOMINIUM	2755 ORDWAY ST NW	1/8 - 1/4N 15	8	
UNKNOWN	3435 CONNECTICUT AV NW	1/8 - 1/4NNW D16	9	
APARTMENTS	3039 MACOMB ST NW	1/8 - 1/4WNW 17	9	
SMITHSONIAN NAT ZOOLOGICAL PAR	3001 CONNECTICUT AV NW	1/8 - 1/4SSE E18	9	
CENTER CATHEDRAL MANSION	3000 CONNECTICUT AV NW	1/8 - 1/4SSE E19	9	
CIRCLE MANAGEMENT PROPERTY	3501 CONNECTICUT AV NW	1/8 - 1/4NNW F21	9	
UNKNOWN	3520 CONNECTICUT AV NW	1/8 - 1/4NNW F23	10	
DCFD ENGINE CO. #28	3522 CONNECTICUT AV NW	1/8 - 1/4NNW F24	10	
EXXON S/S #2-1806	3535 CONNECTICUT AV NW	1/8 - 1/4NNW G27	11	
QUEBEC HOUSE	2800 PORTER ST NW	1/4 - 1/2NNW 28	11	
UNKNOWN	3029 KLINGLE RD NW	1/4 - 1/2SW 29	11	
UNKNOWN	2927 ORDWAY ST NW	1/4 - 1/2NW 30	11	
UNKNOWN	3000 WOODLEY RD NW	1/4 - 1/2SSW H31	12	
APARTMENT BUILDING	3601 CONNECTICUT AV NW	1/4 - 1/2NNW I35	12	
UNKNOWN	2902 PORTER ST NW	1/4 - 1/2NNW I36	12	
UNKNOWN	3109 WOODLEY RD NW	1/4 - 1/2SW L41	13	
UNKNOWN	2865 29TH ST NW	1/4 - 1/2S N45	14	
UNKNOWN	3126 WOODLEY RD NW	1/4 - 1/2SW L46	14	
ARCADIA APARTNETS	3614 CONNECTICUT AV NW	1/4 - 1/2NNW I47	14	
UNKNOWN	3105 WOODLEY RD NW	1/4 - 1/2SW L48	15	

EXECUTIVE SUMMARY

Equal/Higher Elevation	Address	Dist / Dir	Map ID	Page
GLADY'S CARLEY	2926 PORTER ST NW	1/4 - 1/2NNW	149	15
UNKNOWN	3117 WOODLEY RD NW	1/4 - 1/2SW	O50	15
APARTMENT BUILDING	3616 CONNECTICUT AV NW	1/4 - 1/2NNW	151	15
UNKNOWN	3113 WOODLEY RD NW	1/4 - 1/2SW	O52	15
UNKNOWN	3618 CONNECTICUT AV NW	1/4 - 1/2NNW	153	16
UNKNOWN	3101 WOODLEY RD NW	1/4 - 1/2SW	O54	16
UNKNOWN	3201 WOODLEY RD NW	1/4 - 1/2WSW	55	16
UNKNOWN	3624 CONNECTICUT AV NW	1/4 - 1/2NNW	56	16
UNKNOWN	3502 30TH ST NW	1/4 - 1/2NW	57	16
UNKNOWN	2851 29TH ST NW	1/4 - 1/2S	N58	16
UNKNOWN	3200 WOODLEY RD NW	1/4 - 1/2WSW	59	17
JOS. C. COLQUITT	3100 HAWTHORNE ST NW	1/4 - 1/2SW	61	17
UNKNOWN	3008 32ND ST NW	1/4 - 1/2WSW	Q65	18
UNKNOWN	3006 32ND ST NW	1/4 - 1/2SW	Q66	18
UNKNOWN	3101 GARFIELD ST NW	1/4 - 1/2SW	68	18
3701 CONNECTICUT AV CONDO ASSO	3701 CONNECTICUT AV NW	1/4 - 1/2NNW	S71	19
SEDGWICK GARDENS	3726 CONNECTICUT AV NW	1/4 - 1/2NNW	S74	19
ARTHUR MEIGS	3224 CATHEDRAL AV NW	1/4 - 1/2WSW	75	19
RALPH BECKER	2916 32ND ST NW	1/4 - 1/2SW	T76	20
UNKNOWN	2914 32ND ST NW	1/4 - 1/2SW	T77	20
UNKNOWN	2912 32ND ST NW	1/4 - 1/2SW	T78	20
UNKNOWN	2907 32ND ST NW	1/4 - 1/2SW	T79	20
UNKNOWN	3307 WOODLEY RD NW	1/4 - 1/2WSW	B1	21
UNKNOWN	3200 GARFIELD ST NW	1/4 - 1/2SW	U82	21
UNKNOWN	3201 GARFIELD ST NW	1/4 - 1/2SW	U83	21
UNKNOWN	3301 MACOMB ST NW	1/4 - 1/2W	84	21
MICHAEL MEAGHER	3801 CONNECTICUT AV NW	1/4 - 1/2NNW	86	21
UNKNOWN	3148 CLEVELAND AV NW	1/4 - 1/2SW	87	22
Lower Elevation	Address	Dist / Dir	Map ID	Page
KLINGLE APARTMENTS	2755 MACOMB ST NW	0 - 1/8 NE	A3	5
APARTMENTS	2710 MACOMB ST NW	0 - 1/8 NE	A5	5
PORTER STREET APARTMENT	2501 PORTER ST NW	1/8 - 1/4NE	20	9
UNKNOWN	2929 CONNECTICUT AV NW	1/8 - 1/4SSE	25	10
CONNECTICUT PLAZA APARTMENTS	2915 CONNECTICUT AV NW	1/4 - 1/2SSE	34	12
QUEBEC HOUSE APARTMENTS	2801 QUEBEC ST NW	1/4 - 1/2NNE	J37	13
QUEBEC HOUSE SOUTH APARTMENTS	2800 QUEBEC ST NW	1/4 - 1/2NNE	J38	13
ADAS ISHAEL CONGREGATION	2750 QUEBEC ST NW	1/4 - 1/2NNE	J39	13
UNKNOWN	2829 28TH ST NW	1/4 - 1/2S	K40	13
UNKNOWN	2827 28TH ST NW	1/4 - 1/2S	K42	14
CONNECTICUT PLAZA APARTMENTS	2901 CONNECTICUT AV NW	1/4 - 1/2SSE	M43	14
UNKNOWN	2900 CONNECTICUT AV NW	1/4 - 1/2SSE	M44	14
CONNECTICUT PLAZA APARTMENTS	2331 CATHEDRAL AV NW	1/4 - 1/2SSE	P60	17
UNKNOWN	2323 PORTER ST NW	1/4 - 1/2ENE	62	17
THE CARLTON CONDOMINIUM	2829 CONNECTICUT AV NW	1/4 - 1/2SSE	63	17
UNKNOWN	2301 CATHEDRAL AV NW	1/4 - 1/2SE	P64	18
UNKNOWN	2828 CONNECTICUT AV NW	1/4 - 1/2SSE	R67	18
APARTMENT BUILDING	2824 CONNECTICUT NW	1/4 - 1/2SSE	R69	19
UNKNOWN	2800 WOODLEY RD NW	1/4 - 1/2S	80	20
UNKNOWN	2751 WOODLEY PL NW	1/4 - 1/2SSE	85	21
ST THOMAS THE APOSTLE CHURCH	2665 WOODLEY RD NW	1/4 - 1/2SSE	88	22

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

To maintain currency of the following federal and state databases, EDR contacts the appropriate governmental agency on a monthly or quarterly basis, as required

Elapsed ASTM days: Provides confirmation that this EDR report meets or exceeds the 90 day updating requirement of the ASTM standard

FEDERAL ASTM STANDARD RECORDS

NPL: National Priority List

Source: EPA

Telephone: N/A

National Priorities List (Superfund): The NPL is a subset of CERCLIS and identifies over 1,200 sites for priority cleanup under the Superfund Program. NPL sites may encompass relatively large areas. As such, EDR provides polygon coverage for over 1,000 NPL site boundaries produced by EPA's Environmental Photographic Interpretation Center (EPIC).

Date of Government Version: 06/13/00

Date Made Active at EDR: 07/06/00

Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 06/27/00

Elapsed ASTM days: 9

Date of Last EDR Contact: 08/07/00

DELISTED NPL: NPL Deletions

Source: EPA

Telephone: N/A

The National Oil and Hazardous Substances Pollution Contingency Plan (NCP) establishes the criteria that the EPA uses to delete sites from the NPL. In accordance with 40 CFR 300.425 (e), sites may be deleted from the NPL where no further response is appropriate.

Date of Government Version: 06/13/00

Date Made Active at EDR: 07/06/00

Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 06/27/00

Elapsed ASTM days: 9

Date of Last EDR Contact: 08/07/00

CERCLIS: Comprehensive Environmental Response, Compensation, and Liability Information System

Source: EPA

Telephone: 703-413-0223

CERCLIS contains data on potentially hazardous waste sites that have been reported to the USEPA by states, municipalities, private companies and private persons, pursuant to Section 103 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). CERCLIS contains sites which are either proposed to or on the National Priorities List (NPL) and sites which are in the screening and assessment phase for possible inclusion on the NPL.

Date of Government Version: 04/16/00

Date Made Active at EDR: 08/16/00

Database Release Frequency: Quarterly

Date of Data Arrival at EDR: 06/05/00

Elapsed ASTM days: 72

Date of Last EDR Contact: 08/28/00

CERCLIS-NFRAP: No Further Remedial Action Planned

Source: EPA

Telephone: 703-413-0223

As of February 1995, CERCLIS sites designated "No Further Remedial Action Planned" (NFRAP) have been removed from CERCLIS. NFRAP sites may be sites where, following an initial investigation, no contamination was found, contamination was removed quickly without the need for the site to be placed on the NPL, or the contamination was not serious enough to require Federal Superfund action or NPL consideration. EPA has removed approximately 25,000 NFRAP sites to lift the unintended barriers to the redevelopment of these properties and has archived them as historical records so EPA does not needlessly repeat the investigations in the future. This policy change is part of the EPA's Brownfields Redevelopment Program to help cities, states, private investors and affected citizens to promote economic redevelopment of unproductive urban sites.

Date of Government Version: 04/16/00

Date Made Active at EDR: 08/16/00

Database Release Frequency: Quarterly

Date of Data Arrival at EDR: 06/05/00

Elapsed ASTM days: 72

Date of Last EDR Contact: 08/28/00

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

CORRACTS: Corrective Action Report

Source: EPA
Telephone: 800-424-9346

CORRACTS identifies hazardous waste handlers with RCRA corrective action activity.

Date of Government Version: 04/20/00
Date Made Active at EDR: 08/01/00
Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 06/12/00
Elapsed ASTM days: 50
Date of Last EDR Contact: 09/12/00

RCRIS: Resource Conservation and Recovery Information System

Source: EPA/NTIS
Telephone: 800-424-9346

Resource Conservation and Recovery Information System RCRIS includes selective information on sites which generate, transport, store, treat and/or dispose of hazardous waste as defined by the Resource Conservation and Recovery Act (RCRA)

Date of Government Version: 06/21/00
Date Made Active at EDR: 07/31/00
Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 07/10/00
Elapsed ASTM days: 21
Date of Last EDR Contact: 09/26/00

ERNS: Emergency Response Notification System

Source: EPA/NTIS
Telephone: 202-260-2342

Emergency Response Notification System: ERNS records and stores information on reported releases of oil and hazardous substances

Date of Government Version: 08/08/00
Date Made Active at EDR: 09/06/00
Database Release Frequency: Quarterly

Date of Data Arrival at EDR: 08/11/00
Elapsed ASTM days: 26
Date of Last EDR Contact: 08/02/00

FEDERAL ASTM SUPPLEMENTAL RECORDS

BRS: Biennial Reporting System

Source: EPA/NTIS
Telephone: 800-424-9346

The Biennial Reporting System is a national system administered by the EPA that collects data on the generation and management of hazardous waste. BRS captures detailed data from two groups: Large Quantity Generators (LQG) and Treatment, Storage, and Disposal Facilities

Date of Government Version: 12/31/97
Database Release Frequency: Biennially

Date of Last EDR Contact: 09/18/00
Date of Next Scheduled EDR Contact: 12/18/00

CONSENT: Superfund (CERCLA) Consent Decrees

Source: EPA Regional Offices
Telephone: Varies

Major legal settlements that establish responsibility and standards for cleanup at NPL (Superfund) sites. Released periodically by United States District Courts after settlement by parties to litigation matters

Date of Government Version: N/A
Database Release Frequency: Varies

Date of Last EDR Contact: N/A
Date of Next Scheduled EDR Contact: N/A

ROD: Records Of Decision

Source: NTIS
Telephone: 703-416-0223

Record of Decision: ROD documents mandate a permanent remedy at an NPL (Superfund) site containing technical and health information to aid in the cleanup.

Date of Government Version: 01/31/99
Database Release Frequency: Annually

Date of Last EDR Contact: 08/15/00
Date of Next Scheduled EDR Contact: 10/09/00

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

FINDS: Facility Index System/Facility Identification Initiative Program Summary Report

Source: EPA
Telephone: N/A

Facility Index System. FINDS contains both facility information and 'pointers' to other sources that contain more detail. EDR includes the following FINDS databases in this report: PCS (Permit Compliance System), AIRS (Aerometric Information Retrieval System), DOCKET (Enforcement Docket used to manage and track information on civil judicial enforcement cases for all environmental statutes), FURS (Federal Underground Injection Control), C-DOCKET (Criminal Docket System used to track criminal enforcement actions for all environmental statutes), FFS (Federal Facilities Information System), STATE (State Environmental Laws and Statutes), and PADS (PCB Activity Data System).

Date of Government Version: 10/13/99
Database Release Frequency: Quarterly

Date of Last EDR Contact: 10/10/00
Date of Next Scheduled EDR Contact: 01/08/01

HMIRS: Hazardous Materials Information Reporting System

Source: U.S. Department of Transportation
Telephone: 202-366-4526

Hazardous Materials Incident Report System. HMIRS contains hazardous material spill incidents reported to DOT

Date of Government Version: 06/30/99
Database Release Frequency: Annually

Date of Last EDR Contact: 07/25/00
Date of Next Scheduled EDR Contact: 10/23/00

MLTS: Material Licensing Tracking System

Source: Nuclear Regulatory Commission
Telephone: 301-415-7169

MLTS is maintained by the Nuclear Regulatory Commission and contains a list of approximately 8,100 sites which possess or use radioactive materials and which are subject to NRC licensing requirements. To maintain currency, EDR contacts the Agency on a quarterly basis.

Date of Government Version: 04/23/00
Database Release Frequency: Quarterly

Date of Last EDR Contact: 10/10/00
Date of Next Scheduled EDR Contact: 01/08/01

MINES: Mines Master Index File

Source: Department of Labor, Mine Safety and Health Administration
Telephone: 303-231-5959

Date of Government Version: 08/01/98
Database Release Frequency: Semi-Annually

Date of Last EDR Contact: 10/02/00
Date of Next Scheduled EDR Contact: 01/01/01

NPL LIENS: Federal Superfund Liens

Source: EPA
Telephone: 205-564-4267

Federal Superfund Liens. Under the authority granted the USEPA by the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) of 1980, the USEPA has the authority to file liens against real property in order to recover remedial action expenditures or when the property owner receives notification of potential liability. USEPA compiles a listing of filed notices of Superfund Liens.

Date of Government Version: 10/15/91
Database Release Frequency: No Update Planned

Date of Last EDR Contact: 08/21/00
Date of Next Scheduled EDR Contact: 11/20/00

PADS: PCB Activity Database System

Source: EPA
Telephone: 202-260-3936

PCB Activity Database. PADS identifies generators, transporters, commercial storers and/or brokers and disposers of PCB's who are required to notify the EPA of such activities.

Date of Government Version: 01/01/00
Database Release Frequency: Annually

Date of Last EDR Contact: 08/15/00
Date of Next Scheduled EDR Contact: 11/13/00

RAATS: RCRA Administrative Action Tracking System

Source: EPA
Telephone: 202-564-4104

RCRA Administration Action Tracking System. RAATS contains records based on enforcement actions issued under RCRA pertaining to major violators and includes administrative and civil actions brought by the EPA. For administration actions after September 30, 1995, data entry in the RAATS database was discontinued. EPA will retain a copy of the database for historical records. It was necessary to terminate RAATS because a decrease in agency resources made it impossible to continue to update the information contained in the database.

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

Date of Government Version: 04/17/95
Database Release Frequency: No Update Planned

Date of Last EDR Contact: 09/12/00
Date of Next Scheduled EDR Contact: 12/11/00

TRIS: Toxic Chemical Release Inventory System

Source: EPA
Telephone: 202-260-1531
Toxic Release Inventory System: TRIS identifies facilities which release toxic chemicals to the air, water and land in reportable quantities under SARA Title III Section 313.

Date of Government Version: 12/31/97
Database Release Frequency: Annually

Date of Last EDR Contact: 09/25/00
Date of Next Scheduled EDR Contact: 12/25/00

TSCA: Toxic Substances Control Act

Source: EPA
Telephone: 202-260-1444
Toxic Substances Control Act: TSCA identifies manufacturers and importers of chemical substances included on the TSCA Chemical Substance Inventory list. It includes data on the production volume of these substances by plant site.

Date of Government Version: 12/31/98
Database Release Frequency: Every 4 Years

Date of Last EDR Contact: 09/12/00
Date of Next Scheduled EDR Contact: 12/11/00

DISTRICT OF COLUMBIA ASTM STANDARD RECORDS

SHWS: CERCLIS

Source: EPA
Telephone: 703-413-0223
State Hazardous Waste Sites: State hazardous waste site records are the states' equivalent to CERCLIS. These sites may or may not already be listed on the federal CERCLIS list. Priority sites planned for cleanup using state funds (state equivalent of Superfund) are identified along with sites where cleanup will be paid for by potentially responsible parties. Available information varies by state.

Date of Government Version: 02/24/00
Date Made Active at EDR: 11/11/99
Database Release Frequency: Monthly

Date of Data Arrival at EDR: 08/30/99
Elapsed ASTM days: 73
Date of Last EDR Contact: 09/25/00

LF: N/A

Source: Department of Consumer and Regulatory Affairs
Telephone: 202-767-8512

Solid Waste Facilities/Landfill Sites: SWF/LF type records typically contain an inventory of solid waste disposal facilities or landfills in a particular state. Depending on the state, these may be active or inactive facilities or open dumps that failed to meet RCRA Subtitle D Section 4004 criteria for solid waste landfills or disposal sites.

Date of Government Version: N/A
Date Made Active at EDR: N/A
Database Release Frequency: No Update Planned

Date of Data Arrival at EDR: N/A
Elapsed ASTM days: 0
Date of Last EDR Contact: 08/21/00

LUST: District of Columbia LUST Cases

Source: Department of Health
Telephone: 202-645-6080
Leaking Underground Storage Tank Incident Reports: LUST records contain an inventory of reported leaking underground storage tank incidents. Not all states maintain these records, and the information stored varies by state.

Date of Government Version: 09/05/00
Date Made Active at EDR: 10/19/00
Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 09/12/00
Elapsed ASTM days: 37
Date of Last EDR Contact: 08/28/00

GOVERNMENT RECORDS SEARCHED / DATA CURRENCY TRACKING

UST: D.C. UST Database List

Source: Department of Health
Telephone: 202-645-6080
Registered Underground Storage Tanks: UST's are regulated under Subtitle I of the Resource Conservation and Recovery Act (RCRA) and must be registered with the state department responsible for administering the UST program. Available information varies by state program.

Date of Government Version: 07/19/99
Date Made Active at EDR: 09/22/99
Database Release Frequency: Semi-Annually

Date of Data Arrival at EDR: 07/29/99
Elapsed ASTM days: 55
Date of Last EDR Contact: 08/28/00

DISTRICT OF COLUMBIA ASTM SUPPLEMENTAL RECORDS

AST: List of AST Facilities

Source: Department of Health
Telephone: 202-727-7218

Date of Government Version: 07/19/99
Database Release Frequency: Semi-Annually

Date of Last EDR Contact: 08/28/00
Date of Next Scheduled EDR Contact: 12/18/00

EDR PROPRIETARY DATABASES

Former Manufactured Gas (Coal Gas) Sites: The existence and location of Coal Gas sites is provided exclusively to EDR by Real Property Scan, Inc. ©Copyright 1993 Real Property Scan, Inc. For a technical description of the types of hazards which may be found at such sites, contact your EDR customer service representative.

Disclaimer Provided by Real Property Scan, Inc.

The information contained in this report has predominantly been obtained from publicly available sources produced by entities other than Real Property Scan. While reasonable steps have been taken to insure the accuracy of this report, Real Property Scan does not guarantee the accuracy of this report. Any liability on the part of Real Property Scan is strictly limited to a refund of the amount paid. No claim is made for the actual existence of toxins at any site. This report does not constitute a legal opinion.

HISTORICAL AND OTHER DATABASE(S)

Depending on the geographic area covered by this report, the data provided in these specialty databases may or may not be complete. For example, the existence of wetlands information data in a specific report does not mean that all wetlands in the area covered by the report are included. Moreover, the absence of any reported wetlands information does not necessarily mean that wetlands do not exist in the area covered by the report.

Oil/Gas Pipelines/Electrical Transmission Lines: This data was obtained by EDR from the USGS in 1994. It is related to by USGS as GeoData Digital Line Graphs from 1:100,000 Scale Maps. It was extracted from the transportation category including some oil, but primarily gas pipelines and electrical transmission lines.

Sensitive Receptors: There are individuals deemed sensitive receptors due to their fragile immune systems and special sensitivity to environmental discharges. These sensitive receptors typically include the elderly, the sick, and children. While the location of all sensitive receptors cannot be determined, EDR indicates those buildings and facilities - schools, daycares, hospitals, medical centers, and nursing homes - where individuals who are sensitive receptors are likely to be located.

Flood Zone Data: This data, available in select counties across the country, was obtained by EDR in 1999 from the Federal Emergency Management Agency (FEMA). Data depicts 100-year and 500-year flood zones as defined by FEMA.

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 1999 from the U.S. Fish and Wildlife Service.

GEOCHECK™ - PHYSICAL SETTING SOURCE ADDENDUM

TARGET PROPERTY ADDRESS

KLINGLE ROAD
INT OF CONNECTICUT AVE
WASHINGTON, DC 20008

TARGET PROPERTY COORDINATES

Latitude (North): 38 932201 - 38° 55' 55.9"
Longitude (West): 77 057297 - 77° 3' 26.3"
Universal Transverse Mercator: Zone 18
UTM X (Meters): 321672.2
UTM Y (Meters): 4311057.5

EDR's GeoCheck Physical Setting Source Addendum has been developed to assist the environmental professional with the collection of physical setting source information in accordance with ASTM 1527-00, Section 7.2.3. Section 7.2.3 requires that a current USGS 7.5 Minute Topographic Map (or equivalent, such as the USGS Digital Elevation Model) be reviewed. It also requires that one or more additional physical setting sources be sought when (1) conditions have been identified in which hazardous substances or petroleum products are likely to migrate to or from the property, and (2) more information than is provided in the current USGS 7.5 Minute Topographic Map (or equivalent) is generally obtained, pursuant to local good commercial or customary practice, to assess the impact of migration of recognized environmental conditions in connection with the property. Such additional physical setting sources generally include information about the topographic, hydrologic, hydrogeologic, and geologic characteristics of a site, and wells in the area.

Assessment of the impact of contaminant migration generally has two principle investigative components:

1. Groundwater flow direction, and
2. Groundwater flow velocity.

Groundwater flow direction may be impacted by surface topography, hydrology, hydrogeology, characteristics of the soil, and nearby wells. Groundwater flow velocity is generally impacted by the nature of the geologic strata. EDR's GeoCheck Physical Setting Source Addendum is provided to assist the environmental professional in forming an opinion about the impact of potential contaminant migration.

GEOCHECK™ - PHYSICAL SETTING SOURCE SUMMARY

GROUNDWATER FLOW DIRECTION INFORMATION

Groundwater flow direction for a particular site is best determined by a qualified environmental professional using site-specific well data. If such data is not reasonably ascertainable, it may be necessary to rely on other sources of information, such as surface topographic information, hydrologic information, hydrogeologic data collected on nearby properties, and regional groundwater flow information (from deep aquifers).

TOPOGRAPHIC INFORMATION

Surface topography may be indicative of the direction of surficial groundwater flow. This information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

USGS TOPOGRAPHIC MAP ASSOCIATED WITH THIS SITE

Target Property: 2438077-H1 WASHINGTON WEST, DC MD VA
Source: USGS 7.5 min quad index

GENERAL TOPOGRAPHIC GRADIENT AT TARGET PROPERTY

Target Property: General ENE

Source: General Topographic Gradient has been determined from the USGS 1 Degree Digital Elevation Model and should be evaluated on a relative (not an absolute) basis. Relative elevation information between sites of close proximity should be field verified.

HYDROLOGIC INFORMATION

Surface water can act as a hydrologic barrier to groundwater flow. Such hydrologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

Refer to the Physical Setting Source Map following this summary for hydrologic information (major waterways and bodies of water).

FEMA FLOOD ZONE

Target Property County
WASHINGTON, DC

FEMA Q3 Flood
Data Electronic Coverage
YES

Flood Plain Panel at Target Property:
Additional Panels in search area:

1100010010B / CBPP
1100010020B / CBPP
1100010005B / CBPP
1100010015B / CBPP

NATIONAL WETLAND INVENTORY

NWI Quad at Target Property
WASHINGTON WEST

NWI Electronic
Coverage
YES

HYDROGEOLOGIC INFORMATION

Hydrogeologic information obtained by installation of wells on a specific site can often be an indicator of groundwater flow direction in the immediate area. Such hydrogeologic information can be used to assist the environmental professional in forming an opinion about the impact of nearby contaminated properties or, should contamination exist on the target property, what downgradient sites might be impacted.

GEOCHECK® - PHYSICAL SETTING SOURCE SUMMARY

Site-Specific Hydrogeological Data:

Search Radius: 2.0 miles
 Location Relative to TP: 1 - 2 Miles SE
 Site Name: WASHINGTON PLATING
 Site EPA ID Number: DCD047277801
 Groundwater Flow Direction: S TOWARD THE POTOMAC RIVER
 Inferred Depth to Water: less than 124 feet
 Hydraulic Connection: Information is not available about the hydraulic connection between aquifer(s) underlying the site. The depth to bedrock is less than 124 feet.
 Sole Source Aquifer: A sole source aquifer is present at or near the site
 Data Quality: Information is inferred in the CERCLIS investigation report(s)

AQUIFLOW®

Search Radius: 2.000 Miles.

EDR has developed the AQUIFLOW information System to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted by environmental professionals to regulatory authorities at select sites and has extracted the date of the report, groundwater flow direction as determined hydrogeologically, and the depth to water table.

MAP ID	LOCATION FROM TP	GENERAL DIRECTION GROUNDWATER FLOW
Not Reported		

GROUNDWATER FLOW VELOCITY INFORMATION

Groundwater flow velocity information for a particular site is best determined by a qualified environmental professional using site specific geologic and soil strata data. If such data are not reasonably ascertainable, it may be necessary to rely on other sources of information, including geologic age identification, rock stratigraphic unit and soil characteristics data collected on nearby properties and regional soil information. In general, contaminant plumes move more quickly through sandy-gravelly types of soils than silty-clayey types of soils.

GEOLOGIC INFORMATION IN GENERAL AREA OF TARGET PROPERTY

Geologic information can be used by the environmental professional in forming an opinion about the relative speed at which contaminant migration may be occurring.

GEOLOGIC AGE IDENTIFICATION

ROCK STRATIGRAPHIC UNIT

Geologic Code: Ce
 Era: Paleozoic
 System: Cambrian
 Series: Cambrian

Category: Eugeosynclinal Deposits

Geologic Age and Rock Stratigraphic Unit Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec, Geology of the Conterminous U.S. at 1:2,500,000 Scale - a digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

DOMINANT SOIL COMPOSITION IN GENERAL AREA OF TARGET PROPERTY

The U.S. Department of Agriculture's (USDA) Soil Conservation Service (SCS) leads the National Cooperative Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps. The following information is based on Soil Conservation Service STATSGO data.

No soil data reported.

© 1996 Site Specific Hydrogeologic Data gathered by E.J. Kelly, Inc. (See Appendix Table of W.R. All rights reserved. All of the information and documents provided are those of the client (EPA report #101) who have completed and/or completed a Comprehensive Environmental Response and Liability Assessment System (CERCLIS) investigation.

TC554815 3s Page A-3

GEOCHECK® - PHYSICAL SETTING SOURCE SUMMARY

WELL SEARCH DISTANCE INFORMATION

DATABASE	SEARCH DISTANCE (miles)
Federal USGS	1.000
Federal FRDS PWS	Noarest PWS within 1 mile

FEDERAL USGS WELL INFORMATION


MAP ID	WELL ID	LOCATION FROM TP
No Wells Found		

FEDERAL FRDS PUBLIC WATER SUPPLY SYSTEM INFORMATION

MAP ID	WELL ID	LOCATION FROM TP
No PWS System Found		

Note: PWS System location is not always the same as well location.

PHYSICAL SETTING SOURCE MAP - 554815.3s



- Major Roads
- Contour Lines
- Water Wells
- Public Water Supply Wells
- Groundwater Flow Direction
- (C) Indeterminate Groundwater Flow at Location
- (V) Groundwater Flow Varies at Location
- Cluster of Multiple Icons

- Earthquake epicenter, Richter 5 or greater
- Closest Hydrogeological Data

GEOCHECK® - PHYSICAL SETTING SOURCE MAP FINDINGS RADON

AREA RADON INFORMATION

1996 Radon Information:

Zip Code: 20008

Number of sites tested: 644

Maximum Radon Level: 48.1 pCi/L

Minimum Radon Level: 0.8 pCi/L

pCi/L <4	pCi/L 4-10	pCi/L 10-20	pCi/L 20-50	pCi/L 50-100	pCi/L >100
514 (79.81%)	108 (16.77%)	19 (2.95%)	3 (0.47%)	0 (0.00%)	0 (0.00%)

TARGET PROPERTY: Kling Road
 ADDRESS: Int of Connecticut Ave
 STATE/ZIP: Washington DC 20008
 PHONE: 38.9322 / 77.0573

CUSTOMER: Louis Berger & Associates
 CONTACT: Melissa Bird
 INQUIRY #: 554815.3s
 DATE: October 20, 2000 1:30 pm

PHYSICAL SETTING SOURCE RECORDS SEARCHED

HYDROLOGIC INFORMATION

Flood Zone Data: This data, available in select counties across the country, was obtained by EDR in 1999 from the Federal Emergency Management Agency (FEMA). Data depicts 100-year and 500-year flood zones as defined by FEMA.

NWI: National Wetlands Inventory. This data, available in select counties across the country, was obtained by EDR in 1999 from the U.S. Fish and Wildlife Service.

HYDROGEOLOGIC INFORMATION

AQUIFLOW[®] Information System

Source: EDR proprietary database of groundwater flow information.

EDR has developed the AQUIFLOW Information System (AIS) to provide data on the general direction of groundwater flow at specific points. EDR has reviewed reports submitted to regulatory authorities at select sites and has extracted the data of the report, hydrogeologically determined groundwater flow direction and depth to water table information.

GEOLOGIC INFORMATION

Geologic Age and Rock Stratigraphic Unit

Source: P.G. Schruben, R.E. Arndt and W.J. Bawiec. Geology of the Conterminous U.S. at 1:2,500,000 Scale - A digital representation of the 1974 P.B. King and H.M. Beikman Map, USGS Digital Data Series DDS - 11 (1994).

STATSGO: State Soil Geographic Database

The U.S. Department of Agriculture's (USDA) Soil Conservation Service (SCS) leads the national Cooperative Soil Survey (NCSS) and is responsible for collecting, storing, maintaining and distributing soil survey information for privately owned lands in the United States. A soil map in a soil survey is a representation of soil patterns in a landscape. Soil maps for STATSGO are compiled by generalizing more detailed (SSURGO) soil survey maps.

ADDITIONAL ENVIRONMENTAL RECORD SOURCES

FEDERAL WATER WELLS

PWS: Public Water Systems

Source: EPA/Office of Drinking Water

Telephone: 202-260-2805

Public Water System data from the Federal Reporting Data System. A PWS is any water system which provides water to at least 25 people for at least 60 days annually. PWSs provide water from wells, rivers and other sources.

PWS ENF: Public Water Systems Violation and Enforcement Data

Source: EPA/Office of Drinking Water

Telephone: 202-260-2805

Violation and Enforcement data for Public Water Systems from the Safe Drinking Water Information System (SDWIS) after August 1995. Prior to August 1995, the data came from the Federal Reporting Data System (FRDS).

USGS Water Wells: In November 1971 the United States Geological Survey (USGS) implemented a national water resource information tracking system. This database contains descriptive information on sites where the USGS collects or has collected data on surface water and/or groundwater. The groundwater data includes information on more than 900,000 wells, springs, and other sources of groundwater.

RADON

Area Radon Information: The National Radon Database has been developed by the U.S. Environmental Protection Agency (USEPA) and is a compilation of the EPA/State Residential Radon Survey and the National Residential Radon Survey. The study covers the years 1986 - 1992. Where necessary data has been supplemented by information collected at private sources such as universities and research institutions.

PHYSICAL SETTING SOURCE RECORDS SEARCHED

EPA Radon Zones: Sections 307 & 309 of IRAA directed EPA to list and identify areas of U.S. with the potential for elevated indoor radon levels.

Statistical Summary Readings: Radon readings for Delaware, D.C., Maryland, Pennsylvania, Virginia and West Virginia EPA Region 3.

OTHER

Epicenters: World earthquake epicenters, Richter 5 or greater.

Source: Department of Commerce, National Oceanic and Atmospheric Administration

EXECUTIVE SUMMARY

FEDERAL ASTM SUPPLEMENTAL

FINDS: The Facility Index System contains both facility information and "pointers" to other sources of information that contain more detail. These include: RCRIIS; Permit Compliance System (PCS); Aerometric Information Retrieval System (AIRS); FATES (FIFRA [Federal Insecticide Fungicide Rodenticide Act] and TSCA Enforcement System, FTTS [FIFRA/TSCA Tracking System]; CERCLIS; DOCKET (Enforcement Docket used to manage and track information on civil judicial enforcement cases for all environmental statutes); Federal Underground Injection Control (FURIS); Federal Reporting Data System (FRDS); Surface Impoundments (SIA); TSCA Chemicals in Commerce Information System (CICS); PADS; RCRA-J (medical waste transporters/disposers); TRIS; and TSCA. The source of this database is the U.S. EPA/NTIS.

A review of the FINDS list, as provided by EDR, and dated 10/13/1999 has revealed that there are 6 FINDS sites within approximately 0.5 miles of the target property.

<u>Equal/Higher Elevation</u>	<u>Address</u>	<u>Dist / Dir</u>	<u>Map ID</u>	<u>Page</u>
UPTOWN CLEANERS	3333 CONNECTICUT AVE NW	0 - 1/8 NNW B7		6
INTERNATIONAL VALET	3420 CONNECTICUT AVE NW	1/8 - 1/4NNW B9		6
CATHEDRAL CUSTOM CLEANERS	3000 CONNECTICUT AVE NW	1/8 - 1/4 SSE 14		7
PARKPLACE CLEANERS	3504 CONNECTICUT AVE. N	1/8 - 1/4NNW F22		10
KM INC EXXON SERVICE STATION	3535 CONNECTICUT AVE NW	1/8 - 1/4NNW G26		10
MARET SCHOOL INC	3000 CATHEDRAL AVE	1/4 - 1/2 SSW H32		12

HMIRS: The Hazardous Materials Incident Report System contains hazardous material spill incidents reported to the Department of Transportation. The source of this database is the U.S. EPA.

A review of the HMIRS list, as provided by EDR, and dated 06/30/1999 has revealed that there is 1 HMIRS site within approximately 0.5 miles of the target property.

<u>Equal/Higher Elevation</u>	<u>Address</u>	<u>Dist / Dir</u>	<u>Map ID</u>	<u>Page</u>
Not reported	3002 RODMAN ST	1/4 - 1/2 NNW S72		19

EXECUTIVE SUMMARY

Due to poor or inadequate address information, the following sites were not mapped:


Site Name

GLOVER BRIDGE SITE
SOAP STONE CREEK
UNKNOWN
UNKNOWN
BURNT WOOD ROAD NE AT FLORIDA AVE.
NATIONAL ARBORETUM BLADENSBURG ROAD NE
PARK ROAD AND BEACH DRIVE

Database(s)

CERCLIS
CERC-NFRAP
UST
UST
ERNS
ERNS
ERNS

OVERVIEW MAP - 554815.3s - Louis Berger & Associates




- Target Property
- ▲ Sites at elevations higher than or equal to the target property
- ◆ Sites at elevations lower than the target property
- ▲ Coal Gasification Sites (if requested)
- National Priority List Sites
- Landfill Sites

- Power transmission lines
- Oil & Gas pipelines
- 100-year flood zone
- 500-year flood zone
- Wetlands per National Wetlands Inventory

TARGET PROPERTY: Kingle Road
ADDRESS: Int of Connecticut Ave
WASHINGTON DC 20008
STATE/ZIP: 38 9322 / 77 0573
NG:

CUSTOMER: Louis Berger & Associates
CONTACT: Melissa Bird
INQUIRY #: 554815.3s
DATE: October 20, 2000 1:29 pm

DETAIL MAP - 554815.3s - Louis Berger & Associates



- Target Property
- ▲ Sites at elevations higher than or equal to the target property
- ◆ Sites at elevations lower than the target property
- ▲ Coal Gasification Sites (if requested)
- ▲ Sensitive Receptors
- National Priority List Sites
- Landfill Sites

- Power transmission lines
- Oil & Gas pipelines
- 100-year flood zone
- 500-year flood zone

TARGET PROPERTY: Kingle Road
ADDRESS: Int of Connecticut Ave
WASHINGTON DC 20008
CITY/STATE/ZIP: 38.9322 / 77.0573
LAT/LONG:

CUSTOMER: Louis Berger & Associates
CONTACT: Melissa Bird
INQUIRY #: 554815.3s
DATE: October 20, 2000 1:30 pm

MAP FINDINGS SUMMARY

Database	Target Property	Search Distance (Miles)	< 1/8	1/8 - 1/4	1/4 - 1/2	1/2 - 1	> 1	Total Plotted
FEDERAL ASTM STANDARD								
NPL		1.500	0	0	0	0	0	0
Delisted NPL		1.500	0	0	0	0	0	0
CERCLIS		1.500	0	0	0	1	2	3
CERC-NFRAP		1.500	0	0	0	0	0	0
CORRACTS		1.500	0	0	0	0	0	0
RCRIS-TSD		1.500	0	0	0	0	0	0
RCRIS Lg. Quan. Gen.		0.500	0	0	0	NR	NR	0
RCRIS Sm. Quan. Gen.		0.500	1	3	0	NR	NR	4
ERHS		0.500	0	0	2	NR	NR	2
STATE ASTM STANDARD								
State Haz. Waste		1.000	0	0	0	0	NR	0
State Landfill		N/A	N/A	N/A	N/A	N/A	N/A	N/A
LUST		1.500	0	2	3	9	26	40
UST		0.500	7	15	56	NR	NR	78
FEDERAL ASTM SUPPLEMENTAL								
CONSENT		1.500	0	0	0	0	0	0
ROD		1.500	0	0	0	0	0	0
FINDS		0.500	1	4	1	NR	NR	6
HMIRS		0.500	0	0	1	NR	NR	1
MLTS		0.500	0	0	0	NR	NR	0
MINES		0.500	0	0	0	NR	NR	0
NPL Liens		0.500	0	0	0	NR	NR	0
PADS		0.500	0	0	0	NR	NR	0
RAATS		TP	NR	NR	NR	NR	NR	0
TRIS		0.500	0	0	0	NR	NR	0
TSCA		0.500	0	0	0	NR	NR	0
STATE OR LOCAL ASTM SUPPLEMENTAL								
AST	TP		NR	NR	NR	NR	NR	0
EDR PROPRIETARY DATABASES								
Coal Gas		N/A	N/A	N/A	N/A	N/A	N/A	N/A
AQUIFLOW - see EDR Physical Setting Source Addendum								

TP = Target Property

NR = Not Requested at this Search Distance

* Sites may be listed in more than one database

Map ID
Direction
Distance
Distance (ft.)
Elevation

MAP FINDINGS

Database(s)

EDR ID Number
EPA ID Number

Coal Gas Site Search: EDR does not presently have coal gas site information available in this state.

1 NNW < 1/8 60 Higher	PARKWAY APARTMENTS 3220 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U002109857 N/A
	UST: Facility ID: 3-001782 Owner: DC FIRE PREVENTION BRANCH		
2 NNW < 1/8 360 Higher	CLEVELAND PARK BRANCH LIBRARY 3300 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054932 N/A
	UST: Facility ID: 3-001804 Owner: D.C. PUBLIC LIBRARY		
A3 NE < 1/8 450 Lower	KLINGLE APARTMENTS 2755 MACOMB ST NW WASHINGTON, DC 20005	UST	U002110010 N/A
	UST: Facility ID: 3-004167 Owner: GEORGE ECONOMOS & TRUST		
4 South < 1/8 463 Higher	UNKNOWN 2715 CORTLAND PL NW WASHINGTON, DC 20008	UST	U003054956 N/A
	UST: Facility ID: 3-001871 Owner: DC FIRE PREVENTION BRANCH		
A5 NE < 1/8 496 Lower	APARTMENTS 2710 MACOMB ST NW WASHINGTON, DC 20008	UST	U003055007 N/A
	UST: Facility ID: 3-004165 Owner: WILLIAM C. SMITH COMPANY		
B6 NNW < 1/8 564 Higher	UNKNOWN 3400 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054885 N/A

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	MAP FINDINGS		
	UNKNOWN (Continued)		U003054885
	UST Facility ID: 3-001612 Owner: DC FIRE PREVENTION BRANCH		
B7 NNW < 1/8 601 Higher	UPTOWN CLEANERS 3333 CONNECTICUT AVE NW WASHINGTON, DC 20008	RCRIS-SQG FINDS	1000344076 DCD0670918206
	RCRIS: Owner: 3333 CON CLEANERS INC (215) 555-1212 Contact: MICHAEL CUNNINGHAM (202) 363-5050 Record Date: 11/08/1985 Classification: Conditionally Exempt Small Quantity Generator Used Oil Recyc: No Violation Status: No violations found		
	FINDS: Other Potentially Environmental Activity Identified at Site: AIRS Facility System (AIRS/AFS)		
B8 NNW < 1/8 825 Higher	UNKNOWN 2911 NEWARK ST NW WASHINGTON, DC 20008	UST	U003055195 N/A
	UST: Facility ID: 3-005331 Owner: DC FIRE PREVENTION BRANCH		
B9 NNW 1/8-1/4 875 Higher	INTERNATIONAL VALET 3420 CONNECTICUT AVE NW WASHINGTON, DC 20008	RCRIS-SQG FINDS	1000216659 DCD044758159
	RCRIS: Owner: SUH, JOO BOK (215) 555-1212 Contact: J SUH (202) 966-2966 Record Date: 01/26/1994 Classification: Conditionally Exempt Small Quantity Generator		

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	MAP FINDINGS		
	INTERNATIONAL VALET (Continued)		1000216659
	Used Oil Recyc: No Violation Status: No violations found		
C10 NNW 1/8-1/4 709 Higher	UPTOWN THEATER 3426 CONNECTICUT AV NW DC 20008	UST	U003294470 N/A
	UST: Facility ID: 3-001805 Owner: CIRCLE COMPANIES		
11 SSE 1/8-1/4 726 Higher	UNKNOWN 3100 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054916 N/A
	UST: Facility ID: 3-001781 Owner: 3024 TILDEN ST NW		
C12 NNW 1/8-1/4 743 Higher	UNKNOWN 3432 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054917 N/A
	UST: Facility ID: 3-001784 Owner: 3024 TILDEN ST NW		
D13 NNW 1/8-1/4 858 Higher	UNKNOWN 3417 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054886 N/A
	UST: Facility ID: 3-001613 Owner: 3024 TILDEN ST NW		
14 SSE 1/8-1/4 870 Higher	CATHEDRAL CUSTOM CLEANERS 3000 CONNECTICUT AVE NW WASHINGTON, DC 20008	RCRIS-SQG FINDS	1000240230 DCD083503458

Map ID
Direction
Distance
Distance (ft)
Elevation

MAP FINDINGS

Database(s)

EDR ID Number
EPA ID Number

CATHEDRAL CUSTOM CLEANERS (Continued)

1000240230

ACRIS

Owner: BERNSTEIN MGMT
(202) 363-6301

Contact: CHA H LEE
(201) 234-9198

Record Date: 11/08/1985

Classification: Small Quantity Generator

Used Oil Recyc: No

Violation Status: Violations exist

Regulation Violated: Not reported
Area of Violation: Generator All Requirements
Date Violation Determined: 05/05/1989
Priority of Violation: Low
Schedule Date to Achieve Compliance: 07/02/1989
Actual Date Achieved Compliance: 05/17/1994

Enforcement Action: Written Informal
Enforcement Action Date: 06/02/1989
Proposed Monetary Penalty: Not reported
Final Monetary Penalty: Not reported

Regulation Violated: Not reported
Area of Violation: Generator All Requirements
Date Violation Determined: 03/06/1992
Priority of Violation: Low
Schedule Date to Achieve Compliance: 04/01/1992
Actual Date Achieved Compliance: 03/25/1992

Enforcement Action: Written Informal
Enforcement Action Date: 03/06/1992
Proposed Monetary Penalty: Not reported
Final Monetary Penalty: Not reported

There are 2 violation record(s) reported at this site

Evaluation: Non-Financial Record Review
Compliance Evaluation Inspection (CEI)

Area of Violation: Generator All Requirements
Generator All Requirements

Date of Compliance: 03/25/1992
05/17/1994

FINDS:

Other Pertinent Environmental Activity Identified at Site:
AIRS Facility System (AIRS/AFS)

15
North
1/8-1/4
881
Higher

CLEVELAND TERRACE CONDOMINIUM
2755 ORDWAY ST NW
WASHINGTON, DC 20008

UST

U003055184
N/A

UST:

Facility ID: 3-005144
Owner: CLEVELAND TERRACE CONDO ASSOC

Map ID
Direction
Distance
Distance (ft)
Elevation

MAP FINDINGS

Site

Database(s)

EDR ID Number
EPA ID Number

D16
NNW
1/8-1/4
914
Higher

UNKNOWN
3435 CONNECTICUT AV NW
WASHINGTON, DC 20008

UST

U003054918
N/A

UST:
Facility ID: 3-001285
Owner: 3024 TILDEN ST NW

17
WNW
1/8-1/4
1033
Higher

APARTMENTS
3039 MACOMB ST NW
WASHINGTON, DC 20008

UST

U003055006
N/A

UST:
Facility ID: 3-004164
Owner: WILLIAM C. SMITH COMPANY

E18
SSE
1/8-1/4
1052
Higher

SMITHSONIAN NAT ZOOLOGICAL PARK
3001 CONNECTICUT AV NW OFFICE OF FACILIT
WASHINGTON, DC 20008

UST

U003111902
N/A

UST:
Facility ID: 3-000670
Owner: SMITHSONIAN NAT ZOOLOGICAL PARK

E19
SSE
1/8-1/4
1052
Higher

CENTER CATHEDRAL MANSION
3000 CONNECTICUT AV NW
WASHINGTON, DC 20008

UST

U003054825
N/A

UST:
Case Number: 97081
Facility Status: Case Open
Product: H
UST:
Facility ID: 3-000163
Owner: COLUMBIA REALTY VENTURE

20
NE
1/8-1/4
1104
Lower

PORTER STREET APARTMENT
2501 PORTER ST NW
WASHINGTON, DC 20008

UST

U003055187
N/A

UST:
Facility ID: 3-005235
Owner: SMITH PROPERTY HOLDINGS 34 P

F21
NNW
1/8-1/4
1110
Higher

CIRCLE MANAGEMENT PROPERTY
3501 CONNECTICUT AV NW
WASHINGTON, DC 20008

UST

U002109699
N/A

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	MAP FINDINGS		
	CIRCLE MANAGEMENT PROPERTY (Continued)		U002109699
	UST: Case Number: 91039 Facility Status: Case Closed Product: G UST: Facility ID: 3-000118 Owner: CIRCLE MANAGEMENT INC		
F22 NNW 1/8-1/4 1133 Higher	PARKPLACE CLEANERS 3504 CONNECTICUT AVE. N.W. WASHINGTON, DC 20008	FINDS	1001879205 0000-0791-21
F23 NNW 1/8-1/4 1225 Higher	UNKNOWN 3520 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054921 N/A
	UST: Facility ID: 3-001788 Owner: DC FIRE PREVENTION BRANCH		
F24 NNW 1/8-1/4 1236 Higher	DCFD ENGINE CO. #28 3522 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054833 N/A
	UST: Facility ID: 3-000299 Owner: DC FIRE DEPARTMENT		
25 SSE 1/8-1/4 1293 Lower	UNKNOWN 2929 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003053844 N/A
	UST: Facility ID: 1-001611 Owner: DC FIRE PREVENTION BRANCH		
G26 NNW 1/8-1/4 1304 Higher	KM INC EXXON SERVICE STATION 3535 CONNECTICUT AVE NW WASHINGTON, DC 20008	RCRIS-SQG FINDS	1000732369 DCD983970526

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	MAP FINDINGS		
	KM INC EXXON SERVICE STATION (Continued)		1000732369
	RCRIS: Owner: KM INC (202) 364-6360 Contact: WILLIAM MILFORD (202) 364-6360 Record Date: 09/08/1992 Classification: Small Quantity Generator Used Oil Recyc: No Violation Status: No violations found		
	FINDS: Other Pertinent Environmental Activity Identified at Site: AIRS Facility System (AIRS/AFS)		
G27 NNW 1/8-1/4 1304 Higher	EXXON S/S #2-1806 3535 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U002109720 N/A
	UST: Facility ID: 3-000372 Owner: EXXON COMPANY USA		
28 NNW 1/4-1/2 1347 Higher	QUEBEC HOUSE 2800 PORTER ST NW WASHINGTON, DC 20008	UST	U002110280 N/A
	UST: Facility ID: 3-005236 Owner: DC FIRE PREVENTION BRANCH		
29 SW 1/4-1/2 1389 Higher	UNKNOWN 3029 KLINGLE RD NW WASHINGTON, DC 20008	UST	U003054868 N/A
	UST: Facility ID: 3-001100 Owner: DC FIRE PREVENTION BRANCH		
30 NW 1/4-1/2 1445 Higher	UNKNOWN 2927 ORDWAY ST NW WASHINGTON, DC 20008	UST	U003055183 N/A
	UST: Facility ID: 3-005143 Owner: UNKNOWN		

Map ID Direction Distance Distance (ft.) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
H31 SSW 1/4-1/2 1458 Higher	UNKNOWN 3000 WOODLEY RD NW WASHINGTON, DC 20008 UST: Facility ID: 3-005058 Owner: DC FIRE PREVENTION BRANCH	UST	U003055164 N/A
H32 SSW 1/4-1/2 1459 Higher	MARET SCHOOL INC 3000 CATHEDRAL AVE WASHINGTON, DC 20008 FINDS: Other Pertinent Environmental Activity Identified at Site: Enforcement Docket System (DOCKET)	FINDS	1001626920 03-86-0214-0
H33 SSW 1/4-1/2 1459 Higher	MARET SCHOOL (PRIVATE) 3000 CATHEDRAL AVE., NW WASHINGTON, DC 20008 LUST: Case Number: 99062 Facility Status: Case Open Product: H	LUST	1001276719 N/A
34 SSE 1/4-1/2 1515 Lower	CONNECTICUT PLAZA APARTMENTS 2915 CONNECTICUT AV NW DC 20008 UST: Facility ID: 1-001779 Owner: CONNECTICUT PLAZA APARTMENTS	UST	U003294394 N/A
135 NNW 1/4-1/2 1671 Higher	APARTMENT BUILDING 3601 CONNECTICUT AV NW WASHINGTON, DC 20008 UST: Facility ID: 3-001790 Owner: DC FIRE PREVENTION BRANCH	UST	U002109864 N/A
136 NNW 1/4-1/2 1679 Higher	UNKNOWN 2902 PORTER ST NW WASHINGTON, DC 20008	UST	U003055188 N/A

Map ID Direction Distance Distance (ft.) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
	UNKNOWN (Continued)		U003055188
	UST: Facility ID: 3-005238 Owner: DC FIRE PREVENTION BRANCH		
J37 NNE 1/4-1/2 1691 Lower	QUEBEC HOUSE APARTMENTS 2801 QUEBEC ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-004588 Owner: CAFRITZ LEASING MANAGEMENT	UST	U002110138 N/A
J38 NNE 1/4-1/2 1691 Lower	QUEBEC HOUSE SOUTH APARTMENTS 2800 QUEBEC ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-000100 Owner: CAFRITZ LEASING MANAGEMENT	UST	U003054818 N/A
J39 NNE 1/4-1/2 1712 Lower	ADAS ISRAEL CONGREGATION 2750 QUEBEC ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-004587 Owner: DC FIRE PREVENTION BRANCH	UST	U002110137 N/A
K40 South 1/4-1/2 1726 Lower	UNKNOWN 2829 28TH ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-004301 Owner: 2829 28TH STREET L.L.C.	UST	U003055026 N/A
L41 SW 1/4-1/2 1734 Higher	UNKNOWN 3109 WOODLEY RD NW WASHINGTON, DC 20008 UST: Facility ID: 3-005061 Owner: UNKNOWN	UST	U003055167 N/A

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
MAP FINDINGS			
K42 South 1/4-1/2 1737 Lower	UNKNOWN 2827 28TH ST NW WASHINGTON, DC 20008	UST	U003055025 N/A
	UST: Facility ID: 3 004298 Owner: UNKNOWN		
M43 SSE 1/4-1/2 1738 Lower	CONNECTICUT PLAZA APARTMENTS 2901 CONNECTICUT AV NW WASHINGTON, DC 20008	UST LUST	U002107639 N/A
	LUST: Case Number: 93020 Facility Status: Case Closed Product: H		
	UST: Facility ID: 1-001610 Owner: CONNECTICUT PLAZA APARTMENTS		
M44 SSE 1/4-1/2 1738 Lower	UNKNOWN 2900 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054915 N/A
	UST: Facility ID: 3-001778 Owner: DC FIRE PREVENTION BRANCH		
N45 South 1/4-1/2 1740 Higher	UNKNOWN 2865 29TH ST NW WASHINGTON, DC 20008	UST	U003055028 N/A
	UST: Facility ID: 3-004308 Owner: UNKNOWN		
L46 SW 1/4-1/2 1755 Higher	UNKNOWN 3126 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055170 N/A
	UST: Facility ID: 3-005064 Owner: UNKNOWN		
M47 NNW 1/4-1/2 1755 Higher	ARCADIA APARTMENTS 3614 CONNECTICUT AV NW DC 20008	UST	U003294464 N/A

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
MAP FINDINGS			
	ARCADIA APARTMENTS (Continued)		U003294464
	UST: Facility ID: 3-001791 Owner: BORGER MANAGEMENT INC		
L48 SW 1/4-1/2 1757 Higher	UNKNOWN 3105 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055166 N/A
	UST: Facility ID: 3-005060 Owner: UNKNOWN		
M48 NNW 1/4-1/2 1765 Higher	GLADYS CARLEY 2926 PORTER ST NW WASHINGTON, DC 20008	UST	U003055189 N/A
	UST: Facility ID: 3-005239 Owner: ROGER W & GLADYS CARLEY		
O50 SW 1/4-1/2 1766 Higher	UNKNOWN 3117 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055169 N/A
	UST: Facility ID: 3-005063 Owner: UNKNOWN		
I51 NNW 1/4-1/2 1767 Higher	APARTMENT BUILDING 3616 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U002109866 N/A
	UST: Facility ID: 3-001792 Owner: DC FIRE PREVENTION BRANCH		
O52 SW 1/4-1/2 1771 Higher	UNKNOWN 3113 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055168 N/A
	UST: Facility ID: 3-005062 Owner: UNKNOWN		

Map ID Direction Distance Distance (ft.) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
153 NNW 1/4-1/2 1780 Higher	UNKNOWN 3618 CONNECTICUT AV NW WASHINGTON, DC 20008 UST: Facility ID: 3-001787 Owner: DC FIRE PREVENTION BRANCH	UST	U003054920 N/A
054 SW 1/4-1/2 1788 Higher	UNKNOWN 3101 WOODLEY RD NW WASHINGTON, DC 20008 UST: Facility ID: 3-005059 Owner: UNKNOWN	UST	U003055165 N/A
55 WSW 1/4-1/2 1805 Higher	UNKNOWN 3201 WOODLEY RD NW WASHINGTON, DC 20008 UST: Facility ID: 3-005070 Owner: UNKNOWN	UST	U003055176 N/A
56 NNW 1/4-1/2 1816 Higher	UNKNOWN 3624 CONNECTICUT AV NW WASHINGTON, DC 20008 UST: Facility ID: 3-001786 Owner: DC FIRE PREVENTION BRANCH	UST	U003054919 N/A
57 NW 1/4-1/2 1842 Higher	UNKNOWN 3502 30TH ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-003627 Owner: UNKNOWN	UST	U003054998 N/A
N58 South 1/4-1/2 1866 Higher	UNKNOWN 2851 29TH ST NW WASHINGTON, DC 20008	UST	U003055027 N/A

Map ID Direction Distance Distance (ft.) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
	UNKNOWN (Continued)		U003055027
	UST: Facility ID: 3-004307 Owner: UNKNOWN		
59 WSW 1/4-1/2 1934 Higher	UNKNOWN 3200 WOODLEY RD NW WASHINGTON, DC 20008 UST: Facility ID: 3-005052 Owner: UNKNOWN	UST	U003055158 N/A
P60 SSE 1/4-1/2 1955 Lower	CONNECTICUT PLAZA APARTMENTS 2331 CATHEDRAL AV NW WASHINGTON, DC 20008 LUST: Case Number: 93022 Facility Status: Case Closed Product: H UST: Facility ID: 1-001671 Owner: CONNECTICUT PLAZA APARTMENTS	UST LUST	U002107663 N/A
61 SW 1/4-1/2 1976 Higher	JOS. C. COLQUITT 3100 HAWTHORNE ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-004082 Owner: JOS. C. COLQUITT	UST	U002110006 N/A
62 ENE 1/4-1/2 2003 Lower	UNKNOWN 2323 PORTER ST NW WASHINGTON, DC 20008 UST: Facility ID: 3-005233 Owner: UNKNOWN	UST	U003055185 N/A
63 SSE 1/4-1/2 2017 Lower	THE CARLTON CONDOMINIUM 2829 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003053878 N/A

Map ID	Direction	Distance	Distance (ft.)	Elevation	Site	Database(s)	EDR ID Number	EPA ID Number
MAP FINDINGS								
					THE CARLTON CONDOMINIUM (Continued)		U003053876	
					UST:			
					Facility ID:	1-001777		
					Owner:	THE CARLTON CONDOMINIUM		
P64	SE	1/4-1/2	2057	Lower	UNKNOWN	UST	U003053857	N/A
					3101 CATHEDRAL AV NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	1-001670		
					Owner:	CATHCONN ASSOCIATES LTD		
Q65	WSW	1/4-1/2	2207	Higher	UNKNOWN	UST	U003055084	N/A
					3008 32ND ST NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	3-004495		
					Owner:	UNKNOWN		
Q66	SW	1/4-1/2	2217	Higher	UNKNOWN	UST	U003055083	N/A
					3008 32ND ST NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	3-004494		
					Owner:	UNKNOWN		
R67	SSE	1/4-1/2	2223	Lower	UNKNOWN	UST	U003054914	N/A
					2828 CONNECTICUT AV NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	3-001776		
					Owner:	DC FIRE PREVENTION BRANCH		
88	SW	1/4-1/2	2240	Higher	UNKNOWN	UST	U003054858	N/A
					3101 GARFIELD ST NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	3-000843		
					Owner:	3060 M ST. LIMITED PARTNERSHIP		

Map ID	Direction	Distance	Distance (ft.)	Elevation	Site	Database(s)	EDR ID Number	EPA ID Number
MAP FINDINGS								
R69	SSE	1/4-1/2	2251	Lower	APARTMENT BUILDING	UST	U003111903	N/A
					2824 CONNECTICUT NW			
					WASHINGTON, DC 20008			
					UST:			
					Facility ID:	3-001775		
					Owner:	NATHAN KOTZ		
S70	NNW	1/4-1/2	2261	Higher	3701 CONNECTICUT AVE NW AT AN APARTMENT BUILDING	ERNS	8718877	N/A
					3701 CONNECTICUT AVE NW AT AN APARTMENT BUILDING			
					WASHINGTON, DC			
S71	NNW	1/4-1/2	2262	Higher	3701 CONNECTICUT AV CONDO ASSOC	UST	U002109891	N/A
					3701 CONNECTICUT AV NW			
					WASHINGTON, DC 20005			
					UST:			
					Facility ID:	3-001821		
					Owner:	3701 CONNECTICUT AVENUE		
S72	NNW	1/4-1/2	2270	Higher	3002 ROOMAN ST	HMIRS	87110027	N/A
					WASHINGTON, DC			
S73	NNW	1/4-1/2	2322	Higher	3701 CT AVE NW APARTMENT BUILDING	ERNS	8718876	N/A
					3701 CT AVE NW APARTMENT BUILDING			
					WASHINGTON DC (County), DC			
S74	NNW	1/4-1/2	2326	Higher	SEDGWICK GARDENS	UST	U003294465	N/A
					3726 CONNECTICUT AV NW			
					, DC 20008			
					UST:			
					Facility ID:	3-001793		
					Owner:	DARO REALTY INC		
75	WSW	1/4-1/2	2341	Higher	ARTHUR MEIGS	UST	U002109677	N/A
					3224 CATHEDRAL AV NW			
					WASHINGTON, DC 20008			

Map ID Direction Distance Distance (ft) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	ARTHUR MEIGS (Continued)		U002109677
	UST: Facility ID: 3-000010 Owner: ARTHUR MEIGS		
T76 SW 1/4-1/2 2357 Higher	RALPH BECKER 2916 32ND ST NW WASHINGTON, DC 20008	UST	U002110064 N/A
	UST: Facility ID: 3-004356 Owner: UNKNOWN		
T77 SW 1/4-1/2 2361 Higher	UNKNOWN 2914 32ND ST NW WASHINGTON, DC 20008	UST	U003055082 N/A
	UST: Facility ID: 3-004493 Owner: UNKNOWN		
T78 SW 1/4-1/2 2363 Higher	UNKNOWN 2912 32ND ST NW WASHINGTON, DC 20008	UST	U003055041 N/A
	UST: Facility ID: 3-004354 Owner: UNKNOWN		
T79 SW 1/4-1/2 2369 Higher	UNKNOWN 2907 32ND ST NW WASHINGTON, DC 20008	UST	U003055040 N/A
	UST: Facility ID: 3-004353 Owner: UNKNOWN		
80 South 1/4-1/2 2380 Lower	UNKNOWN 2800 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055155 N/A
	UST: Facility ID: 3-005049 Owner: DC FIRE PREVENTION BRANCH		

Map ID Direction Distance Distance (ft) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
81 WSW 1/4-1/2 2459 Higher	UNKNOWN 3307 WOODLEY RD NW WASHINGTON, DC 20008	UST	U003055156 N/A
	UST: Facility ID: 3-005050 Owner: UNKNOWN		
U82 SW 1/4-1/2 2536 Higher	UNKNOWN 3200 GARFIELD ST NW WASHINGTON, DC 20008	UST	U003054859 N/A
	UST: Facility ID: 3-000844 Owner: 30/60 M ST. LIMITED PARTNERSHIP		
U83 SW 1/4-1/2 2536 Higher	UNKNOWN 3201 GARFIELD ST NW WASHINGTON, DC 20008	UST	U003054857 N/A
	UST: Facility ID: 3-000842 Owner: 30/60 M ST. LIMITED PARTNERSHIP		
84 West 1/4-1/2 2548 Higher	MICHAEL MEAGHER 3301 MACOMB ST NW WASHINGTON, DC 20008	UST	U003054813 N/A
	UST: Facility ID: 3-000050 Owner: MICHAEL MEAGHER		
85 SSE 1/4-1/2 2552 Lower	UNKNOWN 2751 WOODLEY PL NW WASHINGTON, DC 20008	UST	U003054058 N/A
	UST: Facility ID: 3-005048 Owner: UNKNOWN		
86 NNW 1/4-1/2 2556 Higher	UNKNOWN 3801 CONNECTICUT AV NW WASHINGTON, DC 20008	UST	U003054939 N/A

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	UNKNOWN (Continued)		U003054939
	UST: Facility ID: 3-001820 Owner: DC FIRE PREVENTION BRANCH		
87 SW 1/4-1/2 2582 Higher	UNKNOWN 3148 CLEVELAND AV NW WASHINGTON, DC 20008	UST	U003054908 N/A
	UST: Facility ID: 3-001739 Owner: 3024 TILDEN ST NW		
88 SSE 1/4-1/2 2583 Lower	ST THOMAS THE APOSTLE CHURCH 2665 WOODLEY RD NW WASHINGTON, DC 20008	UST	U002110240 N/A
	UST: Facility ID: 3-005044 Owner: UNKNOWN		
89 SSE 1/2-1 2844 Lower	CALVERT WOODLEY APARTMENTS 2601 WOODLEY RD NW WASHINGTON, DC 20008	UST LUST	U002110239 N/A
	LUST: Case Number: 90030 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-005043 Owner: CALVERT WOODLEY COMPANY		
90 South 1/2-1 3143 Lower	CLEVELAND HOUSE 2727 29TH ST NW WASHINGTON, DC 20008	UST LUST	U002110042 N/A
	LUST: Case Number: 96105 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-004306 Owner: SMITH PROPERTY HOLDINGS (DC) LP		

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
91 SSE 1/2-1 3542 Lower	CALVERT HOUSE APTS. 2401 CALVERT ST NW WASHINGTON, DC 20009	UST LUST	U002109704 N/A
	LUST: Case Number: 96047 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-000182 Owner: H. G. SMITHY COMPANY		
V92 NNW 1/2-1 4293 Higher	UDC OIL SPILL 1997 SITE 4200 CONNECTICUT AVE. NW WASHINGTON, DC 20008	CERCLIS FINDS	1001126463 DC0001900000
	CERCLIS Classification Data: Site Incident Category: Not reported Ownership Status: Not reported Site Description: THE SITE IS LOCATED IN A HIGHLY COMMERCIAL/RESIDENTIAL AREA IN THE NORTHWEST SECTION OF WASH. DC. SOAPSTONE CREEK IS APPROXIMATELY 500 FT IN AN EASTERLY DIRECTION FROM THE UNIVERSITY Federal Facility: Not reported NPL Status: Not reported		
	CERCLIS Assessment History: Assessment: DISCOVERY Assessment: REMOVAL ASSESSMENT Assessment: UNILATERAL ADMIN ORDER Assessment: PRELIMINARY ASSESSMENT Completed: 19970118 Completed: 19970226 Completed: 19970226 Completed: 19991014		
	CERCLIS Site Status: NFRAP (No Further Remedial Action Planned)		
	FINDS: Other Pertinent Environmental Activity Identified at Site: Enforcement Docket System (DOCKET)		
V93 NNW 1/2-1 4369 Higher	TEXACO 4225 CONNECTICUT AV NW WASHINGTON, DC 20008	UST LUST	U002109752 N/A
	LUST: Case Number: 89013 Facility Status: Case Closed Product: D		
	UST: Facility ID: 3-000685 Owner: KOO L YUEN		
94 North 1/2-1 4406 Lower	ROYAL NETHERLANDS EMBASSY 4200 LINNEAN AV NW WASHINGTON, DC 20008	UST LUST	U003054815 N/A

Map ID Direction Distance Distance (ft) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
	ROYAL NETHERLANDS EMBASSY (Continued)		U003054815
	LUST: Case Number: 96003 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-000056 Owner: ROYAL NETHERLANDS EMBASSY		
95 SSW 1/2-1 4670 Lower	BRITISH EMBASSY 3100 MASSACHUSETTS AV NW WASHINGTON, DC 20008	UST LUST	U002109701 N/A
	LUST: Case Number: 90065 Facility Status: Case Closed Product: G,H		
	UST: Facility ID: 3-000154 Owner: BRITISH EMBASSY		
96 WSW 1/2-1 4674 Higher	SAINT SOPHIA CHURCH 38TH / MASS. AVE, NW WASHINGTON, DC	LUST	S100008090 N/A
	LUST: Case Number: 91007 Facility Status: Case Closed Product: H		
97 WSW 1/2-1 5000 Higher	ALBAN TOWERS 3700 MASSACHUSETTS AV NW WASHINGTON, DC 20016	UST LUST	U002109938 N/A
	LUST: Case Number: 99117 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-002175 Owner: DC FIRE PREVENTION BRANCH		
98 WSW 1/2-1 5073 Higher	GARFIELD HOUSE APARTME 2844 WISCONSIN AVE NW WASHINGTON, DC	LUST	S102509236 N/A

Map ID Direction Distance Distance (ft) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
	GARFIELD HOUSE APARTME (Continued)		S102509236
	LUST: Case Number: 97005 Facility Status: Case Open Product: H		
99 SE > 1 5525 Lower	1768 COLUMBIA ROAD ASSOC LLC 1768 COLUMBIA RD NW WASHINGTON, DC 20009	UST LUST	U003053831 N/A
	LUST: Case Number: 96041 Facility Status: Case Closed Product: H		
	UST: Facility ID: 1-001545 Owner: 1768 COLUMBIA ROAD ASSOC LLC		
W100 NNW > 1 5622 Higher	CHARLES E SMITH REALTY PROPERTY 4411 CONNECTICUT AV NW DC 20008	UST LUST	U003377565 N/A
	LUST: Case Number: 98108 Facility Status: Case Open Product: H		
W101 NNW > 1 5622 Higher	SOAPSTONE CREEK OIL SPILL RESPONSE 4411 CONNECTICUT AVE., NW WASHINGTON, DC 20008	CERCLIS	1001230489 DCSFN0305387
	CERCLIS Classification Data: Site Incident Category: Not reported Ownership Status: Not reported CERCLIS Assessment History: Assessment: DISCOVERY CERCLIS Site Status: Not reported	Federal Facility NPL Status: Not reported Completed: 19980710	
102 SW > 1 5732 Higher	CARILLON HOUSE 2500 WISCONSIN AVENUE, N WASHINGTON, DC 20007	LUST	U003054812 N/A
	LUST: Case Number: 93053 Facility Status: Case Closed Product: H		

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
103 West > 1 5736 Higher	ANNUNCIATION CATHOLIC CHURCH 3125 39TH ST NW WASHINGTON, DC 20016	UST LUST	U002109940 N/A
	LUST: Case Number: 96043 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-002177 Owner: ANNUNCIATION CATHOLIC CHURCH		
104 SW > 1 5811 Higher	AMOCO OIL CO S/S #3478 2450 WISCONSIN AV NW WASHINGTON, DC 21201	UST LUST	U002109683 N/A
	LUST: Case Number: 90040 Facility Status: Case Closed Product: G		
	UST: Facility ID: 3-000016 Owner: AMOCO OIL CO		
105 NNW > 1 6075 Higher	CONNECTICUT HOUSE 4500 CONNECTICUT AV NW WASHINGTON, DC 20008	UST LUST	U002109887 N/A
	LUST: Case Number: 91026 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-001828 Owner: CONNECTICUT HOUSE ASSOC LTD PART		
106 East > 1 6270 Lower	CROMWELL APARTMENTS 1515 OGDEN ST NW WASHINGTON, DC 20010	UST LUST	U002107498 N/A
	LUST: Case Number: 93004 Facility Status: Case Closed Product: H		
	UST: Facility ID: 1-000003 Owner: 1515 OGDEN ST LTD PARTNERSHIP		

Map ID Direction Distance Distance (ft.) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
107 SE > 1 6397 Lower	2100 COOPERATIVE ASSOC 2100 19TH ST, NW , DC	LUST	S102834889 N/A
	LUST: Case Number: 88010 Facility Status: Case Closed Product: H		
108 SE > 1 6413 Lower	AMOCO OIL CO S/S #84665 2307 CHAMPLAIN ST NW WASHINGTON, DC 20009	UST LUST	U002107506 N/A
	LUST: Case Number: 91058 Facility Status: Case Open Product: G.D		
	UST: Facility ID: 1-000014 Owner: AMOCO OIL CO		
109 West > 1 6472 Higher	CATHEDRAL AVENUE COOP 4101 CATHEDRAL AVE., NW WASHINGTON, DC	LUST	S100521467 N/A
	LUST: Case Number: 93042 Facility Status: Case Closed Product: H		
110 WSW > 1 6557 Higher	3900 TUNLAW COOPERATIVE 3900 TUNLAW COOPERATIVE WASHINGTON, DC 20007	UST LUST	U002109676 N/A
	LUST: Case Number: 92044 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-000009 Owner: 3900 TUNLAW COOPERATIVE		
X111 WSW > 1 6562 Higher	3900 WATSON PLACE INC. 3900 WATSON PL NW WASHINGTON, DC 20016	UST LUST	U002110158 N/A

Map ID Direction Distance Distance (ft) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	3900 WATSON PLACE INC. (Continued)		U002110158
	LUST: Case Number: 95035 Facility Status: Case Closed Product: H		
	UST: Facility ID: 3-004889 Owner: 3900 WATSON PLACE INC		
X112 WSW > 1 6562 Higher	WATSON PLACE CONDOMI 3900 WATSON PLACE, NW WASHINGTON, DC	LUST	S100008144 N/A
	LUST: Case Number: 92008 Facility Status: Case Closed Product: H		
113 SSE > 1 6609 Lower	WASHINGTON HILTON HOTEL & TOWERS 1919 CONNECTICUT AV NW WASHINGTON, DC 20009	UST LUST	U003053874 N/A
	LUST: Case Number: 97029 Facility Status: Case Open Product: H		
	UST: Facility ID: 1-001770 Owner: THE WASHINGTON HILTON HOTEL & TO		
114 ESE > 1 6867 Lower	DORCHESTER HOUSE APART 2480 16TH ST, NW WASHINGTON, DC	LUST	S101403098 N/A
	LUST: Case Number: 91037 Facility Status: Case Closed Product: H		
115 SSE > 1 6905 Lower	UNIVERSAL NORTH BLDG 1875 CONNECTICUT AVE NW WASHINGTON, DC 20009	RCRIS-SQG LUST	1000886511 DC0000228593

Map ID Direction Distance Distance (ft) Elevation	Site	Database(s)	EDR ID Number EPA ID Number
	UNIVERSAL NORTH BLDG (Continued)		1000886511
	RCRIS: Owner: CAFRITZ COMPANY (202) 986 6300		
	Contact: DONALD FISHER (202) 986 6300		
	Record Date: 03/28/1994		
	Classification: Conditionally Exempt Small Quantity Generator		
	Used Oil Recyc: No		
	Violation Status: No violations found		
	LUST: Case Number: 94020 Facility Status: Case Open Product: H		
116 West > 1 6984 Higher	BERKSHIRE APARTMENTS 4201 MASSACHUSETTS AV NW WASHINGTON, DC 20016	UST LUST	U003054821 N/A
	LUST: Case Number: 95075 Facility Status: Case Open Product: H		
	UST: Facility ID: 3-000102 Owner: BERKSHIRE APARTMENTS		
117 SE > 1 7078 Lower	DIPLOMAT APARTMENTS 2420 16TH ST NW WASHINGTON, DC 20009	UST LUST	U002107835 N/A
	LUST: Case Number: 98062 Facility Status: Case Closed Product: H		
	UST: Facility ID: 1-002902 Owner: DIPLOMAT ASSOC LP DARALA INC GP		
118 ENE > 1 7093 Lower	TWIN OAKS APTS - 3800 3800 14TH STREET, NW WASHINGTON, DC	LUST	S101403124 N/A
	LUST: Case Number: 91070 Facility Status: Case Open Product: H		

Map ID Direction Distance Distance (ft) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
119 ESE > 1 7109 Lower	AMOCO OIL CO (FORMER) 3037 14TH ST NW WASHINGTON, DC 21230	UST LUST	U002107508 N/A
	LUST: Case Number: 97044 Facility Status: Case Closed Product: G UST: Facility ID: 1-000031 Owner: AMOCO OIL CO		
Y120 SSE > 1 7225 Lower	AMERICAN GEOPHYSICAL U 2000 FLORIDA AVE, NW , DC	LUST	S102834861 N/A
	LUST: Case Number: 92026 Facility Status: Case Open Product: G,H		
Y121 SSE > 1 7234 Lower	PRESIDENT MADISON APPA 1908 FLORIDA AVE, NW WASHINGTON, DC	LUST	S100521466 N/A
	LUST: Case Number: 93040 Facility Status: Case Closed Product: D		
122 SE > 1 7275 Lower	ADAMS MORGAN FOREIGN CAR SERVICE 1781 FLORIDA AV NW , DC 20009	UST LUST	U003294591 N/A
	LUST: Case Number: 99001 Facility Status: Case Open Product: W UST: Facility ID: 9 000145 Owner: ADAMS MORGAN FOREIGN CAR SERVICE		
123 ESE > 1 7435 Lower	FAIRMONT LTD PARTNERS 1401 FAIRMONT ST., NW , DC	LUST	S102834795 N/A

Map ID Direction Distance Distance (ft) Elevation	MAP FINDINGS	Database(s)	EDR ID Number EPA ID Number
	FAIRMONT LTD PARTNERS (Continued)		S102834795
	LUST: Case Number: 94075 Facility Status: Case Closed Product: H		
124 WSW > 1 7543 Higher	ARCHIBALD GLOVER PARK OUTFALL OIL SPILL 42ND & EDMUND STREET, N.W. WASHINGTON, DC 20024	CERCLIS FINDS	1001114749 DC0001405067
	CERCLIS Classification Data: Site Incident Category: Not reported Ownership Status: Not reported CERCLIS Assessment History: Assessment: DISCOVERY Assessment: REMOVAL ASSESSMENT CERCLIS Site Status: Not reported	Federal Facility: Not reported NPL Status: Not reported Completed: 19960222 Completed: 19960223	
125 NNW > 1 7555 Higher	ESSEX CONDO 4740 CONNECTICUT AV NW WASHINGTON, DC 20008	UST LUST	U002109763 N/A
	LUST: Case Number: 93028 Facility Status: Case Closed Product: H UST: Facility ID: 3-000753 Owner: ESSEX CONDO		
126 ESE > 1 7693 Lower	AMOCO 2600 14TH STREET, NW WASHINGTON, DC 20009	LUST	U002107512 N/A
	LUST: Case Number: 97032 Facility Status: Case Open Product: G		

ORPHAN SUMMARY

City	EDR ID	Site Name	Site Address	Zo	Databases(s)	Facility ID
WASHINGTON	100094120	SOAP STONE CREEK	4500 ALBEMARLE ST.	20008	CERC-NFRAP	
WASHINGTON	90164233	BURNT WOOD ROAD NE AT FLORIDA AVE.	BURNT WOOD ROAD NE AT FLORIDA AVE.	ERNS	ERNS	
WASHINGTON	1001814062	GLOVER BRIDGE SITE	CONNELT CUT AVENUE BETWEEN -	20008	CERCLIS	
WASHINGTON	8855694	NATIONAL ARBORETUM BLADENSBURG ROAD NE	NATIONAL ARBORETUM BLADENSBURG ROAD	ERNS	ERNS	
WASHINGTON	971229	PARK ROAD AND BEACH DRIVE	PARK ROAD AND BEACH DRIVE	ERNS	ERNS	
WASHINGTON	U003055030	UNKNOWN	2128 30TH ST NW	20008	UST	3-004323
WASHINGTON	U003255163	UNKNOWN	2981 WOODLEY RD NW	20008	UST	3-005057